

REGIONAL INTERESTS DEVELOPMENT APPROVAL SUPPORTING DOCUMENT

Ensham Life of Mine Extension
Zone 2 and Zone 3

Prepared for:

Bligh Coal Limited, Idemitsu Australia Pty Ltd and Bowen Investment (Australia) Pty
Ltd
Level 9/175 Eagle Street
Brisbane
QLD 4000

SLR Ref: 620.30686.00600-R01
Version No: -v4.0
L\343884466.1



PREPARED BY

SLR Consulting Australia Pty Ltd
ABN 29 001 584 612
Level 16, 175 Eagle Street
Brisbane QLD 4000 Australia
(PO Box 26 Spring Hill QLD 4004)
T: +61 7 3858 4800
E: brisbane@slrconsulting.com www.slrconsulting.com

BASIS OF REPORT

This report has been prepared by SLR Consulting Australia Pty Ltd (SLR) with all reasonable skill, care and diligence, and taking account of the timescale and resources allocated to it by agreement with Bligh Coal Limited, Idemitsu Australia Pty Ltd and Bowen Investment (Australia) Pty Ltd (the Client). Information reported herein is based on the interpretation of data collected, which has been accepted in good faith as being accurate and valid.

This report is for the exclusive use of the Client. No warranties or guarantees are expressed or should be inferred by any third parties. This report may not be relied upon by other parties without written consent from SLR.

SLR disclaims any responsibility to the Client and others in respect of any matters outside the agreed scope of the work.

CONTENTS

1	INTRODUCTION	6
1.1	Project Description.....	8
1.1.1	Mining Techniques.....	9
1.1.2	Flare Construction	10
1.1.3	Flare Exclusion Areas	11
1.2	Purpose	14
2	REGULATORY CONSIDERATIONS	17
2.1	Regional Planning Interests Act 2014.....	17
2.2	Regional Planning Interests Regulation 2014	17
2.2.1	Priority Agricultural Area (RPI Regulation, Schedule 2, Part 2)	17
2.2.2	Strategic Cropping Area (RPI Regulation, Schedule 2, Part 4)	18
2.3	Central Queensland Regional Plan.....	19
2.3.1	Regional Outcomes and policies.....	19
2.4	Public Notification.....	20
2.4.1	Avoiding duplication of notification.....	20
2.4.2	Previous public notification.....	21
3	ASSESSMENT AGAINST RPI GUIDELINES	25
4	ASSESSMENT AGAINST RPI REGULATION REQUIRED OUTCOMES	42
4.1	Priority Agricultural Area (RPI Regulation, Schedule 2, Part 2)	42
4.2	Strategic Cropping Area (RPI Regulation, Schedule 2, Part 4)	54
5	EXISTING ENVIRONMENT	56
5.1	Land Use within the Project	56
5.2	Property.....	56
5.3	Land Resources Assessment	56
5.3.1	Subsidence	56
5.3.2	Dispersive Soils	57
5.3.3	Land Suitability and Agricultural Land Classes	57
6	POTENTIAL IMPACTS	60
6.1	Flare Exclusion Zones	60
6.1.1	Rehabilitation	60
6.2	Subsidence.....	60
6.2.1	Impacts	60
6.2.2	Natural Variation	62

CONTENTS

6.3	Surface Impacts to Areas of Regional Interest	62
7	CONCLUSIONS	63
8	REFERENCES	64

CONTENTS

DOCUMENT REFERENCES

TABLES

Table 1	Tenure Ownership	8
Table 2	Avoiding Duplication of Public Notification	21
Table 3	RIDA RPI Guideline Checklist	26
Table 4	Zone 2 PALU Assessment Results	42
Table 5	PALU Site Photo Presentation	43
Table 6	Prescribed Solutions for RO1 – PAA	44
Table 7	Mapped PALU Area – 2011 Satellite Imagery	46
Table 8	Mapped PALU Area – 2013 Satellite Imagery	47
Table 9	Mapped PALU Area – 2015 Satellite Imagery	48
Table 10	Mapped PALU Area – 2017 Satellite Imagery	49
Table 11	Mapped PALU Area – 2018 Satellite Imagery	50
Table 12	Mapped PALU Area – 2019 Satellite Imagery	51
Table 13	Mapped PALU Area – 2020 Satellite Imagery	52
Table 14	Mapped PALU Area – 2021 Satellite Imagery	53
Table 15	Prescribed Solutions for RO2 – SCA.....	54
Table 16	Areas of ARI for the Project.....	62

FIGURES

Figure 1	Project Location.....	7
Figure 2	Bord and Pillar Mining Conceptual Overview	10
Figure 3	Flares and flare exclusion areas	12
Figure 4	Mine plan of underground workings	13
Figure 5	Priority Agricultural Area	15
Figure 6	Strategic Cropping Area via Strategic Cropping Land Trigger Map	16
Figure 7	Land Use.....	58
Figure 8	Underlying Property Ownership.....	59
Figure 9	Pre-Mining Panel (Station 502_3) Vertical Surface Movement	61
Figure 10	Underground Mining Panel (Station 502_1): Measured Subsidence Levels.....	61

APPENDICES

Appendix A	Project Description and Alternatives
Appendix B	Fodder Frequency Mapping
Appendix C	Land Resource Report
Appendix D	Subsidence Report
Appendix E	Subsidence Management Plan
Appendix F	Peer Review Letter - Subsidence Report
Appendix G	Peer Review Letter - Subsidence Management Plan

1 Introduction

The Ensham Joint Venture (Ensham JV) partners are proposing to develop the Ensham Life of Mine Extension Project to extend the life of the existing underground operations into an area identified as Zones 2 and 3 (the Project) as shown on Figure 1. The existing Ensham Mine is operated by Ensham Resources Pty Ltd (Ensham), a wholly owned subsidiary of Idemitsu Australia Pty Ltd, on behalf of the Ensham JV partners. The Ensham JV partners, and holders of the Environmental Authority (EA), are Bligh Coal Limited (ACN 010186393) (47.5 per cent), Idemitsu Australia Pty Ltd (ACN 010236272) (37.5 per cent) and Bowen Investment (Australia) Pty Ltd (ACN 002806831) (15 per cent). The Ensham JV partners are the Proponents for the Project. Ensham currently operates the existing mine under EA EPML00732813. The Applicants for the RIDA are the Ensham Joint Venture Partners

This document has been prepared to support an application for a Regional Interests Development Approval (RIDA) under section 29 of the Regional Planning Interests Act 2014 (RPI Act). The application seeks approval to allow the construction (4 flares only) and the extension of the existing underground resource activity which is mapped within a priority agricultural area (PAA) and strategic cropping area (SCA) in reference to the RPI Act.

Ensham is an existing open-cut and underground bord and pillar coal mine located 35 kilometres (km) east of Emerald in Central Queensland. Existing bord and pillar operations are located on mining lease (ML) 7459, ML 70326 and ML 70365, targeting the Aries/Castor coal seam plies.


The Project entails the following major components, both described in more detail in the Project Description (Section 1.1):

- Extension of the existing underground mine activities
- Construction of four (4) gas drainage flares to safely manage methane gas levels within the underground mine.

Approval of the Project will allow Ensham to:

- Continue to produce at current coal production rate of approximately 4.5 million tonnes per annum (Mtpa) of product coal. Without the additional Project area, the current underground operations will become physically constrained resulting in lower production levels that will impact the overall economic viability of the mine and consequently the workforce
- Extend the life of mine (LOM) by two years with sufficient coal reserves to approximately 2029
- Progress the underground operation within existing mining leases. The Project would continue to utilise existing operational mine equipment, existing mining methodologies, and existing infrastructure located on the existing mining leases
- Continue to provide ongoing direct and indirect employment opportunities within the Central Highlands region.

The Project is proposed to commence in late H1 2022 in Zone 2. This supporting document represents the assessment of the Project against the RPI Act, Schedule 2, Part 2 of the RPI Regulation, the RPI Statutory Guidelines and Chapter 4 of the Central Queensland Regional Plan.



Coordinate System: GDA 1994 MGA Zone 55
 Scale: 1:150,000 at A4
 Project Number: 620.30686
 Date: 14-Mar-2022
 Drawn by: JG

- Roads
- Zone 2
- Zone 3
- Mining Leases

**620.30686 ENSHAM RIDA
 SUPPORTING DOC**

Project Location



FIGURE 1

1.1 Project Description

This section summarises the Project, which is presented in further detail in Appendix A (Project description and Alternatives).

Ensham proposes to increase the life of the existing underground operations by extending the underground bord and pillar mine into the area identified as the Project. The Project covers approximately 603 hectares (ha) and includes two zones as seen in Figure 1:

- Zone 2: partially includes existing leases ML 70326, ML 70365, and ML 7459. The surface area of the northern portion of Zone 2 is largely disturbed with large areas of cleared land and includes seismic lines and tracks. It contains areas of certified and uncertified rehabilitated spoil as well as unrehabilitated spoil and pre-strip areas from open-cut mining.
- Zone 3: partially includes existing leases ML 7459 and ML 70366. The surface area of Zone 3 is disturbed land with borrow pits, dragline spoil, levees, topsoil stockpiles, pre-strip areas, tracks, and seismic lines associated with the existing open-cut operations at Ensham Mine. It is largely cleared with sparse stands of vegetation across the area.

The tenure ownership of the lots inside the Project are identified in Table 1.

Table 1 Tenure Ownership

Lot	Zone	Owner
Lot 31 CP864573	Zone 2	BLIGH COAL LIMITED - PO BOX 301 BRISBANE QLD 4001 BOWEN INVESTMENT (AUSTRALIA) PTY LTD - PO BOX 301 BRISBANE QLD 4001 IDEMITSU AUSTRALIA PTY LTD - PO BOX 301 BRISBANE QLD 4001
Lot 32 RP908643	Zone 2	BLIGH COAL LIMITED - PO BOX 301 BRISBANE QLD 4001 BOWEN INVESTMENT (AUSTRALIA) PTY LTD - PO BOX 301 BRISBANE QLD 4001 IDEMITSU AUSTRALIA PTY LTD - PO BOX 301 BRISBANE QLD 4001
Lot 33 RP864576	Zone 3	BLIGH COAL LIMITED - PO BOX 301 BRISBANE QLD 4001 BOWEN INVESTMENT (AUSTRALIA) PTY LTD - PO BOX 301 BRISBANE QLD 4001 IDEMITSU AUSTRALIA PTY LTD - PO BOX 301 BRISBANE QLD 4001

Lot	Zone	Owner
Lot 30 CP864574	Zone 3	BLIGH COAL LIMITED - PO BOX 301 BRISBANE QLD 4001 BOWEN INVESTMENT (AUSTRALIA) PTY LTD - PO BOX 301 BRISBANE QLD 4001 IDEMITSU AUSTRALIA PTY LTD - PO BOX 301 BRISBANE QLD 4001


1.1.1 Mining Techniques

The surface area above the Project has been subject to activities associated with the open-cut mine since the grant of the mining leases in 1994. Ensham proposes to mine Zone 2 and 3 using the existing bord and pillar mining method.

This underground mining system forms stable coal pillars and roadways in each panel to avoid large scale overburden fracturing and subsidence (Gordon Geotechniques, 2022). A concept drawing is shown in Figure 2.

As shown in this diagram, the bord and pillar method generates bords (roadways) and pillars which are maintained to minimise the risk of subsidence. Excavation is carried out using the continuous miner cutting machine, which loads the coal into a shuttle car machine. The shuttle car then transports the coal and loads onto the conveyor belt system. Once the bord is excavated to the end of the drive (i.e. the primary working), the miner is reversed and additional coal may be taken from the roof and/or floor of the panel when retreating (i.e. the secondary working) to meet the maximum allowable extraction. Then continuous miner is moved to the next mining sequence. The subsidence assessment has been undertaken on the secondary workings basis (i.e. the maximum subsidence predicted). This mining technique does not involve the removal of any pillars.

Figure 2 Bord and Pillar Mining Conceptual Overview



The proposed bord and pillar mining method results in a better environmental outcome compared to longwall mining with respect to subsidence, which will in turn reduce future land degradation.

In order for proposed mine operations to be conducted safely, the construction, installation and use of gas drainage flares will be required for the Project. The flares will be used for safety mitigation and are required to drain methane gas from underground mining operations to create a safe working environment. Flares generate a lower environmental impact than free venting as required under Mineral Resources Act 1989, due to the methane in the gas being combusted by the flare to form CO₂ which has a GHG footprint that is approximately 28 times lower compared to free venting as methane.

1.1.2 Flare Construction

Standard flare installation procedures will be employed in line with risk assessments to reduce the hazards of combustible material within an exclusion zone around the flare. This typically involves slashing the adjacent grass, and laying a base of gravel around the flare. Drilling to the coal seam must occur before the hole is cemented, which will allow gas to drain towards the surface. Minor quantities of drilling muds will be disposed of in accordance with appropriate rehabilitation methods. Gas is then ignited at a safe distance above the surface. Each flare would be approximately 8 m tall with the flare height (i.e. height of the ignited gas flame) being up to 3 m above the flare.

Each flare will be established in already cleared locations which are already approved for disturbance under the current EA. Flares will be constructed and operated at a time consistent with the mining schedule.



1.1.3 Flare Exclusion Areas

No additional material infrastructure other than installation of four flares will be required. For safety, the installation of the flares includes an exclusion zone. The flare exclusion area will be fenced to prohibit wildlife and people from unauthorised entry. This exclusion area would be established on previously disturbed land and would not require any vegetation clearing (other than maintenance of grass levels to minimise fire risk). These locations would utilise existing tracks on existing mining leases for non-material construction purposes as well as ongoing general access and maintenance matters.

There are two flare exclusion areas proposed in each zone, which therefore total four exclusion areas in total. Each flare exclusion area is 80 m by 20 m, which equates to 0.16 hectares (ha). The location of each flare within the Project and their respective exclusion areas are shown in Figure 3.

The flares, and their exclusion areas, are the critical components of this RIDA. The four flares are located within mapped priority agricultural area (PAA); of the four flares, one flare is located within mapped strategic cropping area (SCA) as discussed in Section 6.1. Further information in relation to the exclusion areas and the extent of the PAA and SCA is detailed in Section 2.

The proposed mine plan of underground workings is shown in Figure 4.




Coordinate System: GDA 1994 MGA Zone 55
 Scale: 1:50,000 at A4
 Project Number: 620.30686
 Date: 10-May-2022
 Drawn by: JG

● Flare Exclusion Areas
 (80m x 20m)

□ Zone 2
 □ Zone 3

**620.30686 ENSHAM RIDA
 SUPPORTING DOCUMENT**

Flares and Flare Exclusion Areas



Coordinate System: GDA 1994 MGA Zone 55
 Scale: 1:50,000 at A4
 Project Number: 620.30686
 Date: 23-Feb-2022
 Drawn by: JG



- Current Underground Mine Workings
- Existing Mine Pits
- Zone 2
- Zone 3
- Mining Leases
- Approved Underground Workings

Proposed Underground Mine

- 2021
- 2022
- 2023
- 2024
- 2025
- 2026
- 2027
- 2028
- 2029

**620.30686 ENSHAM RIDA
 SUPPORTING DOCUMENT**

Mine Plan of Underground Workings

FIGURE 4

1.2 Purpose



The purpose of this document is to support the Assessment Application for a RIDA under the RPI Act. The Assessment Application for a RIDA is being submitted by the Applicants for the following reasons:

1. A RIDA is being sought to obtain approval under the RPI Act to carry out a resource activity in an area of regional interest
2. To assess the Project's impact on areas of regional interest, as required by Section 29 (b) of the RPI Act

This application demonstrates that there will be no material impact to mapped PAA or SCA, and that Required Outcome 1 (RO1) under Schedule 2 of the Regional Planning Interests Regulation 2014 (RPI Regulation) for PAA (Part 2) and RO2 for SCA (Part 4) is achieved by the Project. Refer to Section 4 for further details.

For the purpose of this application, the status of the PAA and SCA ('as mapped') within the Project is not being challenged. The Project, comprising the continuation of underground mining into Zones 2 and 3, is entirely within the mapped PAA and partially within SCA. The Project area in relation to mapped PAA and mapped SCA is outlined on Figure 5 and Figure 6 respectively.

An assessment of the Project against the ROs under the RPI Regulation is provided under Section 4. A summary of the existing environment at the Project area is provided under Section 5 and potential impacts of the Project to PAA and SCA is discussed under Section 6.



Coordinate System: GDA 1994 MGA Zone 55
 Scale: 1:70,000 at A4
 Project Number: 620.30686
 Date: 12-May-2022
 Drawn by: JG





- Flare Exclusion Areas (80m x 20m)
- Zone 2
- Zone 3
- Mining Leases
- Underground Mine Workings
- Approved Underground Workings

620.30686 ENSHAM SOIL SURVEY

Priority Agricultural Area

FIGURE 5



Coordinate System: GDA 1994 MGA Zone 55
 Scale: 1:70,000 at A4
 Project Number: 620.30686
 Date: 22-Apr-2022
 Drawn by: JG



- Flare Exclusion Areas (80m x 20m)
- Strategic Cropping Land
- Zone 2
- Zone 3
- Mining Leases
- Underground Mine Workings
- Approved Underground Workings

620.30686 ENSHAM SOIL SURVEY

Strategic Cropping Area via
 Strategic Cropping Land Trigger Map

FIGURE 6

2 Regulatory Considerations

2.1 Regional Planning Interests Act 2014

The RPI Act identifies and protects areas in Queensland that are of 'regional interest'. The RPI Act outlines the requirement for a RIDA for resource activities carried out in ARIs, other than exempt resource activities. Four ARIs are identified by the RPI Act as follows:

- A PAA – an area which includes one or more areas used for a priority agricultural land use (PALU). A PALU is highly productive agriculture of a type identified in a Regional Plan for an ARI or of a type prescribed under a regulation for an ARI
- A priority living area (PLA) – an area mapped as a PLA and exists as a settled area of a city, town or other community and other areas deemed necessary or desirable
- The SCA – an area shown on the Strategic Cropping Land (SCL) trigger map as SCL. SCL is defined as land that is, or which is likely to be highly suitable for cropping, because of a combination of the land's soil, climate and landscape features
- A strategic environmental area (SEA) – an area with strategic environmental value which is either shown on a map in a Regional Plan or prescribed by regulation, where there is a quality or characteristic of the environment that is conducive to ecological health or public amenity.

Of the ARIs protected by the RPI Act, PAA and SCA are mapped within the Project.

2.2 Regional Planning Interests Regulation 2014

The RPI Regulation underpins the RPI Act and defines criteria for assessment of impacts to ARIs. Schedule 2 of the RPI Regulation details important definitions of ARIs, 'Required Outcomes' (ROs) and 'Prescribed Solutions' for impacts to ARIs. The ROs relevant to the Project are outlined below.

2.2.1 Priority Agricultural Area (RPI Regulation, Schedule 2, Part 2)

The RPI Regulation (Schedule 2, Part 1) states the definition of land use which is considered as a PALU. For land to be considered 'used' for a PALU, the land must have been used for a PALU for 'at least three years during the ten years immediately preceding the assessment application'.

The RPI Regulation also outlines the following ROs:

- Required outcome 1—managing impacts on use of property for priority agricultural land use in priority agricultural area
- Required outcome 2—managing impacts on a region in relation to use of an area in the region for a priority agricultural land use.

An assessment of potential PALUs and the assessment against ROs has been outlined under Section 4.1.

2.2.2 Strategic Cropping Area (RPI Regulation, Schedule 2, Part 4)

The RPI Regulation (Schedule 2, Part 4) outlines the following ROs for the SCA:

- Required outcome 1— no impact on strategic cropping land
- Required outcome 2— managing impacts on strategic cropping land on property (SCL) in the strategic cropping area
- Required outcome 3— managing impacts on strategic cropping land for a region.

An assessment against ROs has been outlined under Section 4.2.

2.3 Central Queensland Regional Plan

The Central Queensland Regional Plan (CQ Regional Plan) provides strategic direction and policies to deliver regional outcomes which align with the state's interests in planning and development.

The plan provides policy responses to resolve the most important issues affecting Central Highlands economy and the liveability of its towns. The plan specifically provides direction to resolve competing state interests relating to the agricultural and resources sectors, and to enable the growth potential of the region's towns. The regional policies aim to:

- Protect Priority Agricultural Land Uses while supporting co-existence opportunities for the resources sector,
- Provide certainty for the future growth of towns.

The purpose of the plan is to identify the state's interests in land use planning for the region. Specifically, the plan identifies:

- regional outcomes for the region
- regional policies for achieving the regional outcomes
- the state's intent for the future spatial structure of the region, including PAA, PLA and priority outcomes for infrastructure.

The plan's regional policies address the emerging regional issues of land use competition between the agricultural and resources sectors, and the need to protect areas required for the growth of towns.

The plan also discusses other state interests relevant to land use planning in the region, including housing and liveable communities, economic growth, environment and heritage, and hazards and safety.

2.3.1 Regional Outcomes and policies

The Central Queensland region's greatest competitive industry strengths are in supporting coal mining, Coal Seam Gas (CSG)/Liquid Natural Gas (LNG) and agricultural sectors.

Resolving the conflict between agriculture and the resources sector is crucial to the long-term sustainability of both industries and ultimately the region's economy. Impacts on the productivity of agricultural land from resource activities can include direct land take, changes to land access, loss or degradation of soil, subsidence and overland flow modifications. Within Zones 2 and 3, the possible effect on the PAA and SCA results from subsidence as a result of mining activities. Subsidence impacts are discussed further in Section 6.2.

Surface effects that may be associated with the construction of each flare represent a very small amount of the PAA/SCA inside the Project and are unlikely to incur material changes to the landscape (refer to Table 16 for the extent of disturbance on ARI for the Project).

The regional outcomes and policies contained in the CQ Regional Plan align with and advance the achievement of the state's interest in relation to:

- supporting the long-term viability and growth of the agricultural sector
- maximising the productive use of key mining resources
- providing for liveable communities.

In relation to agriculture, the first Regional Outcome states that “Agriculture and resources industries within the Central Queensland region continue to grow with certainty and investor confidence” (CQ Regional Plan, 2013).

The regional outcome is supported by the regional policies (CQ Regional Plan, 2013), whereby the policies aim to protect PALU while supporting co-existence opportunities for the resources sector. These are stated as follows from the CQ Regional Plan:

- Regional policy 1: Protect Priority Agricultural Land Uses within Priority Agricultural Areas
- Regional policy 2: Maximise opportunities for co-existence of resource and agricultural land uses within Priority Agricultural Areas.

PAAs are identified and mapped in the CQ Regional Plan and comprise of the region’s strategic areas containing highly productive agricultural land uses. PALUs within the PAA are recognised as the primary land use and are given priority over any other proposed land use.

The Project site and land surrounding is predominantly used for a mix of cropping and grazing purposes, alongside existing mining operations. The Project will disturb a total of 0.64 ha for the 4 flares and their exclusion areas. Underground mining using the bord and pillar mining method coupled with utilizing existing infrastructure further supports the Project’s approach to minimising surface disturbance.

Each area will be rehabilitated post-mining as the flare stack will be safely deconstructed and the exclusion area rehabilitated to its previous land use. The effects of each exclusion area are discussed more in Section 6. The Project satisfies the Regional Policy 1 and Regional Policy 2 outcomes, as no PALU is impacted by the Project and agricultural lands uses will continue for the duration of the Project.

2.4 Public Notification

2.4.1 Avoiding duplication of notification

Under Section 34 (3) of the RPI Act ‘the chief executive may, on the written request of the applicant, grant an exemption from notification for an assessment application if satisfied there has been sufficient notification under another Act or law of the resource activity or regulated activity to the public’.

The RPI Act Statutory Guideline 06/14 Public notification of assessment applications outlines that it is not the intention of the Government to repeat notification of a proposed activity where notification has been undertaken as part of another process (i.e. an EIS process under the State Development and Public Works Organisation Act 1971 or the Environmental Protection Act 1994) and where that notification included detailed information of the proposed activity and its relationship to the areas of regional interest impacted.

While the Assessment Application is not a notifiable assessment application, Ensham considers that no requirement to notify the application should be made, on the basis that sufficient public notification has occurred under legislation other than the RPI Act.

2.4.2 Previous public notification

The Ensham Life of Mine Extension Project was issued final Terms of Reference (ToR) in November 2020, which required the assessment of the potential impacts of the Project land uses on SCA and PAA (refer to Section 9.2 of the final ToR). The Environmental Impact Statement (EIS) was submitted on 12 March 2021, then publicly notified under Section 51 and 52 of the Environmental Protection Act 1994 for a 6-week public submission period commencing 27 April 2021 and concluded on 8 June 2021. DES received a total of 29 submissions in respect of the EIS. All submissions were responded to, and the submissions register was provided to DES on 13 August 2021 along with the Amended EIS addressing the matters raised in the submissions.

An EIS Assessment Report was subsequently issued by DES on 9 November 2021, outlining that the EIS is largely compliant with the final ToR and that a RIDA is required under the RPI Act.

The Ensham Life of Mine Extension Project's referral under the Environment Protection and Biodiversity Act 1999 (Cth) (EPBC Act) was also published on the Department of Agriculture, Water and the Environment website on 29 May 2020.

The RPI Act Statutory Guideline 06/14 Public notification of assessment applications outline requirements for an assessment application to avoid duplication of notification, an assessment against the guideline criteria is provided in Table 2.

Table 2 Avoiding Duplication of Public Notification

RPI Act Section 34(3)	RPI Act Statutory Guideline 06/15 Public notification of assessment application	Criteria Met (Yes/No)	Evidence of Addressed Criteria
The chief executive may, on the written request of the applicant, grant an exemption from notification for an assessment application if satisfied there has been sufficient notification under another Act or law of the resource activity or regulated activity to the public.	The period between the previous public notification and the receipt of the application under the RPI Act does not exceed 12 months.	Yes	The EIS was publicly notified for a submission period commencing 27 April 2021 and concluded on 8 June 2021. This application has been made within the 12 months of this date.
	The publicly notified activity or project included the land the subject of the application made under the RPI Act.	Yes	<p>The EIS included the land the subject of this application being the areas identified as Zone 2 and 3 within approved mining leases ML 70326, ML 70365, ML 70366 and ML 7459. The scope of mining for Zones 2 and 3 in this application covers the same Zones 2 and 3 scope that was assessed in the EIS. The land is described in Chapter 4 – Project Description and Chapter 7 – Land Use and Tenure of the EIS.</p> <p>The EPBC Act referral also included the land comprising Zones 2 and 3 as described in section 1.6 of the referral form.</p>

	<p>The publicly notified activity or project detailed the surface area impacts of the activity the subject of the application made under the RPI Act.</p>	Yes	<p>The EIS addressed the potential surface area impacts to PAA and SCA in Zones 2 and 3. These are the same areas and activities outlined in this application. Surface area impacts are outlined in the following chapters of the EIS:</p> <ul style="list-style-type: none"> Chapter 7 Land Use and Tenure – Section 7.3.3 identifies that the potential impacts to the PAA and SCA are considered to be minor on the following basis: <ul style="list-style-type: none"> (a) land use impacts associated with the Project will be minor as surface disturbance is limited to flaring infrastructure in Zones 2 and 3; (b) predicted subsidence of up to 40mm as a result of the Project is less than the estimated seasonal variation in surface levels as a result of changes in moisture content; and (c) there is no potential loss and/or fragmentation of rural agricultural land. Chapter 8 – Land Resources. Section 8.5.3 addresses the impacts on the soil noting that: <ul style="list-style-type: none"> (a) the proposed activities are to occur on land that is highly disturbed and will not involve vegetation clearing; and (b) subsidence is predicted to be within the expected levels of natural ground swell variation and is unlikely to result in the formation of significant depressions in the surface topography. <p>The EPBC Act referral also outlined the surface area impacts in relation to the activities proposed in Zones 2 and 3 as described in the supporting technical report for matters of national environmental significance - section 2.0. Particularly, it is noted that surface cracking is not predicted above the Project</p>
--	---	-----	---

RPI Act Section 34(3)	RPI Act Statutory Guideline 06/15 Public notification of assessment application	Criteria Met (Yes/No)	Evidence of Addressed Criteria
			area due to the predicted low levels of maximum surface disturbance.
	The publicly notified activity or project provided sufficient information about matters relating to an area of regional interest.	Yes	<p>The EIS provided sufficient information in relation to the PAA and SCA in Zones 2 and 3. These are the same areas and activities outlined in this application. Refer to the following chapters of the EIS:</p> <ul style="list-style-type: none"> Chapter 4 – Project Description, and Chapter 8 – Land Resources. <p>The EPBC Act referral also provided information in respect of the PAA and SCA as described in section 1.5 of the referral form. Both processes required public notification and all responses to submissions were advertised and presented on Idemitsu Australia's website at the following location:</p> <p>https://www.idemitsu.com.au/mining/project/s/ensham-life-of-mine-extension-project/</p>

Prior to the preparation of the EIS, Ensham undertook a comprehensive stakeholder consultation process and engaged stakeholders at both local and regional levels regarding the potential environmental impacts of the Project.

The Applicants have actively engaged with a range of stakeholders during the preparation of the Environmental Impact Statement (EIS), which ensured that stakeholders had the opportunity to comment on Zone 2 and Zone 3 issues and concerns that relate to them.

Stakeholders identified included:

- Local communities – people who live and work in Emerald, Comet and nearby townships/localities
- Landowners/impacted neighbours – those overlying or neighbouring the Project's proposed mining lease area
- Non-government organisations – social services providers and community organisations, including local allied health and aged care providers
- Indigenous groups – the Western Kangoulou People and the Garingbal and Kara Kara People
- State government departments and agencies – those with the decision-making power and services in the Project's nearby communities
- CHRC – the Mayor, Councillors and Council executives
- Ensham JV partner employees – those working at the existing mine
- Industry bodies – Central Highlands Development Corporation.

Stakeholder engagement and consultation for the EIS was undertaken from June 2020 to November 2020. On 29 January 2020, the Queensland Government declared a public health emergency in Queensland in response

to the COVID-19 pandemic. Given the restrictions in place during the public health emergency declaration, an initial round of engagement via online means was undertaken in early-mid 2020, followed by face-to-face meetings and community workshops in October 2020 when some restrictions were eased.

A number of submissions were made following a 6 week advertising period during the public notice period. Responses to all submissions were subsequently made by Ensham and were submitted to the Department of Environment and Science (DES). DES then issued an EIS Assessment Report (the Report) in November 2021 incorporating a number of recommendations. Recommendations from this Report have subsequently been incorporated into the Zone 2 and 3 Environmental Authority amendment documents as submitted.

Consultation aimed to provide information on the Project, identifying any issues or concerns, seeking feedback and providing responses.

The Applicants will continue stakeholder engagement activities as documented in the Community and Stakeholder Engagement Plan to inform Project development and management, build on established relationships throughout the community, and build on an existing reputation as an operator that is genuinely committed to the well-being and sustainability of the community.

For the reasons outlined above and Table 2, Ensham considers that there has been sufficient public notification completed under the EP Act and EPBC Act in relation to the activities that will be undertaken as part of the Project.

3 Assessment Against RPI Guidelines

The RIDA application are informed by the RPI Act and RPI Regulation. The RPI Guidelines are used to aid the compliance with the RPI Act and RPI Regulation. The RPI Guidelines cover all elements of the RIDA process, however not all guidelines are relevant to each individual application. As the proposed construction and mining footprints are being conducted within PAA and SCA mapped land, this RIDA Application has been assessed against the following RPI Guidelines:

- RPI Act guideline 01/14 - How to make an assessment application under the RPI Act
- RPI Act guideline 02/14 - Carrying out activities in priority agricultural area
- RPI Act guideline 03/14 - Carrying out activities in the strategic cropping area
- RPI Act guideline 06/14 - Notification requirements under the RPI Act
- RPI Act guideline 07/14 - How to identify a priority agricultural land use
- RPI Act guideline 09/14 - How to determine if an activity has a permanent impact on strategic cropping land

There are several other RPI Act guidelines available, however these are not relevant to the Project and this RIDA supporting document. Table 3 provides a list all relevant RPI Guideline items to be addressed, how they have been addressed and where further detail can be found within the RIDA application.

Table 3 RIDA RPI Guideline Checklist

RPI Guideline	Reference in RPI Guideline	Requirement	Guideline met? (Yes/No)	Explanation is how guideline is met	Document Reference
01/14	Page 3, Paragraph 2	Assessment must be made in the approved form	Yes	Assessment is in the approved form by DSDILGP	Application Form
01/14	Page 3, Paragraph 2	Assessment must be accompanied by a report containing essential supporting information	Yes	Supporting document prepared	This document
01/14	Page 3, Paragraph 2	Assessment must be accompanied by the applicable fee.	Yes	Ensham provided the correct fee	Application Form
01/14	Page 3, Paragraph 3	Assessment application must be made by 'an eligible person'.	Yes	An eligible person is someone who holds, or has applied for, or can apply for an EA or a resource authority for the resource activity - Ensham is such a person. This is due to Ensham being a wholly owned subsidiary of Idemitsu Australia Pty Ltd.	Section 1 of the Supporting Document
01/14	Page 4, Paragraph 2	The applicant must complete all sections of the assessment application form for a regional interests development approval.	Yes	All sections completed	Application Form

RPI Guideline	Reference in RPI Guideline	Requirement	Guideline met? (Yes/No)	Explanation is how guideline is met	Document Reference
01/14	Page 4, Paragraph 4	Real property descriptions and contact details for the owner of the land must be provided. (The land that is the subject of the application comprises all lots/properties including any part of a lot on which the activities are proposed).	Yes	Correct information provided for property owners and their contact details	Application Form – Section 2
01/14	Page 4, Paragraph 5	Locality maps and site plans showing the locations of the land that is the subject of the application and the lots on plan will be necessary.	Yes	Maps and spatial data provided to DSDILGP showcasing the land subject to the application	Application Form -Section 4
01/14	Page 4, Paragraph 6	Under section 29 of the RPI Act an assessment application is required to be accompanied by an assessment application report. Other supporting information outlined in the form includes maps, site plans, GIS data files and other relevant documents.	Yes	All supporting documentation provided	Supporting Document - all relevant information attached

RPI Guideline	Reference in RPI Guideline	Requirement	Guideline met? (Yes/No)	Explanation is how guideline is met	Document Reference
01/14	Page 4, Paragraph 7	Detailed information on the location, nature, extent (in hectares) and duration of the surface impacts of the proposed activity is required to enable the assessment of the impact of the activity on the area of regional interest	Yes	This is provided in the supporting document	Section 1 & 6 of the Supporting Document
01/14	Page 4, Paragraph 8	The report accompanying the assessment application must include a description of the impact of the proposed activities on the feature, quality, characteristic or other attribute of the area and a table identifying the location and surface area of each proposed activity.	Yes	This is provided in the supporting document	Section 1 & Section 6 of the Supporting Document
01/14	Page 4, Paragraph 9	The report must also include an explanation of how the proposed activity will meet the required outcome/s and address the prescribed solution/s contained in the assessment criteria for the area of regional interest.	Yes	This is provided in the supporting document	Section 4 of the Supporting Document

RPI Guideline	Reference in RPI Guideline	Requirement	Guideline met? (Yes/No)	Explanation is how guideline is met	Document Reference
01/14	Page 4, Paragraph 11	It is recommended that as much information is included in the original application so that DSDILGP does not have to issue a requirement notice seeking additional information. This process may delay your approval as it extends the statutory timeframes for a decision.	Yes	All supporting documentation will be provided	This checklist, as well as across all application documents
01/14	Page 4, Paragraph 12	The application must identify the source of the information provided, including whether the information was provided by an owner other than the applicant	Yes	The application information is sourced from the Applicants who are also the land owners	Across all application documents
01/14	Page 4, Paragraph 12	The application must state whether an owner other than the applicant agrees to the information being made publicly available on the DSDILGP website	Yes	The Applicants are the land owners	Section 5.2 of the Supporting Document
01/14	Page 5, Paragraph 1	IF YES TO ABOVE - provide the express written agreement of that owner to the information being made publicly available on the DSDILGP website.	Yes	Not applicable as the Applicants are the land owners	Not applicable

RPI Guideline	Reference in RPI Guideline	Requirement	Guideline met? (Yes/No)	Explanation is how guideline is met	Document Reference
01/14	Page 5, Paragraph 3	<p>Locality Maps must show:</p> <ul style="list-style-type: none"> • the land that is the subject of the application • cadastral boundaries of all properties including the subject of the application and adjoining properties • the area of regional interest, and the feature, quality, characteristic or other attribute of the area of regional interest • the existing land use and infrastructure within the area of surface impact (for example, structures, roads, power lines, irrigation channels) • the existing land use on surrounding land within a one-kilometre radius of the boundaries of the land which is the subject of the application • areas identified for special consideration (for example, restricted land around residences, critical business infrastructure, vegetation and regional ecosystems, natural or modified watercourses and 	Yes	This is provided in the supporting document and application form	Application form -Sections 1, 3 and 4

RPI Guideline	Reference in RPI Guideline	Requirement	Guideline met? (Yes/No)	Explanation is how guideline is met	Document Reference
		wetlands protected under state legislation) • a north point, scale and contours.			
01/14	Page 5, Paragraph 5	Site plans will need to indicate the location, nature and extent of each proposed activity in relation to: <ul style="list-style-type: none"> • the land which is the subject of the application, and the expected area of impact • the area/s of regional interest • the feature, quality, characteristic or other attribute of the area of regional interest e.g. each PALU or each environmental attribute • existing infrastructure e.g. a house, shed, roads, access ways, easements, existing CSG well • overland flow and drainage paths • property boundaries • land constraints e.g. vegetation, underground infrastructure, electricity transmission lines 	Yes	This is provided in the supporting document and application form	Application form -Sections 1, 3 and 4

RPI Guideline	Reference in RPI Guideline	Requirement	Guideline met? (Yes/No)	Explanation is how guideline is met	Document Reference
		<ul style="list-style-type: none"> a north point, scale and contours. 			
01/14	Page 5, Paragraph 7	Other documentation to aid the government in understanding the impacts of the proposed activity	Yes	Information included as appendixes to the Supporting Document	Appendix B Fodder Frequency Mapping Appendix C Land Resource Report Appendix D Subsidence Report Appendix E Subsidence Management Plan Appendix F Peer Review Letter - Subsidence Report Appendix G Peer Review Letter - Subsidence Management Plan
02/14	Page 4, Paragraph 7	One example of where an activity may be considered not likely to have a significant impact on a PAA may be where the activity will not: <ul style="list-style-type: none"> result in a decrease in the particular agricultural product supplied from the PAA or region 	Yes	The activity does not impact either of these examples given	Section 4.1 of the Supporting Document

RPI Guideline	Reference in RPI Guideline	Requirement	Guideline met? (Yes/No)	Explanation is how guideline is met	Document Reference
		<ul style="list-style-type: none"> result in a decrease in the PAA or region's ability to undertake a particular PALU in the future. 			
02/14	Page 5, Paragraph 2	An assessment application for a Regional Interests Development Approval is required to be made to the chief executive of the Department State Development, Manufacturing, Infrastructure and Planning (DSDILGP) in the approved form.	Yes	RIDA application is in the approved form	RIDA made in the approved form
02/14	Page 5, Paragraph 2	The RPI Act requires that the assessment application must be accompanied by a report and the applicable fee.	Yes	RIDA has accompanied report and fee	RIDA has accompanied report and fee
02/14	Page 5, Paragraph 3	The report must assess the activity's impact on the Priority Agricultural Area and identify any constraints on the configuration or operation of the activity.	Yes	PAA is discussed at length in the supporting document, particularly regarding the activity's impact (or lack of (in Ensham's case)) on the PAA	Section 4.1 and 6of the Supporting Document

RPI Guideline	Reference in RPI Guideline	Requirement	Guideline met? (Yes/No)	Explanation is how guideline is met	Document Reference
02/14	Page 5, Paragraph 4	A single application may seek approval for multiple activities across multiple areas of regional interest. In this instance, the application will need to address each applicable set of assessment criteria prescribed in Schedule 2 of the RPI Regulation.	Yes	The supporting document encompasses PAA and SCA in the same application	PAA and SCA discussed throughout Supporting Document
02/14	Page 5, Paragraph 6	A pre-application meeting is strongly recommended to discuss a proposed activity that is located in an area of regional interest.	Yes	Pre-application meeting has been performed and discussion points raised have been actioned from that	Pre-application meeting undertaken on 11 February 2022
02/14	Page 6, Paragraph 1	The PAA Assessment Criteria apply and will need to be addressed if an applicant proposes to locate an activity in a PAA.	Yes	Inside PAA and is addressed in Supporting Document	Section 4.1 of the Supporting Document
02/14	Page 7, Table 1, Paragraph 4	Comply with Required Outcome 1 for Prescribed Solution 1 (Table 1) - The application should include shape files and relevant GIS data	Yes	PAA land inside the Project has not been used as a PALU "for at least 3 years during the 10 years immediately before an assessment application"	Section 4.1 of the Supporting Document

RPI Guideline	Reference in RPI Guideline	Requirement	Guideline met? (Yes/No)	Explanation is how guideline is met	Document Reference
02/14	Page 7, Table 1, Paragraph 3	The key steps to determine whether land is used for a PALU are: 1. identify the properties that are impacted 2. identify the location of PALU on each property 3. determine the time period associated with each PALU.	Yes	These steps have been completed. An area in the southwest extent of Zone 2 is mapped as a PALU, however it has been determined this area is not considered PALU and is classified as '3.2.2 Grazing modified pastures' (Woody fodder plants - woody plants used primarily for the purpose of providing forage for livestock grazing) .	Section 4.1 of the Supporting Document
02/14	Page 6, Paragraph 3	Required Outcome 1: The activity will not result in a material impact on the use of the property for a PALU	Yes	All items are addressed in the supporting document (outlined in doc from Table 1 and Table 2 in 02/14)	Section 4.1 of the Supporting Document
02/14	Page 6, Paragraph 4	Required Outcome 2: The activity will not result in a material impact on the region because of the activity's impact on the use of land in the PAA for 1 or more PALUs	Yes	Not relevant to this Project - addressed in supporting document	Section 4.1 of the Supporting Document
03/14	Page 4, Paragraph 9	An assessment application for a regional interests development approval is required to be lodged with the Chief Executive	Yes	RIDA made in the approved form	RIDA made in the approved form

RPI Guideline	Reference in RPI Guideline	Requirement	Guideline met? (Yes/No)	Explanation is how guideline is met	Document Reference
		of DSDILGP in the approved form			
03/14	Page 4, Paragraph 9	The assessment application must be accompanied by a report and the applicable fee.	Yes	RIDA has accompanied report and fee	RIDA has accompanied report and fee
03/14	Page 4, Paragraph 10	The report must assess the activity's impact on the SCA and identify any constraints on the configuration or operation of the activity. The activity's impact on the SCA will be assessed against the SCA Assessment Criteria	Yes	SCA is discussed at length in the supporting document, particularly regarding the activity's impact (or lack of (in Ensham's case)) on the SCA	Section 4.2 of the Supporting Document

RPI Guideline	Reference in RPI Guideline	Requirement	Guideline met? (Yes/No)	Explanation is how guideline is met	Document Reference
03/14	Page 5, Paragraph 7	Where an application is for an activity that is to be carried out on land within the SCA and all or part of the land overlaps with land used for a priority agricultural land use (PALU) in a priority agricultural area (PAA), the assessor only needs be satisfied the activity meets the applicable PAA assessment criteria in deciding the application (relevant to the overlapping land). That is, whether the SCA criteria are met or not is not relevant in deciding that part of the application for where the overlap occurs, however the SCA criteria must be met for all areas where no overlap occurs.	Yes	All SCA land in the Project overlaps with the PAA land. SCA criteria has been satisfied by the PAA criteria in this assessment (as the activity meets the applicable PAA assessment criteria in deciding the application).	Section 4 of the Supporting Document
03/14	Page 6, Paragraph 1	Required Outcome 1: The activity will not result in any impact on strategic cropping land in the strategic cropping area.	Yes	Not relevant to the Project as the some of the activity will impact on the SCA.	Section 4.2 of the Supporting Document

RPI Guideline	Reference in RPI Guideline	Requirement	Guideline met? (Yes/No)	Explanation is how guideline is met	Document Reference
03/14	Page 6, Paragraph 2	Required outcome 2: The activity will not result in a material impact on strategic cropping land on the property (SCL).	Yes	All items are addressed in the supporting document (outlined in doc from Table 2 and Table 3 in 03/14).	Section 4.2 of the Supporting Document
03/14	Page 6, Paragraph 3	Required outcome 3: The activity will not result in a material impact on strategic cropping land in an area in the strategic cropping area. E.g. the activity is being carried out over more than one property (SCL) in the strategic cropping area	Yes	Not relevant to the Project as the activity is proposed over a single property within the SCA.	Section 4.2 of the Supporting Document
06/14	Page 3, Paragraph 1	The RPI Act requires an assessment application to be publicly notified if: a) the proposed resource activity is in a Priority Living Area (as stated in the Regional Planning Interests Regulation 2014 (RPI Regulation)) or b) the chief executive has given the applicant a requirement notice requiring the applicant to notify the application.	Yes	The Project is not in a PLA and the chief executive has not given the applicant a requirement notice requiring the applicant to notify the application	Section 2.4 of the Supporting Document

RPI Guideline	Reference in RPI Guideline	Requirement	Guideline met? (Yes/No)	Explanation is how guideline is met	Document Reference
06/14	Page 3, Paragraph 6	Avoiding duplication of notification: It is not the intention to repeat notification of a proposed activity where notification has been undertaken as part of another process (e.g., the EIS process under the State Development and Public Works Organisation Act 1971 or the Environmental Protection Act 1994) and where that notification included detailed information of the proposed activity and its relationship to the area/s of regional interest impacted.	Yes	Notification addressed in supporting document	Section 2.4 of the Supporting Document
06/14	Page 3, Paragraph 7	Section 34(3) of the RPI Act provides that an exemption from notification can be granted by the chief executive where a request is made in writing and the chief executive is satisfied that there has been sufficient notification of the activity completed under another act or law.	Yes	Notification addressed in supporting document	Section 2.4 of the Supporting Document

RPI Guideline	Reference in RPI Guideline	Requirement	Guideline met? (Yes/No)	Explanation is how guideline is met	Document Reference
06/14	Page 3, Paragraph 8	<p>Generally, any previous public notification of a proposed activity or project would need to meet the following criteria to be considered sufficient public notification for the purposes of Section 34(3) of the RPI Act:</p> <ul style="list-style-type: none"> • the period between the previous public notification and the receipt of the application under the RPI Act does not exceed 12 months • the publicly notified activity or project included the land the subject of the application made under the RPI Act • the publicly notified activity or project detailed the surface area impacts of the activity the subject of the application made under the RPI Act • the publicly notified activity or project provided sufficient information about matters relating to an area of regional interest. For example, existing land uses on the site and the 	Yes	All of these subpoints are addressed in the supporting document	Section 2.4 of the Supporting Document

RPI Guideline	Reference in RPI Guideline	Requirement	Guideline met? (Yes/No)	Explanation is how guideline is met	Document Reference
		impact of the proposed resource activity on the town.			
06/14	Page 3, Paragraph 9	If an applicant intends to request an exemption from notification from the chief executive, it is recommended that this request be included in the application upon lodgement and be accompanied by justification.	Yes	Exemption from notification made inside the application	Section 2.4 of the Supporting Document
06/14	Page 3, Paragraph 10	Where it is determined sufficient public notification has been undertaken under another process, consideration of the relevant matters raised in submissions received as part of the publicly notified activity or project would be considered by the chief executive in the decision of the application made under the RPI Act.	Yes	Evidence of prior public notification given in the supporting document	Section 2.4 of the Supporting Document

4 Assessment Against RPI Regulation Required Outcomes

4.1 Priority Agricultural Area (RPI Regulation, Schedule 2, Part 2)

Required Outcome 1

- An assessment of the underlaying land against the requirements of RPI Act Guideline 7/14 has been completed, and considers the following from this guideline:
- Step 1 Identify what properties the applicant proposes to impact upon
- Step 2 Identify whether the impacted properties are being (or have recently been) used for a PALU, and
- Step 3 Determine the time period of impact associated with the operation of each PALU at each property.
- The requirements of the RPI Act Guideline 7/14 are addressed below.

Identification of Properties

Lots underlying the Project are continuous between Zone 2 and 3 and are commonly owned by Bligh Coal Ltd, Bowen Investment (Australia) Pty Ltd and Idemitsu Australia Pty Ltd. Bligh Coal Ltd, Bowen Investment (Australia) Pty Ltd and Idemitsu Australia Pty Ltd have confirmed that these lots are operated as a single agricultural enterprise, principally cattle grazing. Property ownership and status is further discussed under Section 5.2.

PALU Identification

A search of the Ag Trends Spatial data mapping indicates that the land in the south-west portion of Zone 2 is used as irrigated pasture (refer to Section 5.1), which may qualify this area of land as a PALU. Land use identified over all other areas of Zone 2 and Zone 3 does not qualify as potential PALU under RPI Act Guideline 7/14 and as confirmed by Ensham these areas have been used historically for cattle grazing.

Forage Frequency Mapping

A review of the forage frequency mapping (provided as Appendix B), showed that between 2012 and 2021, cropping frequency occurred two or fewer times over the last ten years within Zone 2. Table 4 summarises the results from the forage report.

Table 4 Zone 2 PALU Assessment Results

Frequency Type	2012-2021
Estimated Total Crop Frequency	2 or fewer
Estimated Frequency map for summer (February) crops	2 or fewer
Estimated Frequency map for Winter (September) crops	2 or fewer
Estimated Frequency Summer (February) Coarse grain and pulse crops	2
Estimated Frequency Summer (February) Cotton crops	2 or fewer
Estimated Frequency Winter (September) Cereal crops	2 or fewer

Frequency Type	2012-2021
Estimated Frequency Winter (September) Pulse crops	2 or fewer

Site Inspection

A site inspection took place on 19 November 2021 within Zone 2 (55 648554 m E, 7405873 m N). The dominant land use identified was grazing woody fodder plants (*Leucaena*). The panorama photos in Table 5 show the view of north, east, south and west.

Table 5 PALU Site Photo Presentation



PALU History Identification

Review of the available historical satellite imagery, property history (the Applicants are the owners of the underlying property) and site observations to date were taken into account as provided by Ensham. This review

determined that the mapped portion of irrigated pasture (i.e. potential PALU) in Zone 2 has been utilised for dryland cropping of Leucaena for grazing of cattle. In addition, land use identified over all other areas of Zone 2 and Zone 3 does not qualify as PALU under RPI Act Guideline 7/14, as Ensham has confirmed these areas have been used historically for cattle grazing.

Historical Imagery

The analysis of historical satellite imagery considered available images for 2011, 2013, 2015, 2017, 2018, 2019, 2020 and 2021 and is outlined in Table 7 to Table 714. The image for 2011 shows cropping activity in the southwest of Zone 2. The Applicants purchased the underlying property in the early 1990s and the Leucaena was planted in 2008. This cropping activity, Ensham confirms, was dryland cropping of Leucaena (a fodder crop). Ensham further confirms that this area has continued to be cropped with Leucaena and grazed by cattle since 2011 and has not been irrigated (i.e. is rainfed). As such, as outlined by the RPI Act Statutory Guideline 07/14, this area is not considered PALU and is classified as '3.2.2 Woody fodder plants - woody plants used primarily for the purpose of providing forage for livestock grazing'. In any case, no material impact will result in this area, as discussed in detail under Section 6.

RO1 requires that that an activity will not result in material impact on the use of the property in a PALU. Prescribed Solutions for RO1 state various solutions for deciding if the activity impacts on PAA. It has been determined that the Project satisfies all prescribed solutions for RO1, as outlined under Table 6.

Table 6 Prescribed Solutions for RO1 – PAA

Prescribed Solutions for RO1 (Schedule 2, Part 2, Section 3 – RPI Regulation)	Response
(2) The application demonstrates the activity will not be located on land that is used for a priority agricultural land use.	No activities are proposed on land that is used for a PALU. Underground workings beneath this land will result, however no material impacts will result at surface (Refer to Section 6.2).
(3) The application demonstrates all of the following:	-
(a) if the applicant is not the owner of the land and has not entered into a voluntary agreement with the owner— (i) the applicant has taken all reasonable steps to consult and negotiate with the owner about the expected impact of carrying out the activity on each priority agricultural land use for which the land is used; and (ii) carrying out the activity on the property will not result in a loss of more than 2% of both— (A) the land on the property used for a priority agricultural land use; and (B) the productive capacity of any priority agricultural land use on the property;	Not applicable. The Applicants are the owners of underlying property (refer to Section 5.2).

Prescribed Solutions for RO1 (Schedule 2, Part 2, Section 3 – RPI Regulation)	Response
(b) the activity can not be carried out on other land that is not used for a priority agricultural land use, including, for example, land elsewhere on the property, on an adjacent property or at another nearby location;	No activities are proposed on land that is used for a PALU. UG workings beneath this land will result and no material impact will result at surface (Refer to Section 6.2). Further, the Project is constrained by the location of the resource.
(c) the construction and operation footprint of the activity on the part of the property used for a priority agricultural land use is minimised to the greatest extent possible;	Ensham have minimised surface impacts to this land to the greatest degree possible by only proposing the bare minimum surface infrastructure required and proposing the bord and pillar UG mining technique, which will result in no material impacts at surface (Refer to Section 6.2). No other surface infrastructure is proposed, and the current use of this land will continue through the life of the mine.
(d) the activity will not constrain, restrict or prevent the ongoing conduct on the property of a priority agricultural land use, including, for example, everyday farm practices and an activity or infrastructure essential to the operation of a priority agricultural land use on the property;	UG workings beneath this land will result, however no material impacts will result at surface (Refer to Section 6.2).
(e) the activity is not likely to have a significant impact on the priority agricultural area;	There is no significant impact on the PAA. UG workings beneath this land will result in no material impacts at surface (Refer to Section 6.2). The property underlying the Project will continue to be available for dryland cropping for the life of the Project.
(f) the activity is not likely to have an impact on land owned by a person other than the applicant or the land owner mentioned in paragraph (a).	The Applicants are the owners of underlying property (refer to Section 5.2). The activity will result in no material impacts at surface and no impacts to adjacent land owned by others will result.

Required Outcome 2

RO2 is not relevant to the Project as the activity is proposed over a single property within the PAA. Refer to Section 5.2.

Table 7 Mapped PALU Area – 2011 Satellite Imagery


Photo Information	Land Use Description
Date: 29 May 2011 Source: NearMap Imagery 2022	Grazing woody fodder plants (Leucaena)
	

Table 8 Mapped PALU Area – 2013 Satellite Imagery


Photo Information	Land Use Description
Date: 7 August 2013 Source: Google Earth Satellite Imagery	Grazing woody fodder plants (Leucaena)
	

Table 9 Mapped PALU Area – 2015 Satellite Imagery


Photo Information	Land Use Description
Date: 2015 Source: Ensham	Grazing woody fodder plants (Leucaena)
	

Table 10 Mapped PALU Area – 2017 Satellite Imagery


Photo Information	Land Use Description
<p>Date: Range: 01 July -30 Sept 2017 Source: Queensland Satellite Data QSat 2017 240cm Planet Q3 Image L16 – 7473E-3546N Image L16 – 7474E-3546N</p>	<p>Grazing woody fodder plants (Leucaena)</p>
	

Table 11 Mapped PALU Area – 2018 Satellite Imagery


Photo Information	Land Use Description
Date: 31 August 2018 Source: Google Earth Professional 2022	Grazing woody fodder plants (Leucaena)
 <p>Image © 2022 CNES / Airbus</p>	

Table 12 Mapped PALU Area – 2019 Satellite Imagery

Photo Information	Land Use Description
Date: 16 June 2019 Source: Google Earth Professional 2022	Grazing woody fodder plants (Leucaena)
 <p>Image © 2022 Maxar Technologies</p>	

Table 13 Mapped PALU Area – 2020 Satellite Imagery


Photo Information	Land Use Description
Date: 2020 Source: Ensham	Grazing woody fodder plants (Leucaena)
	

Table 14 Mapped PALU Area – 2021 Satellite Imagery

Photo Information	Land Use Description
Date: 2021 Source: Ensham	Grazing woody fodder plants (Leucaena)
	

4.2 Strategic Cropping Area (RPI Regulation, Schedule 2, Part 4)

Required Outcome 1

RO1 is not relevant to the Project.

Required Outcome 2

RO2 requires that the activity not result in a material impact on SCL on the property. Prescribed solutions for RO2 state solutions for deciding if the activity impacts on SCL in the SCA. It has been determined that the Project satisfies all of the prescribed solutions for RO2 and will not result in a material impact to SCL on the property, as outlined under Table 15.

Importantly, lots underlying the Project are continuous between Zone 2 and 3 and are commonly owned by Bligh Coal Ltd, Bowen Investment (Australia) Pty Ltd and Idemitsu Australia Pty Ltd. Bligh Coal Ltd, Bowen Investment (Australia) Pty Ltd and Idemitsu Australia Pty Ltd have confirmed that these lots are operated as a single agricultural enterprise, principally cattle grazing. Property ownership and status is further discussed under Section 5.2.

Table 15 Prescribed Solutions for RO2 – SCA

Prescribed Solutions for RO2 (Schedule 2, Part 4, Section 11 – RPI Regulation)	Response
The application demonstrates all of the following—	-
(a) if the applicant is not the owner of the land and has not entered into a voluntary agreement with the owner—the applicant has taken all reasonable steps to consult and negotiate with the owner of the land about the expected impact of carrying out the activity on strategic cropping land;	Not applicable. Ensham is the owner of underlying property (refer to Section 5.2).
(b) the activity cannot be carried out on land that is not strategic cropping land, including, for example, land elsewhere on the property (SCL), on adjacent land or at another nearby location;	Underground workings beneath this land will result in no material impacts to mapped SCA areas (Refer to Section 6.2). The Project is constrained by the location of the resource.
(c) the construction and operation footprint of the activity on strategic cropping land on the property (SCL) is minimised to the greatest extent possible;	Ensham have minimised surface impacts to this land to the greatest degree possible by only proposing the bare minimum surface infrastructure required (i.e. one flare in Zone 3 is located on SCA. Refer to Section 6.1). This will present as approximately 0.07 m ² of permanent impact to SCL. The bord and pillar UG mining technique, which will result in no material impacts at surface (Refer to Section 6.2). No other surface infrastructure is proposed, and the current use of this land will continue through the life of the mine.

Prescribed Solutions for RO2 (Schedule 2, Part 4, Section 11 – RPI Regulation)	Response
(d) if the activity will have a permanent impact on strategic cropping land on a property (SCL)—no more than 2% of the strategic cropping land on the property (SCL) will be impacted.	The surface impacts to the SCA will result from the flare in Zone 3, which will present as a permanent impact of less than 2% of the strategic cropping land on the property i.e. 0.000007 ha of permanent impact of a total 154 ha of mapped SCA (Refer to Section 6.1). The bord and pillar UG mining technique will result in no material impacts at surface (Refer to Section 6.2) and will allow the land use to continue for the life of the mine and following mine closure.

Required Outcome 3

RO2 is not relevant to the Project as the activity is proposed over a single property within the SCA. Refer to Section 5.2.

5 Existing Environment

5.1 Land Use within the Project

Land in the vicinity of the Project consists of mining operations, irrigated/dryland cropping and dryland grazing land. Land uses and activities inside and surrounding the proposed Project (1 km radius) are shown on Figure 7.

5.2 Property

Lots underlying the Project are continuous between Zone 2 and 3 and are commonly owned by Bligh Coal Ltd, Bowen Investment (Australia) Pty Ltd and Idemitsu Australia Pty Ltd. Lots underlying the Project are continuous between Zone 2 and 3 and are commonly owned by Bligh Coal Ltd, Bowen Investment (Australia) Pty Ltd and Idemitsu Australia Pty Ltd. Bligh Coal Ltd, Bowen Investment (Australia) Pty Ltd and Idemitsu Australia Pty Ltd have confirmed that these lots are operated as a single agricultural enterprise, principally cattle grazing. A map outlining the lots and plan for each land parcel inside and surrounding the Project is presented in Figure 8.

5.3 Land Resources Assessment

A Land Resource assessment for the Project (SLR, 2022) has been undertaken (Appendix C). This assessment characterised and detailed the type, distribution and quality of soils within the Project. Four dominant soil map units (SMUs) were identified across the Project and consisted of the following:

- 1: Crusty Brown Vertosols
- 2A: Eutrophic Brown Dermosols
- 2B: Eutrophic Brown Dermosols
- 3: Magnesic Brown Kandosols
- 4: Clastic Rudosols

5.3.1 Subsidence

Gordon Geotechniques Pty Ltd was commissioned by Ensham to undertake a subsidence study to assess the potential impacts of the Project (Appendix D – Subsidence Report), and prepare a Subsidence Management Plan (Appendix E). Both the Subsidence Report and Subsidence Management Plan have been peer reviewed and these documents are included as Appendix F and Appendix G respectively. The modelling results indicated that low levels of subsidence (less than 35 mm) are predicted for the Project. Real-Time Kinematic Global Positioning System monitoring indicates actual measured subsidence levels of less than 10 mm above underground mining operations which are consistent with the modelling prediction. Given this level of subsidence compared to natural soil movement of approximately 50 mm (IESC, 2015), subsidence will not impact land resources for the Project.


5.3.2 Dispersive Soils

Some slightly dispersive topsoils were identified from SMUs 2A, 2B and 3 in Zone 2 and 3, with some moderately dispersive subsoils also being identified across the Project. These subsoils will be appropriately ameliorated as per the requirements of the EA.

5.3.3 Land Suitability and Agricultural Land Classes


Due to the minimal surface footprint from the construction of each flare (see disturbance footprint details in Section 1.1.3), no material impact will be present on the land inside the Project. Flare construction will therefore not influence the Land Suitability Class or the Agricultural Land Class areas categorised from the soils in the Assessment. The Land Resources assessment is included in Appendix C.

\\au.slr.local\Corporate\Projects\SLR\620-BNE\620-BNE\620.30686_00000 Soils and Land Assessment\06 SLR Data\01 CAD\GIS\GIS\IRDA Application\620.30686 Fl 2 Land Use.mxd



Land Use

- Cropping
- Dryland cropping
- Grazing irrigated modified pastures
- Grazing native vegetation
- Grazing woody fodder plants (Leucaena)
- Irrigated cropping
- Marsh/wetland
- Mining
- Other minimal use
- Reservoir/dam
- Residential and farm infrastructure

 0 0.5 1 km

Coordinate System: GDA 1994 MGA Zone 55
Scale: 1:55,000 at A4
Project Number: 620.30686
Date: 15-Mar-2022
Drawn by: JG



- Flare Exclusion Areas (80m x 20m)
- Zone 2
- Zone 3
- Mining Leases

620.30686 ENSHAM SOIL SURVEY

Land Use



FIGURE 7



Coordinate System: GDA 1994 MGA Zone 55
 Scale: 1:80,000 at A4
 Project Number: 620.30686
 Date: 10-May-2022
 Drawn by: JG



- Flare Exclusion Areas (80m x 20m)
- Zone 2
- Zone 3
- Cadastre (DCDB 2021)
- Mining Leases
- Ensham Owned Property (i.e. Bligh Coal Limited, Idemitsu Australia Pty Ltd and Bowen Investment (Australia) Pty Ltd)

**620.30686 ENSHAM RIDA
 SUPPORTING DOCUMENT**

Underlying Property Ownership

6 Potential Impacts

6.1 Flare Exclusion Zones

As stated earlier, four flares are proposed to be constructed for the Project, two in Zone 2 and two in Zone 3. Each of these locations will utilise existing tracks on existing mining leases for construction of the flares for ongoing general access and maintenance. The construction of each flare will include a safety exclusion area of approximately 80 m by 20 m and as a conservative approach for this Assessment, this area will be considered the construction footprint, with a total area of 0.64 ha across the four flare locations. The Applicants accept that impacts relating to SCL will be permanent at one flare location in Zone 3 and will be limited only to ground disturbance associated with flare removal and reinstatement of approximately 0.07 m².

6.1.1 Rehabilitation

Post-mining, each flare structure and associated equipment will be decommissioned and removed from site. Each exclusion area will be rehabilitated in accordance with the EA (Appendix 3 – Rehabilitation Success Criteria). Topsoil previously stockpiled at the pre-construction stage will be redressed on top of the subsoil exposed during construction of the flares.

6.2 Subsidence

The Subsidence Report was prepared by Gordon Geotechniques in January 2022. Findings of this report are outlined below, and the Subsidence Report is included in Appendix D. A Subsidence Management Plan has been developed by Gordon Geotechniques and is provided in Appendix E. Both the Subsidence Report and Subsidence Management Plan have been peer reviewed and these documents are included as Appendix F and Appendix G respectively.

6.2.1 Impacts

Due to the nature of the bord and pillar mining method, low levels of subsidence, typically less than 35 mm, are predicted in Zones 2 and 3. Recent Real-Time Kinematic Global Positioning System (RTK GPS) monitoring at Ensham indicates that current subsidence levels above mined underground operations are less than 10 mm. This supports the upper subsidence level prediction for the Project. The subsidence levels for Zones 2 and 3 (Gordon Geotechniques, 2022) are predicted to range up to a maximum of 35mm with measured levels (based on RTK GPS equipment with +/- 5mm accuracy) of up to 10 mm for the existing mine. Similar levels of subsidence would be expected for zones 2 and 3 as similar pillar design criteria will be applied for the project as for the current operating underground mine. The measured values are significantly less than natural soil variation of up to 50mm (refer to Section 6.2.2). A Subsidence Management Plan has been prepared and includes real time monitoring. Nine additional real time monitoring stations will be included for the Project to monitor subsidence levels prior to, during, and post mining.

The negligible extent of subsidence is demonstrated on Figure 9 and Figure 10, which show subsidence levels in a non-mining area and measured subsidence in an underground mining area, respectively. Further details are provided under Appendix D (Subsidence Report).

Figure 9 Pre-Mining Panel (Station 502_3) Vertical Surface Movement





Figure 10 Underground Mining Panel (Station 502_1): Measured Subsidence Levels



6.2.2 Natural Variation

Natural ground variation is accepted to be up to 50 mm, as outlined by the Australian Government Department of the Agriculture, Water and the Environment (DAWE). DAWE outlined that seasonal variation in surface levels can be as high as 50 mm as a result of changes in moisture content meaning that the predicted subsidence is within the range of normal seasonal fluctuation (IESC, 2015). Underground mining activities are predicted not cause impacts beyond that expected in the natural variation in the area (refer to Section 6.2.1) and is supported by measure data. Additional RTK GPS monitoring, both pre-mining and during/post mining, will be undertaken for Zones 2 and 3.

6.3 Surface Impacts to Areas of Regional Interest

PAA and SCA are mapped within the Project (i.e. Zone 2 and Zone 3). The only surface impacts to ARIs will result from the flares described in Section 6.1. The total flare disturbance including exclusion areas is 0.64 ha, resulting in 0.1% of the mapped SCA and 0.01% of the mapped PAA areas being impacted by the Project. Permanent impact to SCA will include removal and reinstatement of one flare (approximately 0.000007 ha). The ROs for SCA and PAA applicable to this application require that surface impacts be not more than 2%. Refer to Section 4.1 and Section 4.2 outlining the detailed assessment against the ROs for SCA and PAA.

Table 16 shows the areas of ARI across the Project, including the flare exclusion zones.

Table 16 Areas of ARI for the Project

Area of regional interest (ARI)	Area of ARI across Project (ha)	Percentage Area of ARI across Project (%)	Extent of disturbance on ARI in Project (ha)	Percentage of extent of disturbance on ARI in Project (%)
Priority Agricultural Area (PAA)	603	100	0.64	0.01
Strategic Cropping Area (SCA)	153	25.4	0.16	0.1
Priority Living Area (PLA)	0	0	0	0
Strategic Environmental Area (SEA)	0	0	0	0

7 Conclusions

The Project will not have a material impact on SCA or PAA and satisfies the prescribed solutions under the RPI Regulation as follows:

- The Project satisfies all prescribed solutions for RO1 under Schedule 2, Part 2 of the RPI Regulation and will not result in material impact on the use of the property or a PALU.
- The Project satisfies all prescribed solutions for RO2 under Schedule 2, Part 4 of the RPI Regulation (as described in Table 15) and will not result in a permanent impact of greater than 2% to SCL on the property.
- The underground mining method (bord and pillar) would continue to be used to ensure that surface impacts are minimised. Subsidence from underground mine activities is not predicted to cause any material impacts on ground elevations and supported by measured subsidence levels based on similar pillar design criteria. Measured subsidence levels (5-10mm) and the maximum predicted level (35mm) are well below the reported natural variation in surface levels of up to 50 mm caused by changes in soil moisture content.

Recommendation

Under Section 34 (3) of the RPI Act 'the chief executive may, on the written request of the applicant, grant an exemption from notification for an assessment application if satisfied there has been sufficient notification under another Act or law of the resource activity or regulated activity to the public'. An EIS (including Zones 2 and 3) has been prepared to address requirements under the Queensland Environmental Protection Act 1994 and the Commonwealth Environment Protection and Biodiversity and Conservation Act 1999. The EIS was advertised under both these sets of legislation, with public comments received and responded to, and an EIS assessment report issued by the Department of Environment and Science in November 2021. It is requested that adequate public notice has been undertaken for the Project and an exemption to publicly notify this RIDA be granted.

8 References

AECOM, 2020. Environmental Impact Statement – Ensham Life of Mine Extension Project.

Central Queensland Regional Plan, 2013

Gordon Geotechniques Pty Ltd, 2022, Subsidence Report for the Ensham Life of Mine Extension – Zone 2 and 3, prepared for Ensham Resources Pty Ltd 2022.

Independent Expert Steering Committee (IESC), 2015. Monitoring and Management of Subsidence Induced by Longwall Coal Mining Activity. Report to the Department of the Environment.

Regional Planning Interests Act, 2014

Regional Planning Interests Regulation, 2014

RPI Act Statutory Guideline 01/14, 2019

RPI Act Statutory Guideline 02/14, 2019

RPI Act Statutory Guideline 03/14, 2019

RPI Act Statutory Guideline 06/14, 2019

RPI Act Statutory Guideline 07/14, 2019

RPI Act Statutory Guideline 09/14, 2019

SLR, 2022, Land Resource Assessment - Zone 2 and 3, Ensham Life of Mine Extension -Zone 2 and 3, prepared for Ensham Resources Pty Ltd 2022.

APPENDIX A

Project Description and Alternatives

4.0 Project description and alternatives

4.1 Introduction

This chapter presents information on the Ensham Life of Mine Extension Project – Zones 2 and 3 which is the subject of the environmental authority (EA) amendment application (hereafter referred to as ‘the Project’) including an overview of the mining activities proposed for the Project, and a brief overview of the existing Ensham Mine operations.

4.2 Project overview

Ensham Mine is an existing open-cut and underground bord and pillar coal mine located approximately 35 kilometres (km) east of Emerald in Queensland. The existing bord and pillar operations are currently authorised to continue until 2028 within Mining Lease (ML) 7459, ML 70326 and ML 70365, and extract a portion of the various combined Aries/Castor seam plies. An extension of these leases to 2050 would be sought to accommodate the additional underground mining and mine rehabilitation obligations under the current EA, and proposed Progressive Rehabilitation Closure Plan (PRCP). The open-cut mine is due to commence closure in 2022. However, Pits C and D within the open-cut mine will be retained to allow for access to the underground mine portals and will be rehabilitated towards the end of the open-cut rehabilitation program.

The proponents for the Project propose to increase the life of the existing underground operations by extending the underground bord and pillar mine into an area identified as Zones 2 and 3 as shown in **Figure 4-1**.

The Project covers approximately 603 hectares (ha) and includes two zones:

- Zone 2: partially includes existing leases ML 70326, ML 70365, and ML 7459 (total area is approximately 394 ha of which 346 ha would represent the projected mining footprint), and
- Zone 3: partially includes existing leases ML 7459 and ML 70366 (total area is approximately 209 ha of which 175 ha would represent the projected mining footprint).

The above-nominated mining footprint areas for Zones 2 and 3 are projected areas under which underground mining would occur. This total projected mining footprint area of 521 ha for both Zones 2 and 3 represents 8.17% of the total 6376 ha currently disturbed open-cut and current underground mining areas. In addition, the total mining footprint of 521 ha for both Zones 2 and 3 represents a 7.01% of the total 7429 ha approved for mining (open cut and underground).

Zones 2 and 3 have been subject to surface activities associated with the open cut mining mine since the grant of the mining leases. It is proposed to continue to mine these zones using bord and pillar underground methods which will considerably minimise future land disturbance. This will mean limited future surface disturbance with only 2 gas drainage flares planned in each zone in an area of approximately 0.6 hectares. Given the current mine design, it is not expected that the measured subsidence levels would contribute significantly to land disturbance when compared to soil expansion rates of 50mm observed. Recent monitoring at Ensham has indicated subsidence levels of less than 10 mm above mined underground panels. This monitoring has an accuracy of ± 5 mm and is able to detect the observed low levels of

movement. It is expected that similar levels of subsidence will be generated in Zones 2 and 3 based on similar design principles used in the current underground operations.


The proponents intend to separately progress the Ensham Life of Mine Extension – Zone 1. This Zone 1 extension is also proposed as a bord and pillar underground mine and will require a new mining lease to the north-west of the existing approved mine. The Zone 1 extension is not the subject of this EA amendment application, but will be the subject of separate EA amendment and mining lease applications (see section 4.7).

Project objectives

Approval of the Project will allow Ensham Mine to:

- Continue to produce at current planned coal production rate of approximately 4.5 million tonnes per annum (Mtpa) of product coal while remaining within the current Environmental Authority (EA) limit (condition A5) which authorises the mining of 12 million tonnes of run of mine (ROM) coal per annum. Without zones 2 and 3, the current underground operations will become physically restrained to lower production levels and affect the overall economic viability of the mine,
- Extend the life of mine (LOM) by up to two years with sufficient coal reserves to approximately 2029,
- Progress the underground operation within existing mining leases. The Project would continue to utilise existing operational mine equipment, existing mining methodologies, and existing infrastructure located on the existing mining leases, and
- Continue to provide substantial employment opportunities within the Central Highlands region. The Project is proposed to commence in late H1 2022 in Zone 2.

Figure 4-1 Ensham Underground Mine Plan (Currently Approved and the Indicative Project)



4.3 Site description

Location

The Project is located at the existing Ensham Mine, in the western part of the central Bowen Basin, approximately 200 km west of Rockhampton, and 35 km east of Emerald along the Nogoa River in Central Queensland. The location of the mine from a regional context is discussed in **Chapter 1** (Introduction) and **Chapter 5** (Land Use and Tenure).

Being located in the central Bowen Basin, the Project is situated in an existing mining precinct with a number of other coal mines operating in the area including Kestrel Mine to the north-west, Gregory Crinum to the north-east, Oaky Creek to the north, Lake Lindsay to the north-northeast, Curragh, Jellinbah and Mackenzie North to the east, Blackwater Mine to the southeast, and, Togara North to the south (refer **Figure 1-1 in Chapter 1** (Introduction)). The Project is located within the Central Highlands Regional Council (CHRC) local government area.

The Nogoa River and some minor tributaries traverse through the Zone 2 of the Project, with the Nogoa River (fed by the ephemeral Theresa Creek) and releases from the upstream Fairbairn Dam, providing a year-round water supply to downstream users.

The Project is located within the existing Ensham Mine mining leases as shown in Figure 4-1. The southern portion of Zone 2 includes an area mapped as Strategic Cropping Area (SCA) and Priority Agricultural Area (PAA) (refer **Chapter 5** (Land Use and Tenure)) while the northern portion is largely disturbed with large areas of cleared land and includes seismic lines and tracks. It contains areas of certified and uncertified rehabilitated spoil as well as unrehabilitated spoil and pre-strip areas from open-cut mining. Zone 3 is disturbed land with borrow pits, dragline spoil, levees, topsoil stockpiles, pre-strip areas, tracks, and seismic lines associated with the existing open-cut operations at Ensham Mine. Zone 3 is largely cleared with sparse stands of vegetation across the area. The majority of Zone 3 is mapped as SCA and PAA. Both Zone 2 and Zone 3 are currently used for grazing.

All activities directly associated with the Project will be carried out within the existing Ensham mining leases. There will be no activities required outside the existing Ensham mining leases for the Project.

Tenements and ownership

Zones 2 and 3 comprise four registered land parcels which are all freehold and owned by the Ensham Joint Venture (Ensham JV).

The Ensham JV also holds various resource tenements which includes seven MLs and two MDLs.

4.4 Existing Ensham Mine operations

The existing mining operations at Ensham Mine consist of open-cut and underground operations, with the rehabilitation of the open-cut mining areas currently underway. The open-cut operation is scheduled to close in 2022. Both current underground and open-cut operations are authorised to continue until January 2028 after which time the mining leases would need to be renewed.

The existing underground workings are accessed through three portals located in Pits C and D. These portals are used for ventilating the mine, for personnel and materials access, and, conveying ROM coal from the underground workings to the above-ground coal stockpile. Coal is then transported by road trains on a private road to the coal handling plant (CHP) where it is crushed and sized to produce product coal. The product coal

is then transported via rail to Gladstone for electricity generation at the Gladstone Power Station, and, to the Gladstone Coal Terminal for export overseas.

Methane gas is currently drained from the target coal seam through in-seam drainage holes that are connected to an underground piping system which transports the gas to the surface via a borehole to where the gas is flared. As is a common practice in the Bowen Basin, underground in-seam gas drainage is a means of draining in-situ gas in advance of mining to maintain a safe working environment. Flaring of the drained gas is required to reduce greenhouse gas emissions as required by the Clean Energy regulator and s318CO (2) of the *Minerals Resource Act 1989*. Gas from the existing underground mining operation is currently being flared in locations to the west of C and D pits as shown in **Figure 4-2**.

Legend

- Project
- Coal Conveyor Transport System
- Proposed Flaring Infrastructure
- Existing Flaring Infrastructure
- Exclusion Zone
- Ensham ML
- Ensham MDL
- Pit
- Mining Infrastructure
- Underground Mined Area

Flaring Infrastructure Legend

- 2021
- 2022
- 2023
- 2024
- 2025
- 2026
- 2027
- 2028
- 2029


Map Labels

- MDL217
- MDL218
- Ensham Road
- Zone 2
- Flare 1
- Flare 2
- ML70326
- CDE Pit
- Red Hill Infrastructure
- Vent Fans
- UG Admin
- AB Pit
- Zone 3
- Flare 3
- Flare 4
- ML70366
- ML70049
- FY Pit
- Coal Stockpile
- ML70367
- ML7460
- ML7459
- Coal Stockpile
- Train Load Out
- OC Workshop Village
- Dockwings Road

Ensham RESOURCES

ENSHAM LIFE OF MINE PROJECT ZONES 2 AND 3

Projection: GDA 1994 MGA Zone 55
Source: © State of Queensland (Department of Natural Resources, Mines and Energy) 2020
13 December 2021



Project construction

The Project is a continuation of the existing underground mine and will continue to use existing surface infrastructure located on the existing approved MLs (which includes Zone 2 and Zone 3). No additional material infrastructure other than installation of four flares (as shown in Figure 4-2 and described in **Section 0**) will be required. This work would likely involve approximately 5 people to construct the flaring infrastructure.

As there will be no material surface construction activities or construction traffic, nor increases in ROM coal production, the Project will not require any upgrades to the existing road, rail, or port infrastructure. The transport assessment for the Project is discussed further in **Chapter 16** (Transport).

4.5 Proposed Project operations

Exploration Activities

No additional exploration will be required for the Project. There is sufficient geological data available for the anticipated mine plan shown in **Figure 4-2**.


Conceptual mine design, schedules, and ROM production

The mining sequence for the Project is based on the extension of the current approved mine workings. **Figure 4-2** shows the existing approved mined underground areas (approved under EA EPML00732813), the mine schedule from 2022 to 2029, and the infrastructure required to support the existing approved underground mining areas and the Project. **Figure 4-3** shows the planned coal production from 2022 to 2029. As discussed in Section 4.7, operations in Zone 1 would commence at a later time after obtaining all necessary approvals. If approved, production is expected to be maintained up to approximately 4.5 Mtpa of product coal until approximately 2037.

As shown in **Figure 4-2**, Zone 2 would be the first underground area to be accessed from ML 70365 in 2022. Mining in Zone 3 would commence also from ML 70365 in approximately 2026 and continue until 2029.

The mine design has been completed with a factor of safety of 1.6 for bord and pillar workings beneath the Nogoia River floodplain and 2.11 beneath the Nogoia River to connect the bord and pillar mining areas as discussed further in **Chapter 5** (Land resources). Underground mining for the Project will range from a depth of approximately 80 to 210 metres (m) below the surface. There will be no mining under the Nogoia River.

Figure 4-3 Ensham Mine ROM coal production



Mining and processing equipment and infrastructure

A mining infrastructure study has been conducted as part of the Prefeasibility Assessment (Idemitsu, 2020) and the findings of that study are discussed in the following sections.

Underground equipment

The Project will continue to use continuous underground miners (or similar) which will provide sufficient capability to mine the Project site. Other existing equipment that will likely continue to be used includes shuttle cars, mobile bolters, feeder breakers, and other ancillary underground equipment.

Coal clearance system

Extracted coal will continue to be transported from the underground production panels to the ROM storage area using a system of underground conveyors. The existing underground coal clearance system has sufficient capacity for the Project and will be extended in the underground workings as the mining operations progress into zones 2 and 3.

ROM storage area

The ROM stockpile area is expected to remain approximately the same size during the Project. Existing or similar loaders and road trains will continue to be utilised to manage the ROM stockpiles.

Coal handling plant

The existing CHP comprises a truck dump station, crushing and screening plant, product conveyors, stackers, reclaim system, and loadout system. After crushing, the product coal will continue to be stockpiled and loaded onto trains via the existing train loadout facility. Currently, no waste rock is produced.

A minor upgrade of the CHP, within the footprint of the current CHP disturbed area, is currently being trialled. The trial includes a small dry processing module which complies with existing EA conditions. This module, if successful, would be integrated into the existing footprint of the CHP to assist with the dry removal of rock from the seam coal. The introduction of technology to remove rock from the coal is consistent with the previously approved coal handling and preparation plant (CHPP) function with a significantly lower environmental impact (i.e. no tailings facility and associated additional water use). This is discussed further in section 4.6.7 - Waste Materials.

Associated infrastructure

Ventilation

Existing underground ventilation systems will be extended for the Project as zones 2 and 3 are developed using current practices and procedures.

Gas drainage and management

Consistent with existing practices at Ensham Mine, gas drainage will be required for the Project to allow seam gas pre-drainage to ensure a safe working environment in the underground workings. Coal seam drainage gas will be vented in Zone 2 and Zone 3 via flaring infrastructure. A total of four flares will operate on existing mining leases - two flares will be located in Zone 2 and two flares in Zone 3 in locations as shown in **Figure 4-2**.

Installation and use of these gas flares is for safety mitigation and represents a lower environmental impact than free venting as required under Mineral Resources Act 1989 legislation. The flares would be initially established in locations already approved for disturbance identified in Zones 2 and 3. The flares will be constructed and operated at a time consistent with the mining schedule currently anticipated around 2022-2029 for Zone 2, and approximately 2026-2029 for Zone 3. Flares will be established in cleared areas. The Project flares would all be constructed and operated at least one kilometre away from waterways which provide fish passage. The coordinates of the flares are shown in **Table 4-1**.

Table 4-1 Proposed flare locations

Flare	Coordinates (GDA 94)	
	mE	mN
1	649916.6	7407667
2	651108.9	7407285
3	648985	7399439
4	649285.5	7398580

The setup of the flares will be risk based and include an exclusion zone which will be fenced to prohibit wildlife and people from unauthorised entry. This exclusion area would be approximately 80 m by 20 m on disturbed land and would not require vegetation clearing (other than maintenance of grass levels to minimise fire risk). These locations would utilise existing tracks on existing mining leases for construction purposes and ongoing general access and maintenance matters. Flaring stacks would be approximately 8 m tall with the flare height being up to 3 m above the stack. The total area of the exclusion zones for the 4 flares would be approximately 0.6ha.

Further information regarding the greenhouse gas assessment is presented in **Chapter 7** (Air Quality and Greenhouse Gases).

Compressed air

Surface compressors are currently located within the Red Hill infrastructure complex located in Pit C above the portals as shown in Figure 4-2. The existing compressed air system will be adequate to support the Project.

Electricity supply

66 kilovolt (kV) power is currently provided to Ensham Mine from the Ergon Lilyvale substation via an existing 27km overhead transmission line. The underground mine is supplied via an existing 66/11 kV 10 megavolt amp transformer located at Red Hill.

Demand modelling conducted for the Project indicates there is sufficient capacity to supply power for the Project and no new surface electrical infrastructure will be required.

Should additional underground power be required for the Project then a borehole will be established. The location of the borehole would be in the northern section of ML 70365 on non-strategic cropping land and above 0.1% AEP flood line.

Communications

The current underground communications system is located along conveyors, mining operations and substations to provide communications between underground and surface personnel.

The existing underground fibre optic communication network is adequately servicing the current mining operations and will be extended underground as required for the Project.

Raw water supply

The current water supply system at Ensham Mine, including surface potable water infrastructure, will be utilised for the Project. Additional piping and booster pumps will be installed underground to supply the required water pressure for the Project.

No changes in water licencing arrangements are expected for the Project.

Mine dewatering

Mine affected water is currently pumped from the underground to surface infrastructure using a dedicated dewatering system. This dewatering system would be extended underground for the Project.

No changes to the surface mine water infrastructure would be required. The water management system will be adequate to manage Project mine water as assessed in **Chapter 9** (Water Balance and Water Quality).

Flood protection

Flood protection will continue to be provided to the open cut pits and underground portals in proximity to the floodplain using the existing Regulated Structures (the levees) as licenced under the current EA. These levees are certified on an annual basis by a suitably qualified RPEQ engineer to a 0.1% AEP + 0.5m flood height. No changes to these levees will be required. This matter is discussed in more detail in **Chapter 10** (Flooding and Hydrology).

Surface buildings

The existing surface buildings have sufficient capacity for the Project. No new surface buildings will be required to be constructed for the Project.

Workforce

Operational workforce

The Ensham Mine currently employs approximately 692 full-time equivalent (FTE) personnel, who are a mixture of local Emerald and surrounding community-based persons, and, drive in/drive out and fly in/fly out persons. This workforce will be maintained up to approximately 2022 when the current open-cut operations are scheduled to be completed. From that time, the workforce will reduce to approximately 613 FTE personnel inclusive of the Project. As discussed in Section 4.7, operations in Zone 1 would commence at a later time after obtaining all necessary approvals. If approved, the workforce is expected to be maintained at approximately 613 FTE personnel until approximately 2037. After completion of the underground mining activities, the workforce will decline with the remaining personnel dedicated to completing rehabilitation activities for the site.

Secondary employment opportunities currently supported through the ancillary services to the Ensham Mine include extended requirements for workforce accommodation and a large range of mine support services such as, fabrication, maintenance, and rehabilitation related services.

Hours of operation

Production personnel currently work 12 hour rotating shifts (day/night) on a 7/7 roster, whereas staff principally work 10-hour day shifts on a 5/2 roster.

No changes to the existing roster arrangements and workforce residential locations, other than the extension of production activities to 2029, are expected for the Project.

Workforce accommodation

The current workforce is a mixture of local Emerald and surrounding community-based persons and drive in/drive out and fly in/fly out personnel. The Social Impact Assessment previously prepared for zones 1,2,3 (AECOM 2020) identifies that approximately 78 per cent of Ensham Mine personnel are either Emerald based or drive in/drive out based. In addition to the local workforce that reside in local community housing, Ensham Mine maintains a 600 person worker camp.

As the Project does not involve any material construction activity, there would be no construction workforce required. It is expected that current operational workforce arrangements will continue for the Project and no new accommodation facilities would therefore be required.

Transport infrastructure

Road transport and traffic

As there is no construction phase or increase in personnel numbers required for the Project, there will be no increase in traffic volume from current approved levels, and will have no discernible impact on the operation of the relevant sections of both the state-controlled (Capricorn Highway) and CHRC controlled (Duckponds Road) networks. A detailed assessment of the Capricorn Highway/Duckponds Road intersection identified that the current configuration would be more than adequate to cater for Project traffic volumes is shown in **Chapter 16** (Transport).

As such, the existing access facilities for Ensham Mine currently provided via the gated access on Duckponds Road will be suitable to cater for the Project. Accordingly, no changes to the road infrastructure will be required.

Rail transport and port operations

Product coal from Ensham Mine is railed on the Aurizon managed Central Queensland Coal Network known as the Blackwater System for delivery to both the Gladstone Coal Terminal and the Gladstone Power Station. As there are no expected increases to the annual coal production rate as shown in **Figure 4-3**, there will be no requirement for changes in either the rail or port requirements.

Coal collected for marketing and quality control purposes may be transported by road. Volumes to be transported are not forecast to exceed 20 tonnes per annum and around 1 tonne per item. Exports from Gladstone Port Corporation will continue to contractually require all vessels to meet all performance and vetting requirements published by Gladstone Ports Corporation in alignment with MSQ, AMSA and IMSO prescribed code and legislation.

Waste materials

The Project will continue to generate mining and non-mining waste materials during the operational phase, as well as wastewater and air emissions. As seen in Figure 4-3, there is no expected increase in the annual coal production for the mine. Waste generated as part of the Project will be managed using the existing waste management systems currently utilised by the existing mine operations. No changes to the waste management systems onsite will be required.

A detailed waste assessment is included in **Chapter 6** (Land Resources) and **Chapter 15** (Waste Management).

Mine waste - waste rock

Waste rock produced by the Project will be generated from the coal handling plant at approximately 5,700 m³ per annum. The Project will place the waste interburden, and roof and floor rock into Pit C and Pit D. The estimated volume of waste rock from the proposed Project over the life of the mine is 45,600 m³ in total which

is approximately 0.1 per cent of total approved waste rock volumes (36 million m³) currently approved for the rehabilitation of Pit C and Pit D. At approximately 0.1 per cent of total approved rock volume for Pit C and Pit D, it is not expected that this addition would impact the approved final landform outcomes including final void water heights shown in Appendix 3 of the 5A EPML00732813.

Characterisation of this waste rock including AMD potential and metalloid mobility is discussed in more detail in **Chapter 6** (Land Resources).

Non-mine waste

Ensham Mine's existing operations produce general solid and liquid wastes that are typical of mine site operations. These sources include:

- regulated waste including hydrocarbon waste such as waste oil, oily water, oily sludge, grease, oil rags, oil filters, as well as coolant, drums, detergents, solvents, batteries, tyres, paints, and resins
- general waste including food waste, packaging, and food containers
- recyclable waste including paper, cardboard, plastics, glass, and aluminium cans
- wood waste including timber, pallets, and off-cuts
- tyres including light vehicle tyres and mine truck tyres
- scrap metal from mine infrastructure areas including drums, conveyor rollers, air filters and miscellaneous metal from maintenance activities.

Waste types, annual generation rates and applied management strategies for the mine site are not expected to materially change from current operations for the Project as coal production rates will remain relatively constant as seen in **Figure 4-3**.

General waste is currently transported and disposed of by an authorised waste management contractor at a licenced landfill. There are a number of local landfills available for the site waste contractor to utilise. Recyclable materials are taken to an authorised recycling centre for initial processing, involving segregation, crushing, and baling for transport to various companies for recycling. Regulated wastes are transported by a licenced waste contractor to an authorised resources recovery facility for recycling, reprocessing, treatment, and disposal.

Sewage is treated at existing onsite sewage treatment plants with effluent used for the irrigation of rehabilitated areas and plantation trees as authorised under the Ensham Mine EA. As there is no increase in personnel numbers, the current system capacity will be adequate and no upgrade will be required for the Project.

The waste inventory, characteristics of non-mining wastes and their management are discussed in detail in **Chapter 14** (Waste management).

Wastewater

Waste mine water will continue to be managed using the existing water management system or the Project. There will be no proposed changes to EA conditions for water discharges. Modelling has indicated that the water management system will be adequate to manage mine water generated by the Project as demonstrated in **Chapter 9** (Water Balance and Water Quality).

Air emissions

Surface activities at the existing Ensham Mine with the potential to impact air quality include vehicle movements on unsealed roads, and coal handling and crushing operations.

The main sources of direct and indirect greenhouse gas emissions from the Project are:

- Fugitive emissions of CH₄ (methane) and CO₂ (carbon dioxide) due to underground air ventilation processes,
- Direct CO₂ from gas flaring of coal seam methane pre-drainage,
- Direct CO₂ emissions from fuel combusted by mining equipment/vehicles,
- Fugitive emissions from mining activities such as coal stockpiling, and, conveying of coal from the underground to the CHP, and
- Indirect CO₂ emissions from off-site electricity generation.

Modelling of air quality impacts associated with the Project predicts compliance with the current EA conditions and will reduce over the life of the Project when the open-cut operations cease. Management of greenhouse gas emissions from the underground mine will be achieved through flaring activities to be undertaken for Zones 2 and 3.

Air emissions associated with the Project are discussed in more detail in **Chapter 7** (Air quality and Greenhouse Gases).

4.6 Project sequencing and environmental approvals

The mining sequence for the Project will involve Zone 2 as the first underground area to be accessed in 2022. Mining in Zone 3 is anticipated to commence in approximately 2026 and continue until 2029. Due to the need to obtain entry to Zone 2 in H1 2022, this environmental authority (EA) amendment application is to seek approval for Zone 2 and 3 only. As the underground mining and associated activities for Zones 2 and 3 will occur on existing mining leases, there will be no requirement to apply for a new mining lease. The land for Zones 2 and 3 is owned by the Ensham JV.

The Ensham Life of Mine - Zone 1 extension is proposed on land within MDL 217 and will require a new mining lease. It is not part of this EA amendment application, but will be the subject of separate EA amendment and ML applications. Operations in Zone 1 would commence after obtaining all necessary approvals. The purpose of sequencing the necessary approvals is to ensure continuity of the operations within the existing mining leases as a priority. The proponents are committed to mining zones 1, 2, 3 subject to obtaining the necessary approvals.

4.7 Feasible alternatives

A range of alternative options have been considered in the development of the Project. Alternatives were considered in terms of location, mine plan and infrastructure configuration, and mining methods. This section discusses the range of alternatives considered and provides justification for the Project. As the development of Zone 1 will occur at a later date and will be subject to a separate approvals process, it has been considered in the range of feasible alternatives discussed below.

Cumulatively with zone 1, the capital costs of the Project (in 2020 dollars) are estimated at \$314.9 million, and comprise:

- \$72.4 million incurred within Central Queensland,
- \$107.1 million incurred within the rest of Queensland,
- \$66.1 million incurred within the rest of Australia, and
- \$69.3 million incurred overseas.

Of the \$314.9 million, \$10.9 million are one-off sustaining costs, and \$304 million are ongoing sustaining costs.

Strategic alternatives

A prefeasibility assessment (PFA) (Idemitsu, 2020) was undertaken which considered a number of strategic alternatives as discussed in summary below.

A ‘do nothing’ scenario was considered as an alternative option to the Project. This option showed that employment for the workforce (approximately 607 FTEs) and the community and economic benefits to the regional, state, and national economies reduce over the years leading up to the existing mine closure in 2028. State royalties and Commonwealth tax revenue derived from the additional coal resource in the Project would be foregone and the contribution to Queensland’s economy and COVID-19 recovery would not be realised.

This was not seen as a preferred outcome given the social and economic harm that closure of the mine would cause, and as such, this scenario was not advanced.

Additional scenarios considered are discussed further in Table 4.2 and summarised below:

- Development of a greenfields mine separate to the existing Ensham Mine and current infrastructure, and
- Development of a brownfields mine expansion utilising existing Ensham Mine and current infrastructure.

Development of a greenfields underground mine was considered to involve:

- Significant disturbance of additional surface areas external to and west of the existing mining leases, including potentially strategic cropping areas, and
- Significant investment of capital to replicate existing onsite coal handling and rail infrastructure.

Both of the above points would represent significant investment hurdles and would likely make this scenario unviable leading to the same outcome as the ‘do nothing’ scenario.

Based on the above, development of a brownfields mine expansion was considered the best scenario due to:

- Proximity to Ensham Mine’s existing operations which include all the supporting mine infrastructure required to operate the Project which delivers a lower capital investment requirement and no impacts on surface agricultural activities and strategic cropping areas,
- Existing access to the Capricornia Coal Chain, which comprises the Blackwater and Moura Rail corridors, both coal terminals at the Port of Gladstone (RG Tanna Coal Terminal and Wiggins Island Coal Export Terminal) and rail haulage operators (Aurizon and Pacific National), and
- Availability of the coal resource and its technical and economic feasibility.

Coal resources within the existing tenements were considered limited based on consideration of the following criteria:

- Availability of a full seam, mined on an in-situ basis,
- Line of oxidation (LOX) lines, beyond which, weather or oxidised coal was not targeted,
- A minimum underground working section thickness of 1.5 m below 60 m depth of cover within a 100 m buffer to the existing open-cut, and
- Tenement boundaries.

Table 4-2 Project alternatives

Case #	Description	Average production (Mtpa)	Project life
Base Case	Thick and thin seam in ML's only, includes Zone 2 and Zone 3. Maintain current operation (5-production units), excluding CHPP.	4.3	10 years
Long Term Plan	Base Case including thick seam in Zone 1. Maintain current operation (5-production units), excluding CHPP.	4.3	13 years
MDL Case 1	Base Case - including the Zone 1 thick & thin seam, excluding CHPP. Maintain current operation (5-production units) with no coal washing.	4.1	17 years
MDL Case 2	Base Case – including the Zone 1 thick & thin seam and including CHPP. Maintain current operation (5-production units) and commence with coal washing when required in 2027.	3.8	17 years
MDL Case 3	MDL Case 1 – without dilution (i.e. mining not undertaken immediately adjacent to the coal seam floor or roof).	4.0	17 years

The Base Case is limited to mining within existing approved MLs only, with no mining proposed in MDL 217. MDL Cases 1 to 3 consider thin seam mining in Zone 1 only, and a coal handling and preparation plant is considered in MDL Case 2 only.

MDL Case 1 was considered the preferred option. The selected option has been evaluated and proven to be technically and financially feasible (Idemitsu, 2020). This option provides easy access to the existing coal reserves within existing mining leases, generates minimal surface impacts, allows continuity of mining, and ensures continuity in the associated employment to 2029.

Mine plan options analysis

With the brownfields scenario identified, the PFA undertook an analysis of potential mine plans to select a preferred mine plan and preferred mining methodology. Having considered the social and economic aspects in the mine scenario phase (above) the mine plan and methodology for the project were considered based on technical and financial feasibility (Idemitsu, 2020).

Six underground mine development cases were evaluated in the PFA. All options sought to extend the Ensham LOM to ensure employment for the existing workforce is maintained up to and beyond 2028. The identification of options and alternatives was primarily based on:

- Seam thickness and structure (fault locations),
- Access for personnel and materials,
- Conveyor access to the surface, and
- Ventilation requirements.

The mine plan is based on the current design principles currently used at the existing Ensham Mine.

Mining methods

The existing underground mine extracts a portion of the various combined Aries/Castor seam plies using the place change bord and pillar mining method. Bord and pillar mining was adopted due to the intensity of faulting (typical of the Rangal Coal Measures) and the presence of the Nogoia River and its floodplain (Idemitsu, 2020). All of the alternative options considered would adopt the same bord and pillar mining method.

Ecologically sustainable development

The Project's compatibility was reviewed against the objectives and principles defined in the *National Strategy for Ecologically Sustainable Development* (Ecologically Sustainable Development Steering Committee, 1992) (**Table 4-3**).

The goals of ecologically sustainable development are to develop and improve the quality of life, both now and in the future, in a manner that maintains the integrity of ecological processes on which life depends.

Table 4-3 Integration of ESD principles into the Project development

Guiding principles of ESD	Integration into Project development
Core objectives	
<i>To enhance individual and community well-being and welfare by following a path of economic development that safeguards the welfare of future generations</i>	<p>The Project will provide significant social and economic benefits to the broader community in terms of economic stimulus from export revenues and royalties, increased employment opportunities and opportunities for suppliers. Outcomes for the “do nothing” and “greenfields development” scenarios would not assist in the enhancement of individual and community well-being and welfare through economic development that safeguards the welfare of future generations.</p>
<i>To provide for equity within and between generations (the Intergenerational Equity Principle)</i>	<p>Through appropriate management strategies and monitoring of the impacts, the Project will not significantly reduce, or fail to maintain the health, diversity and productivity of the Queensland environment or affect future generations.</p> <p>Disturbed land associated with the Project will be progressively rehabilitated as detailed in Chapter 6 (Land Resources).</p> <p>The brownfields nature of the Project provides opportunities for the Project to minimise impacts. This will include making use of existing infrastructure within previously disturbed areas at Ensham Mine, thereby avoiding the requirement for clearing of vegetation.</p> <p>Water management practices currently employed at Ensham Mine will ensure that the downstream water quality is not adversely affected by the Project. Measures to protect water quality are detailed in Chapter 9 (Water Balance and Water Quality).</p> <p>Project emissions will be minimised or mitigated to have no significant long-term adverse effect on the surrounding environment. Mitigation measures are discussed in more detail in Chapter 7 (Air Quality and Greenhouse Gases).</p>
<i>To protect biological diversity and maintain essential ecological processes and life-support systems</i>	<p>The terrestrial and aquatic ecology values in the vicinity of the Project are described in Chapter 12 (Terrestrial Ecology) and Chapter 13 (Aquatic Ecology) respectively. These chapters also provide an assessment of the impacts along with mitigation measures throughout the life of the Project.</p> <p>As very limited surface disturbance and groundwater drawdown is expected as a result of the Project, including surface subsidence, potential impacts to terrestrial and aquatic ecosystems from the Project are very limited.</p>

Guiding principles of ESD	Integration into Project development
Guiding ESD principles	
<i>Decision-making processes should effectively integrate both long and short term economic, environmental, social and equity considerations</i>	The Project will provide immediate and long-term benefits to the economic and social fabric of Queensland and in particular the Central Highlands region. The Project will contribute to the national, state, and local economies.
<i>Where there are threats of serious or irreversible environmental damage, lack of full scientific certainty should not be used as a reason for postponing measures to prevent environmental degradation (the Precautionary Principle)</i>	Ensham JV has undertaken an assessment of the risk of serious or irreversible environmental damage consistent with the Precautionary Principle and used the findings to determine appropriate environmental control strategies. The assessment identified that there are no serious or irreversible environmental damage for the Project. Full details of the risk assessment are detailed in this EA Amendment Chapter 18 (Commitments) . The Project has the technical and financial support and resources to establish and maintain these environmental protection controls.
<i>The global dimension of environmental impacts of actions and policies should be recognised and considered</i>	Ensham JV is aware of their corporate responsibilities in relation to the Project. The Ensham JV participates in the Australian Greenhouse Challenge program, a federal government initiative to encourage reductions in greenhouse gas emissions. The Project will generate greenhouse gas emissions from site operations, product transport and product use. As outlined in Chapter 7 (Air Quality and Greenhouse Gases) , Ensham JV has recognised and considered these aspects and proposes a range of mitigation measures for site level emissions.
<i>The need to develop a strong, growing and diversified economy which can enhance the capacity for environmental protection should be recognised</i>	The Project will add value to international, Australian and Queensland economies. There will be indirect flow on effects to other areas of the Queensland economy as a result of the Project. Ensham Mine will continue to make use of local suppliers and contractors during the Project as detailed in Chapter 4 (Project Description and Alternatives) .
<i>The need to maintain and enhance international competitiveness in an environmentally sound manner should be recognised</i>	Ensham Mine currently performs consistently in the top ten bord and pillar operations globally. The Project will continue Australia's international competitiveness. Ensham JV has used the Project's proximity to the existing Ensham Mine to minimise environmental impacts and will be subject to an EA and contemporary management plans ensuring that all environmental impacts are managed appropriately.
<i>Cost-effective and flexible policy instruments should be adopted, such as improved valuation, pricing, and incentives mechanisms</i>	The Project is consistent with the relevant local, State and Commonwealth government policies. By expanding within the existing mining leases and utilizing existing site infrastructure,

Guiding principles of ESD	Integration into Project development
	the proposed expansion will be both cost effective and will minimise additional environmental impacts.
<i>Decisions and actions should provide for broad community involvement on issues which affect them</i>	Ensham JV has undertaken community consultation prior to preparing the EIS, which is detailed in Chapter 3 (Stakeholder Consultation) process and will continue the progress through the Project's life. Ensham JV will continue to work with and maintain open communication with the community and stakeholders on all aspects of Ensham Mine. Ensham JV will continue to have meetings with local councils and continue briefings with community groups and stakeholders.
<i>To maintain and enhance compliance to export guidelines, regulations, and protocols</i>	Exports from Gladstone Port Corporation will continue to contractually require all vessels to meet all performance and vetting requirements published by Gladstone Ports Corporation in alignment with MSQ, AMSA and IMSO prescribed code and legislation.
Specific ESD objectives for the mining sector	
<i>To ensure mine sites are rehabilitated to sound environmental and safety standards and to a level at least consistent with the condition of surrounding land</i>	Ensham JV has prepared a Rehabilitation Management Plan for the Project (refer Chapter 6 (Land Resources) in which the land disturbed by the Project is to be progressively rehabilitated to a safe and stable landform that does not cause environmental harm and is able to sustain an approved post-mining land use.
<i>To provide appropriate community returns for using mineral resources and achieve better environmental protection and management in the mining sector</i>	<p>This Project will produce coal for domestic and international consumption. Increased demand for coal products in south-east Asia and other international markets has created a window of opportunity for the extension of Ensham Mine. For the foreseeable future, coal exports from the Project will provide significant revenues to Commonwealth, State, and local Governments.</p> <p>The Project will be developed to minimise resource waste and sterilisation. The mine sequencing will be designed to maximise resource extraction.</p> <p>Ensham JV has undertaken a comprehensive environmental assessment process to identify the opportunities to improve environmental protection and management for the Project. This assessment documents the detailed assessments that have been undertaken. In addition, the summary of commitments (Chapter 18 (Commitments)) outlines the proposed environmental management strategies for the Project. The Project has the technical and financial support to establish and maintain these environmental management controls.</p>

Guiding principles of ESD

To improve community consultation and information, improve performance in occupational health and safety and achieve social equity objectives

Integration into Project development

Ensham JV has undertaken community consultation prior to preparing this EA Amendment. The details of which, are presented in **Chapter 3** (Stakeholder Consultation). The Ensham JV has undertaken a review of the risks to occupational health and safety posed by the Project and proposes appropriate management measures as detailed throughout the respective documents.


APPENDIX B

Fodder Frequency Mapping

Introduction

This report presents maps of crop frequency for your chosen area, and chosen time period. Maps are based on time-series analysis of satellite imagery (30-m spatial resolution), for both the summer and winter growing seasons, aimed at detecting cycles of greenness in vegetation. Composite satellite images that display the maximum greenness within a summer or winter growing season for each year are also provided, as a visual reference. For further information refer to the FORAGE User Guide (https://data.longpaddock.qld.gov.au/static/forage_user_guide.pdf).

Estimated total crop frequency map (2012 - 2021)



How to interpret the information

Crop-frequency mapping: Coloured areas on the maps indicate locations where active crops have been detected three or more times in the summer or winter growing seasons, for the time period specified. The map on this page shows "Total Frequency" which is a count of the number of times that an active crop was detected. The maps on the following page show the summer and winter crop frequency, respectively. Analysis of satellite imagery can result in some misclassification, so it is recommended to view the composite imagery (see below) to help confirm the presence of a crop in a given season.

Mapping of broad groups of crops: Crop frequency is also separated into estimates of the broad crop groups within the area. This estimation is based on an automated classification approach (see <https://www.qld.gov.au/environment/land/management/mapping/statewide-monitoring/crops> for more detail).

In the winter season the classification differentiates between the groups:


- Cereal crops (e.g. wheat, barley, oats);
- Pulse crops (e.g. chickpea).

In the summer season the classification differentiates between the groups:


- Coarse-grain and pulse (e.g. sorghum, maize, mungbean);
- Cotton crop.

Composite satellite imagery: Due to the limitations of the automated method used to detect active cropping, it is recommended to view the seasonal composite images (pages 5 onward), compiled to represent the maximum greenness (per pixel) within a growing season. Cropped areas will generally appear bright green in the imagery compared with the surrounding landscape. Even if the crop-frequency mapping does not indicate cropping in an area, it is important to check each composite image to confirm that cropping has not been undertaken. Sometimes it will not be possible to clearly identify cropped areas in the imagery, e.g. in some wetter seasons the entire landscape might appear green. In this case, it is recommended to undertake further investigation using other information sources. Note: the composite images are only used to confirm the presence or absence of cropping activity; it is not possible to visually differentiate between the crop groups.


Estimated frequency map for summer (February) crops (2012 - 2021)




Estimated frequency map for winter (September) crops (2012 - 2021)




Estimated frequency map for summer (February) coarse grain and pulse crops (2012 - 2021)




Estimated frequency map for summer (February) cotton crops (2012 - 2021)



Estimated frequency map for winter (September) cereal crops (2012 - 2021)



Estimated frequency map for winter (September) pulse crops (2012 - 2021)



FORAGE REPORT: CROP FREQUENCY



<http://www.longpaddock.qld.gov.au/forage>

06/04/2022


Lot on Plan: 32RP908643

Label: 30686


February (left) and September (right) images for 2012



February (left) and September (right) images for 2013



February (left) and September (right) images for 2014



FORAGE REPORT: CROP FREQUENCY



<http://www.longpaddock.qld.gov.au/forage>

06/04/2022

Lot on Plan: 32RP908643

Label: 30686

February (left) and September (right) images for 2015




February (left) and September (right) images for 2016




February (left) and September (right) images for 2017




February (left) and September (right) images for 2018



February (left) and September (right) images for 2019



February (left) and September (right) images for 2020



FORAGE REPORT: CROP FREQUENCY

<http://www.longpaddock.qld.gov.au/forage>

06/04/2022


Lot on Plan: 32RP908643

Label: 30686



Queensland
Government

February (left) and September (right) images for 2021



Disclaimer

Limitation of liability: the State of Queensland, as represented by the Department of Environment and Science (DES) gives no warranty in relation to the data (including without limitation, accuracy, reliability, completeness or fitness for a particular purpose). To the maximum extent permitted by applicable law, in no event shall DES be liable for any special, incidental, indirect, or consequential damages whatsoever (including, but not limited to, damages for loss of profits or confidential or other information, for business interruption, for personal injury, for loss of privacy, for failure to meet any duty including of good faith or of reasonable care, for negligence, and for any other pecuniary or other loss whatsoever including, without limitation, legal costs on a solicitor own client basis) arising out of, or in any way related to, the use of or inability to use the data. ©The State of Queensland, 2022.

APPENDIX C

Land Resource Report



ENSHAM LIFE OF MINE EXTENSION PROJECT - ZONES 2 AND 3

Land Resources

Prepared for:

Ensham Resources Pty Ltd
Level 9/175 Eagle Street
Brisbane QLD 4000

SLR Ref: 620.30686.00000-R01
Version No: -v1.0
March 2022



PREPARED BY

SLR Consulting Australia Pty Ltd
ABN 29 001 584 612
Level 16, 175 Eagle Street
Brisbane QLD 4000 Australia
(PO Box 26 Spring Hill QLD 4004)
T: +61 7 3858 4800
E: brisbane@slrconsulting.com www.slrconsulting.com

BASIS OF REPORT

This report has been prepared by SLR Consulting Australia Pty Ltd (SLR) with all reasonable skill, care and diligence, and taking account of the timescale and resources allocated to it by agreement with Ensham Resources Pty Ltd (the Client). Information reported herein is based on the interpretation of data collected, which has been accepted in good faith as being accurate and valid.

This report is for the exclusive use of the Client. No warranties or guarantees are expressed or should be inferred by any third parties. This report may not be relied upon by other parties without written consent from SLR.

SLR disclaims any responsibility to the Client and others in respect of any matters outside the agreed scope of the work.

EXECUTIVE SUMMARY

SLR Consulting Pty Ltd (SLR) was commissioned by Ensham Resources Pty Ltd to complete a Soil and Land Resource Assessment (the Assessment) of the Ensham Life of Mine Extension Project – Zones 2 and 3 (the Project) at Ensham Mine (Ensham), which is the subject of an environmental authority (EA) Amendment application.

The scope of the Assessment included a soil survey, interpretation of soil testing results and a geochemical waste rock assessment to determine the following:

- Soil types
- Land suitability assessment
- Soil resources assessment (topsoil and subsoil volumes)
- Description of soil qualities (erosion risk, dispersion and salinity risks), and
- Waste rock acid generating potential, metal abundance and leachability.

Within the Project, a total of five Soil Map Units (SMU) were identified based on the dominant Australian Soil Classification (ASC) soil types. The majority soil type within the Project is a Eutrophic Brown Dermosol, which has been split into 2A and 2B to represent the changes between Zone 2 and Zone 3. The other SMUs are made up of smaller areas of Magnesic Brown Kandosols, Clastic Rudosols and Crusty Brown Vertosols.

The land suitability assessment indicates the Project consists of:

- Class 4 (marginal land with severe limitations) and Class 5 (unsuitable land) for cropping, and
- Class 2 (suitable land with minor limitations), Class 3 (suitable land with moderate limitations) and Class 5 for grazing.

The main limitations of the soil in the Project were soil wetness (w) and soil water availability (m). There will be no decrease in quality of suitability class land within the Project resulting from the four proposed flares post-rehabilitation.

The agricultural land assessment indicates the Project consists of:

- Class A2 (a wide range of crops and/or horticultural crops)
- Class C2 (grazing native pastures on with lower fertility soils than C1), and
- Class C3 (light grazing of native pastures and land suited to forestry).

The Project will require the addition of four flares in already cleared areas. There will be no decrease in quality of agricultural land within the Project resulting from the proposed flares post-rehabilitation.

Soil resources include a topsoil volume of 1,594,400 m³ and a subsoil volume of 3,825,600 m³. It is noted that no soil stripping is proposed as part of the Project as no land is required to be cleared. Therefore, no changes in soil resource volume will occur.

The waste rock assessment indicates:

- The waste rock is non-acid generating and has significant buffering capacity

EXECUTIVE SUMMARY

- The geochemical abundance index results showed very low and depleted (compared to median crustal concentrations) metal concentrations for most metals
- Leachability of metals showed several exceedances of guideline values for aquatic ecosystem protection, particularly aluminium and vanadium. Such exceedances are unlikely at the reported pH and are likely to be the result of colloid transport through the 0.45µm filter membrane
- The waste rock will be buried within the open cut pits and results indicate any adverse impact from metals concentration and leachability is unlikely, and
- The estimated volume of waste rock from the proposed Project over the life of the mine is 45,600 m³ in total, which is approximately less than 0.13% of total approved waste rock volumes (36 million m³) currently approved for the rehabilitation of open cut Pit C and Pit D. At less than 0.13% of total approved rock volume for Pit C and Pit D, it is not envisaged that this addition would impact the approved final landform outcomes in Appendix 3 of the EA.

CONTENTS

1	INTRODUCTION	9
1.1	Purpose	9
1.2	Relevant Guidelines and Standards	11
1.3	Assessment Considerations	11
1.3.1	Mine Spoil Areas.....	11
1.3.2	Flare Exclusion Areas	11
2	METHODOLOGY	12
2.1	Desktop Review of Geology, Geomorphology, Land Systems and Soils.....	13
2.2	Regional Planning Interests Act	13
2.3	Field Assessment and Sampling Program	16
2.3.1	Soil Field Program.....	16
2.3.2	Waste Rock Characterisation	18
2.4	Land Classification Systems	21
2.4.1	Land Suitability Class	21
2.4.2	Agricultural Land Class	21
3	EXISTING ENVIRONMENT.....	22
3.1	Climate	22
3.2	Geology	22
3.3	Topography and Hydrology	22
3.4	Vegetation and Land Use.....	24
3.5	Land Systems	24
3.6	Waste Rock Source	26
3.7	Previous Investigations	26
3.7.1	Hansen Consulting.....	26
3.7.1.1	Soil Classification	26
3.7.1.2	Land Suitability	26
3.7.1.3	Agricultural Land	27
3.7.2	GT Environmental.....	27
3.7.2.1	Soil Classification	27
3.7.2.2	Agricultural Land	28
3.7.3	Waste Rock Characterisation	28
3.7.3.1	URS 2005	28
3.7.3.2	URS 2015	28
4	SOIL SURVEY RESULTS	29

CONTENTS

4.1	Soil Classification and Description	29
4.1.1	Vertosols.....	29
4.1.2	Dermosols	29
4.1.3	Kandosols	30
4.1.4	Rudosols	30
4.2	Soil Map Units.....	30
4.2.1	Soil Map Unit 1	34
4.2.1.1	Description	34
4.2.1.2	Location.....	34
4.2.1.3	Land Use	34
4.2.1.4	Management Considerations	34
4.2.2	Soil Map Unit 2A.....	34
4.2.2.1	Description	34
4.2.2.2	Location.....	34
4.2.2.3	Land Use	34
4.2.2.4	Management Considerations	34
4.2.3	Soil Map Unit 2B.....	35
4.2.3.1	Description	35
4.2.3.2	Location.....	35
4.2.3.3	Land Use	35
4.2.3.4	Management Considerations	35
4.2.4	Soil Map Unit 3	35
4.2.4.1	Description	35
4.2.4.2	Location.....	35
4.2.4.3	Land Use	35
4.2.4.4	Management Considerations	35
4.2.5	Soil Map Unit 4	36
4.2.5.1	Description	36
4.2.5.2	Location.....	36
4.2.5.3	Land Use	36
4.2.5.4	Management Considerations	36
4.3	Erosion Potential.....	36
4.4	Waste Rock Characterisation.....	37
4.4.1	Waste Rock Characterisation	37
4.4.2	Acid Producing Potential	37
4.4.3	Geochemical Abundance Index (GAI)	38

CONTENTS

4.4.4	Waste Rock Leachate Characteristics	41
4.5	Soil Resources	43
5	SOIL AND LAND RESOURCE IMPACT ASSESSMENT	43
5.1	Land Suitability Methodology	44
5.2	Pre-Mining Land Suitability Results	45
5.2.1	Pre-Mining Land Suitability for Cropping	45
5.2.2	Pre-Mining Land Suitability for Grazing	45
5.2.3	Post-Mining	45
5.3	Agricultural Land Class Assessment	48
5.4	Agricultural Land Class Results	49
5.4.1	Pre-Mining	49
5.4.2	Post-Mining	49
6	CONCLUSIONS	51
7	REFERENCES	53

DOCUMENT REFERENCES

TABLES

Table 1	Approximate Flare Locations	11
Table 2	Field Assessment Parameters	18
Table 3	Sampling frequency based on waste rock tonnage (MEND, 2009)	18
Table 4	Average Monthly Climate Data for Emerald Airport	22
Table 5	Land Systems in Project Area	24
Table 6	SMU Soil Types	30
Table 7	Field Investigation Sites	31
Table 8	Summary of results for 12 waste rock samples	38
Table 9	Median crustal abundance for trace metals (Berkman and Ryall, 1976; Bowen, 1979)	39
Table 10	GAI summary of 12 waste rock samples	40
Table 11	ASLP results of the 12 drill core waste rock samples compared to the aquatic ecosystem 95% protection level	42
Table 12	Available Topsoil Resource Summary	43
Table 13	Available Subsoil Resource Summary	43
Table 14	Land Suitability Classes	44
Table 15	Pre- and Post-Mining Cropping Land Suitability Class	46
Table 16	Pre- and Post-Mining Grazing Land Suitability Class	46
Table 17	Agricultural Land Classes	48
Table 18	Pre- and Post-Mining Agricultural Land Classes	49

CONTENTS

FIGURES

Figure 1	Project Regional Setting	10
Figure 2	Project Location.....	12
Figure 3	Priority Agricultural Area.....	14
Figure 4	Strategic Cropping Area	15
Figure 5	Field Sampling Plan	17
Figure 6	Zone 2 Waste Rock Characterisation Boreholes	19
Figure 7	Zone 3 Waste Rock Characterisation Boreholes	20
Figure 8	Topography & Hydrology	23
Figure 9	Land Systems.....	25
Figure 10	Soil Map Units	32
Figure 11	Sample Sites & ASC Soil Types.....	33
Figure 12	Acid producing potential characteristics of total 12 waste rock samples	38
Figure 13	Cropping and Grazing Land Suitability Class	47
Figure 14	Agricultural Land Classes.....	50

APPENDICES

Appendix A	Soil Laboratory Certificates of Analysis
Appendix B	Detailed Profile Descriptions
Appendix C	Check Site Descriptions
Appendix D	Emerson Aggregate Test Ratings
Appendix E	Land Suitability and Agricultural Land Classification

1 Introduction

SLR Consulting Pty Ltd (SLR) was commissioned by Ensham Resources Pty Ltd to complete a soil and land resource assessment (the Assessment) of the Ensham Life of Mine Extension Project – Zones 2 and 3 (the Project) at Ensham Mine (Ensham), which is the subject of an environmental authority (EA) Amendment application. The Project is located approximately 35 km east of Emerald.

The Project aims to extend the life of the existing underground operations at Ensham by two years, with coal production planned to continue at a rate of approximately 4.5 million tonnes per annum (Mtpa). The total area of Zones 2 & 3 covers approximately 603 hectares (ha), and includes two zones:

- Zone 2: partially includes existing leases ML 70326, ML 70365, and ML 7459, and
- Zone 3: partially includes existing leases ML 7459 and ML 70366 .


The regional setting of the Project is depicted in **Figure 1**.

1.1 Purpose

The purpose of the Assessment is to provide an assessment of impacts to the soil and land resources within the Project as a result of surface disturbance. The Assessment included a soil survey, interpretation and waste rock geochemical characterisation to summarise the following:

- Soil types
- Land suitability assessment
- Soil resources assessment
- Waste rock acid generating potential, metal abundance and leachability, and
- Description of soil qualities (erosion risk, dispersion and salinity risks).

Gordon Geotechniques Pty Ltd was commissioned by Ensham to undertake subsidence modelling to assess the potential impacts of the Project (Idemitsu Australia, 2022 – Appendix B), which includes a peer review letter (Idemitsu Australia, 2022 – Appendix B-1) and prepare a Subsidence Management Plan (Idemitsu Australia, 2022 – Appendix C), which includes a peer review letter (Idemitsu Australia, 2022 – Appendix C-1). Results indicated low levels of subsidence, typically less than 35 mm, are predicted for the Project. Real-Time Kinematic Global Positioning System monitoring indicates subsidence levels of less than 10 mm above underground mining operations (Gordon Geotechniques Pty Ltd, 2022). Given this level of subsidence (less than 10 mm) and compared to natural soil movement of approximately 50 mm (IESC, 2015), subsidence will not impact land resources for the Project. Accordingly, subsidence is not considered further in this Assessment.



Coordinate System: GDA 1994 MGA Zone 55
 Scale: 1:1,000,000 at A4
 Project Number: 620.30686
 Date: 07-Mar-2022
 Drawn by: JG

— Main Roads
 [Red Box] Project Location

620.30686 ENSHAM SOIL SURVEY

Regional Setting



FIGURE 1

1.2 Relevant Guidelines and Standards

The following guidelines and standards were used for the Soil and Land Resource Assessment:

- *Regional Land Suitability Frameworks for Queensland*, Department of Natural Resources and Mines and the Department of Science, Information Technology, Innovation and the Arts (DNRM and DSITI), 2013
- *Australian Soil Classification – Third Edition*, Isbell and National Committee on Soil and Terrain, 2021
- *Guidelines for Surveying Soil and Land Resources (2nd edition)*, McKenzie et al., 2008
- *Australian Soil and Land Survey Field Handbook (3rd edition)*, National Committee on Soil and Terrain, 2009
- *Guidelines for Agricultural Land Evaluation in Queensland (2nd edition)*, Department of Natural Resources and Mines and the Department of Science, Information Technology, Innovation and the Arts (DNRM and DSITI), 2015, and
- *Queensland Soil and Land Resource Survey Information Guideline (Version 2)*, Department of Resources, 2021.

1.3 Assessment Considerations

1.3.1 Mine Spoil Areas


The north eastern section of Zone 2 and the northern section of Zone 3 reside inside a combined mine spoil area of approximately 61 ha. The mine spoil area was not included in the interpretation of soil types and resources as it cannot be categorised as the natural baseline soil. Therefore, the total area of the Project included in the interpretation of soil types and resources is 542 ha. The mine spoil area is depicted in **Figure 2**.

1.3.2 Flare Exclusion Areas

No new infrastructure is required for the Project with the exception of four flares, proposed to be constructed within locations already approved for disturbance in pre-cleared areas. The construction of the flares will include an exclusion area of approximately 80 by 20 m, and, as a conservative approach for the Assessment, this exclusion area will be considered the maximum construction footprint, totalling 0.64 ha. **Table 1** summarises the flare locations and maximum construction footprint associated with each flare are depicted in **Figure 1**.

Table 1 Approximate Flare Locations

Flare	Zone	Area (ha)	Coordinates (GDA94 Zone 55)	
			mE	mN
1	Zone 2	0.16	649917	7407667
2	Zone 2	0.16	651109	7407285
3	Zone 3	0.16	648985	7399439
4	Zone 3	0.16	649286	7398580
Total		0.64	-	-



Coordinate System: GDA 1994 MGA Zone 55
 Scale: 1:70,000 at A4
 Project Number: 620.30686
 Date: 07-Mar-2022
 Drawn by: JG



- Roads
- Flare Exclusion Areas (80m x 20m)
- Zone 2
- Zone 3
- Mine Spoil Area
- Mining Leases

620.30686 ENSHAM SOIL SURVEY

Project Location

FIGURE 2

2.1 Desktop Review of Geology, Geomorphology, Land Systems and Soils


A desktop assessment was undertaken to establish background information on the soil and land resources within the Project. This included a review of:

- *Land of the Isaac-Comet Area, Queensland*, Gunn and Fitzpatrick, 1967
- *Terrain, Soils & Land Capability Assessment*, Hansen Consulting, 2006
- *Desktop Soils and Land Suitability Assessment*, GT Environmental, 2020
- *Geological Survey of Queensland: Map Sheet SF55-15 (Ensham)*, Geological Survey of Qld, 1969
- Site LIDAR data provided by Ensham Resources Pty Ltd, 2022
- *Climate Data Online (Emerald Airport - Station 035264)*, Bureau of Meteorology, 2022
- Queensland Land Use Mapping Program, 2017
- Satellite imagery accessed via Google Maps and Nearmap, 2021, and
- *Strategic Cropping Land (SCL) Trigger Map*, Department of Resources, 2021.

2.2 Regional Planning Interests Act

The *Regional Planning Interests Act of 2014* (RPI Act) identifies and protects areas of regional interest from inappropriate resource activity or regulated activity. Areas of regional interest identified in the RPI Act include priority agricultural areas (PAA), priority living area (PLA), strategic environmental area (SEA) and strategic cropping area (SCA). SCA consists of strategic cropping land (SCL) as identified in the SCL trigger map. A PAA is an area deemed as highly productive agricultural land by the relevant regional council under a regional plan.

The Project intersects both PAA and SCA, as shown in **Figure 3** and **Figure 4**. The status of land identified as PAA and SCA within the Project will not be challenged in this Assessment and will be considered as mapped.



Coordinate System: GDA 1994 MGA Zone 55
 Scale: 1:70,000 at A4
 Project Number: 620.30686
 Date: 22-Apr-2022
 Drawn by: JG





- Flare Exclusion Areas (80m x 20m)
- Priority Agricultural Area
- Zone 2
- Zone 3
- Mining Leases
- Underground Mine Workings
- Approved Underground Workings

620.30686 ENSHAM SOIL SURVEY

Priority Agricultural Area

FIGURE 3



Coordinate System: GDA 1994 MGA Zone 55
 Scale: 1:70,000 at A4
 Project Number: 620.30686
 Date: 22-Apr-2022
 Drawn by: JG



- Flare Exclusion Areas (80m x 20m)
- Strategic Cropping Land
- Zone 2
- Zone 3
- Mining Leases
- Underground Mine Workings
- Approved Underground Workings

620.30686 ENSHAM SOIL SURVEY

**Strategic Cropping Area via
Strategic Cropping Land Trigger Map**

FIGURE 4

2.3 Field Assessment and Sampling Program

2.3.1 Soil Field Program

The soil field program was designed as an integrated free survey, which assumes that land characteristics are interdependent and tend to occur in correlated sets (NCST, 2008). Preliminary survey points were located based on the desktop assessment and refined during the field survey according to the site observations and landform interpretation to target representative soil type identification and boundary delineation. Bore holes were excavated using a hand auger or soil corer to a maximum depth of 1.0 m or upon encountering refusal e.g., consolidated rock. Soil profile logging was undertaken in the field using SLR electronic soil data sheets, including Global Positioning System (GPS) recordings and photographs of the landforms and soil profiles. For those soils which were analysed in the laboratory, certificates of analysis are shown in **Appendix A**. **Appendix B** and **Appendix C** present the detailed and check site descriptions respectively.



Three types of observations were used for this Soil and Land Resource Assessment:

- Detailed sites – Excavated sites that allow for the identification of physical and chemical factors which characterise the major pedological features of the soil profile and allow the characterisation of an associated map unit
- Analysed sites – Detailed sites from which soil samples are collected and sent to a National Association of Testing Authorities (NATA) Australia accredited laboratory for analysis, and
- Check sites - Observations examined in sufficient detail to allocate the site to a specific soil type.

A total of 16 detailed sites (prefix BH) were assessed, with soil samples taken from each site. An additional 26 check sites (prefix CH) were assessed producing a survey density of 1 site per 14 ha, which satisfies a cartographic scale of 1:25,000 in accordance with the *Guidelines for Surveying Soil and Land Resources* (2nd edition), McKenzie et al., 2008. Laboratory analysis was undertaken for 11 sites, representing 68.75% of the 16 detailed sites. Typical sample depths were 0-10, 20-30, 50-60 and 90-100 centimetres (cm). The frequency of the detailed, analysed and check sites are in accordance with the relevant guidelines (McKenzie et al., 2008). Locations of detailed, check and analysed sites are depicted in **Figure 5**.

Laboratory analysis was performed by Environmental Analysis Laboratory (EAL) at the Southern Cross University Lismore, a laboratory with NATA accreditation for the analyses conducted. The soil testing suite included:

- pH (1:5 water)
- Electrical conductivity (EC)
- Cation exchange capacity (CEC)
- Exchangeable sodium percentage (ESP)
- Colour (Munsell)
- Particle size analysis (PSA), and
- Emerson aggregate test (EAT).



Coordinate System: GDA 1994 MGA Zone 55
 Scale: 1:50,000 at A4
 Project Number: 620.30686
 Date: 23-Feb-2022
 Drawn by: JG



- Detailed Sites
- Check Sites
- ⊕ Analysed Sites
- Flare Exclusion Areas (80m x 20m)
- Zone 2
- Zone 3
- Mining Leases

620.30686 ENSHAM SOIL SURVEY

Field Sampling Plan

FIGURE 5

Soil salinity in the laboratory analysed samples was determined through the measurement of EC in a 1:5 soil:water suspension. These values were converted to the EC of a saturated extract (EC_e) based on soil texture.

Soil profiles were assessed in accordance with the *Australian Soil and Land Survey Field Handbook* (NCST, 2009) soil assessment procedures. Detailed soil profile descriptions were recorded covering the major parameters provided in **Table 2**. The soil type classification was assessed through the *Australian Soil Classification – Third Edition* (Isbell, 2021).

Table 2 Field Assessment Parameters

Detailed Field Assessment Parameters	
Horizon depth	Pan presence and form
Field texture grade	Permeability and drainage
Field colour (Munsell colour chart)	Field pH
Pedality structure, grade and consistence	Field moisture
Soil fabric and stickiness	Surface condition
Coarse fragments (abundance and size)	Landform pattern / element
Mottles (amount, size and distinctiveness)	Current land use
Segregations (abundance, nature, form and size)	Vegetation

2.3.2 Waste Rock Characterisation

A total of 12 additional waste rock samples were collected from drill cores from the exploration phase of the Project by an Ensham geologist. The samples were tested for their Acid Mine Drainage (AMD) characteristics, Geochemical Abundance Index (GAI) of metals within the solid waste and Australian Standard Leaching Procedure (ASLP) leachability of metals. Based on the volumes of waste rock to be generated by the Project, the waste rock characterisation frequency is compliant with the guidelines (MEND, 2009), as shown in **Table 3**. Location of drill cores of the waste rock analysed for Zone 2 and Zone 3 are shown in **Figure 6** and **Figure 7**, respectively.

Table 3 Sampling frequency based on waste rock tonnage (MEND, 2009)

Tonnage of Unit (metric tonnes)	Minimum Number of Samples
<10,000	3
<100,000	8
<1,000,000	26
<10,000,000	80

The acid mine drainage (AMD) waste rock characterisation assesses the Net Acid Generation (NAG) potential based on the total sulphur concentrations, which includes sulphur from both, reactive acid producing sulphides and unreactive non-acid producing sulphates. As a result, the Net Acid Generating Potential may overestimate the actual acid producing potential of a material.

H:\Projects\SLR\620.30686\620.30686_000000 Soils and Land Assessment\06 SLR Data\01 CAD\GIS\GIS\Soils\620.30686 F08 Waste Rock Characterization Zone 2.mxd



0 250 500 m

Coordinate System: GDA 1994 MGA Zone 55

Scale: 1:24,000 at A4

Project Number: 620.30686

Date: 08-Mar-2022

Drawn by: JG

⊕ Water Rock Boreholes

Zone 2

Mining Leases

Mine Spoil Area

620.30686 ENSHAM SOIL SURVEY

Waste Rock Characterization
Zone 2



FIGURE 6

To evaluate the potential for overestimation of acid generation, all samples analysed as part of this assessment, were also tested for HCl-extractable sulfur (S_{HCl}). This method determines soluble sulphate from gypsum and a large proportion of iron and aluminium hydroxysulphate compounds (for example jarosite, natrojarosite, schwertmannite), which are generally insoluble in the surface environment. This method determines also some sulphur from organic matter, but not pyrite sulphur.

Waste rock leachate results were compared to water quality parameters with regards to the toxicant default guideline values for water quality in aquatic ecosystems (95% protection level) of the Australian & New Zealand Guidelines for Fresh & Marine Water Quality (Australian Government, 2022)

2.4 Land Classification Systems

The information reviewed and collected as part of the desktop and field assessments was used to determine land classifications. The land classification systems used for the assessment are:

- Land suitability class, and
- Agricultural land class.

These classification systems are applied to the assessment to consider specific and broad land uses. These systems and their purpose for assessing impacts to land resources are summarised in the following sections.

2.4.1 Land Suitability Class

The land suitability classification was applied across the Project in accordance with the *Regional Land Suitability Frameworks for Queensland* (DSITI & DNRM, 2015). This scheme uses the biophysical features of the land and soil to derive detailed rating tables for a range of land and soil hazards. The scheme consists of eight limitations that classify the land based on the severity against the suitability subclasses for various land management options.

The suitability framework provides details for assessing which crops are suitable for individual mapped areas of land or soil and defines land suitable for grazing. Each hazard (refer **Section 6**) was assessed against a set of criteria tables described in the framework, with each hazard ranked from 1 (most suitable) through to 5 (least suitable) with the overall ranking of the land determined by its most significant limitation.

2.4.2 Agricultural Land Class

Agricultural land classification follows a hierarchical scheme that allows the presentation of interpreted land evaluation data to indicate the location and extent of agricultural land that can be used sustainably for a wide range of land uses with minimal land degradation. Three broad classes of agricultural land and one non-agricultural land class are identified in the *Agricultural Land Class System* (DSITI & DNRM, 2015).

3 Existing Environment

3.1 Climate

The nearest operational meteorological station is Emerald Airport (BOM Station 035264), located approximately 40 km southwest of the Project. The annual average rainfall from 1981 to present is 543.2 mm with most rain occurring between December and February. The annual mean maximum temperature is 29.9°C and the annual mean minimum temperature is 16.4°C. Average monthly rainfall and temperature for Emerald Airport is presented in **Table 4**.

Table 4 Average Monthly Climate Data for Emerald Airport

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Annual
Mean Rainfall (mm)	83.0	85.8	59.6	28.3	17.9	30.0	16.6	19.9	25.1	44.4	55.8	80.0	543.2
Mean Maximum Temperature (°C)	34.6	33.8	32.8	30.0	26.4	23.4	23.5	25.6	29.2	32.0	33.5	34.5	29.9
Mean Minimum Temperature (°C)	22.3	22.1	20.5	17.0	13.1	10.3	9.1	10.1	13.6	17.2	19.6	21.5	16.4

Source: Bureau of Meteorology



3.2 Geology

A review of the surface geology Geological Survey of Queensland Emerald Region Sheet no. SF55-15 (GSQ, 1969) showed that the Project is underlain by:

- River and Floodplain Deposits from the Quaternary Alluvium consisting of clay, silt, sand and gravel
- Undifferentiated Cainozoic Soil cover including soil, sand, siliceous and ferruginous gravel, and
- Argillaceous sandstone, laterised sediments, laterite, claystone, siltstone, sandstone and pebbly sandstone from the Tertiary Emerald Formation.

3.3 Topography and Hydrology

The Project lies with the Fitzroy Basin and within Nogoa River sub-basin. Watercourses within the Project are presented in **Figure 8**. Alongside minor tributaries, the Nogoa River traverses through Zone 2. This is perennial, which is largely attributable to controlled releases from Fairbairn Dam.



A review of the LiDAR data available shows the topography of Zone 2 has elevations ranging from approximately 148 mAHD (Australian Height Datum) in the south-western section, to a 266 mAHD escarpment in the north-eastern section. In Zone 3, elevations range from 152 mAHD in the northern section to 168 mAHD in the southern section. Areas of unrehabilitated open cut spoil piles range to an elevation of 200 mAHD, 30m above the surrounding landform and open cut excavations are up to 30 m below natural landform.

3.4 Vegetation and Land Use

The Project is used for livestock grazing, with some areas of remnant vegetation and a small portion incorrectly mapped as cropping (QLUMP, 2017). The southernmost portion of Zone 2 has been planted to *Leucaena* for stock, which transitions into *Eucalyptus* spp. fringing the Nogoa River (SLR, 2021). The centre portion is predominantly used for grazing and the northern portion is made up of remnant vegetation including remnant *Acacia* and *Eucalyptus* spp. woodlands, with small patches of Brigalow woodland also having been retained across Zone 2. Zone 3 has been highly modified and is extensively cleared, supporting no remnant vegetation communities, with a drainage channel containing wetland plants. The predominant land uses within the Project historically consist of grazing and mining (QLUMP, 2017).


3.5 Land Systems

Four land systems occur within the Project (Gunn and Fitzpatrick, 1967), with the majority dominated by the Humboldt land system described as blackbutt and brigalow on weathered clay plains, with a mix of texture-contrast and cracking clay soils. This land system makes up most of Zone 2, with minor land systems consisting of Comet in the southern section and Durrandella and Blackwater in the northern section. The Humboldt land system comprises the entirety of Zone 3. **Table 5** below describes the land systems and areas across the Project (including mine spoil areas (603 ha total)) and is depicted in **Figure 9**.

Table 5 Land Systems in Project Area

Land System	Land System Description	Area (ha)	Project %
Comet	Alluvial plains with brigalow and cracking clay soils, often flooded, along major streams.	51	8
Humboldt	Blackbutt and brigalow on weathered clay plains occurring in most parts of the area; texture-contrast and cracking clay soils.	419	70
Blackwater	Brigalow plains and cracking clay soils on weathered Tertiary clay and older rocks along the central axis of the area.	56	9
Durrandella	Hills with lancewood and narrow-leaved ironbark on weathered Tertiary and Permian rocks in the north-west, centre, and south-east; shallow rocky soils.	77	13
Total		603	100

\\au.slr.local\corporate\Projects\SLR\620-BNE\620-BNE\620-30686-00000 Soils and Land Assessment\06 SLR Data\01 CAD\GIS\GIS\Soils\62030686_F07 Land Systems.mxd



Coordinate System: GDA 1994 MGA Zone 55
Scale: 1:50,000 at A4
Project Number: 620.30686
Date: 23-Feb-2022
Drawn by: JG

- Zone 2
- Zone 3
- Mining Leases

- Land Systems**
- Blackwater
 - Comet
 - Durrandella
 - Humboldt

620.30686 ENSHAM SOIL SURVEY

Land Systems



3.6 Waste Rock Source

The coal seam at Ensham is part of the Permian age Rangal Coal Measures. The Rangal Coal Measures are characteristically non-marine sediments and low in sulphur, essentially deposited as one homogeneous unit. With regards to the waste rock characterisation, the coal seam and associated interburden/overburden may be accompanied by low concentrations of primary sulphides, mainly pyrite.

3.7 Previous Investigations

3.7.1 Hansen Consulting

Hansen Consulting (Hansen, 2006) completed a soils and land capability assessment for Ensham Resources Pty Ltd to assist in planning for a mine expansion program (the Hansen Report). The Hansen Report assessed the middle and northern portions of Zone 3 and the north-eastern portion of Zone 2. Field investigations informed a soil survey, classifying soil types and their properties, estimating volumes of topsoil resources available and assessed the agricultural land suitability.

3.7.1.1 Soil Classification

The Hansen Report classified soil types based upon the *Australian Soil Classification* (ASC) (1996) into the following groups:

- Leptic Rudosols which occur to the north-west of Zone 2
- Petroferric Red Kandosols-Tenosols, Acidic Mesotrophic Red Kandosols and Haplic Mesotrophic Red Ferrosols which occur to the north-west of Zone 2 and the southern boundary of Zone 3
- Colluvic Clastic Rudosols, Regolithic Chernic Tenosols or Acidic Brown Clastic-Leptic Rudosols across the western boundary of Zone 2
- Sodic Pedaric Brown Dermosols Uniform (non-cracking) clay soils which occur in the south of Zone 2 as well as the centre and south of Zone 3, and
- Endohypersodic, or Epipedal Black, Grey or Brown Vertosols which occur at the southern boundary of Zone 2 and across the centre and north of Zone 3.

3.7.1.2 Land Suitability

The Hansen Report described the following land suitability classes:

- Class 1 indicates with negligible limitations to sustaining the intended land use
- Class 2 with minor limitations
- Class 3 with moderate limitations
- Class 4 is classified as marginal land, and
- Class 5 is unsuitable land.

The method for the land suitability classification was adapted from the guidelines for agricultural land evaluation published by the Department of Primary Industries (DPI) (1990) with reference to the publication by Shields and Williams (1991) for a land resources survey in the Kilcummin area of Central Queensland.

The land suitability relevant to the Project was classed as:

- Class 4 and 5 for cropping and grazing in the north and western section of Zone 2, and
- Class 2, 3, 4 and 5 for cropping and Class 1, 2 and 3 for grazing in the northern section of Zone 3

These classes indicate that the north and western land in Zone 2 might be unsuitable for cropping. However, land in the north of Zone 3 could be suitable for both cropping and grazing purposes, particularly the northernmost part of the Zone.

3.7.1.3 Agricultural Land

The Hansen Report classified the land into the following classes:

- Class A described as crop land that is suitable for crops with nil to moderate limitations to production
- Class B described as limited crop land that is marginal for crops due to severe limitations and suitable for pastures. Engineering or agronomic improvements may be required before this land is suitable for cropping
- Class C described as pasture land suitable only for improved or native pastures, continuous cultivation precluded; some areas may tolerate short periods of ground disturbance for pasture establishment, and
- Class D described as non-agricultural land and land not suitable for agricultural uses due to extreme limitations including steep slopes, shallow rocky soils or poor drainage.

The method for the land suitability classification was assessed based on the Guidelines for Agricultural Land Evaluation in Queensland published by the DPI (1990) and in accordance with State Planning Policy 1/92: Development and the Conservation of Good Quality Agricultural Land prepared by the DPI and the Queensland Department of Housing Local Government Planning (DH&LGP) (1993).

The agricultural land suitability relevant to the Project was classed as:

- The majority of land in the north and western section of Zone 2 was described as Class C, with small areas of D identified, and
- Land in the north section of Zone 3 was described as Class A, B and, with a very small section of Class D.

Lands in north and western Zone 2 would be mostly suited to pastureland, whereas Zone 3's northern section would be more suited to both cropping and pastureland.

3.7.2 GT Environmental

GT Environmental (GT Environmental, 2020) conducted a desktop assessment on behalf of Ensham Resources Pty Ltd to assess the potential impacts of the Project on soils and land suitability values and provided a baseline assessment of the soil and land suitability.

3.7.2.1 Soil Classification

The majority of soil types were classified in accordance with the ASC (2002) into the following groups:

- Endohypersodic and Epipedal Black, Grey or Brown Vertosols across the southern area of Zone 2 and across the majority of Zone 3

- Sodic Pedaric Brown Dermosols across the central area of Zone 2 and the southern portion of Zone 3, and
- Acidic and Leptic Rudosols across the northern portion of Zone 2.

3.7.2.2 Agricultural Land

The method for the agricultural land suitability classification was assessed in accordance with State Planning Policy 1/92: Development and the Conservation of Good Quality Agricultural Land and rated in terms of the DH&LGP (1993).

The land suitability was classed as:

- Class 4 for cropping and Class 3 and 4 for grazing for the majority of the southern and middle portion of Zone 2 with a minor belt of Class 3 cropping and Class 2 for grazing along a tributary that feeds the Nogoa River, dividing the southern and middle portions
- Class 4 and 5 for cropping and Class 3, 4 and 5 for grazing in the northern portion of Zone 2, and
- Class 4 for cropping and grazing in Zone 3.

These classes indicate the land in the Project might be unsuitable for cropping. However, some land could be suitable for grazing purposes.

3.7.3 Waste Rock Characterisation

Previous waste rock characterisations at Ensham investigated 66 overburden and reject samples in 2005 (URS, 2005) and 34 samples from drill holes that intersected the roof, interburden and floor of the then to be mined coal seam (URS, 2015).

3.7.3.1 URS 2005

Of the 2005 samples 88% of samples had a total sulfur content of less than or equal to 0.1%, the remaining 12% had a total sulfur content of between 0.1 to 0.75%, none of which are considered PAF. All samples had a negative net acid producing potential (NAPP), ranging from -9 kg H₂SO₄/t to -215 kg H₂SO₄/t (average for overburden -42 kg H₂SO₄/t and potential reject -46 H₂SO₄/t). This means that those samples were all non-acid forming (NAF).

3.7.3.2 URS 2015

Of the 2015 samples all had a negative NAPP, ranging from -1 kg H₂SO₄/t to -119.8 kg H₂SO₄/t (average -35.7 kg H₂SO₄/t). This means that those samples were all NAF.

4 Soil Survey Results

4.1 Soil Classification and Description

The field assessment and subsequent laboratory analysis indicated a total of four soil orders within the Project according to the *Revised Australian Soil Classification* (Isbell, 2021). These included Vertosols, Dermosols, Kandosols and Rudosols. Representative profile descriptions for all detailed profile descriptions are shown in **Appendix B** and check site descriptions are shown in **Appendix C**.

4.1.1 Vertosols

These are soils with the following:

- A clay field texture or 35% or more clay throughout the solum except for a thin, surface crusty horizons 0.03 m or less thick
- When dry, open cracks occur at some time in most years. These are at least 5 mm wide and extend upward to the surface or to the base of any plough layer, peaty horizon, self-mulching horizon, or thin, surface crusty horizon, and
- Slickensides and/or lenticular peds occur at some depth in the solum.

The Vertosols were further classified into Crusty Brown Vertosols.

The Vertosols on site generally consisted of brown medium clay A horizons (topsoil) with moderate structure, overlying a medium clay B2 horizon with strong angular blocky structure. The topsoil showed strongly alkaline, non-sodic and low saline properties. The B2 horizon generally showed strongly alkaline, sodic and very high saline properties.

4.1.2 Dermosols

These are soils other than Vertosols, Hydrosols and Calcarosols which:

- Have B2 horizons with a structure more developed than weak throughout the major part of the horizon, and
- Do not have clear or abrupt textural B horizons.

The Dermosols were further classified into Eutrophic Brown, Black and Grey Dermosols, Magnesic Brown Dermosols and Dystrophic Red Dermosols. Eutrophic Brown Dermosols were identified as the dominant Dermosol type.

The Dermosols on site generally consisted of grey to black clay loam to light clay to medium clay A horizons (topsoil) with weak to moderate structure, overlying a light medium clay to medium clay B2 horizon with moderate to strong angular to sub angular blocky structure. The topsoil showed neutral, non-sodic and low saline properties, whilst the B2 horizon generally showed moderately alkaline, sodic and low saline properties.

4.1.3 Kandosols

Kandosols are soils other than Hydrosols which lack a clear or abrupt texture contrast between the A horizon and a B horizon, with the major part of the B2 horizon consisting of a massive or weak pedality grade and a maximum clay content which exceeds 15%.

The Kandosols were further classified into Magnesic Brown Kandosols and Dystrophic Brown Kandosols. Magnesic Brown Kandosols were identified as the dominant Kandosol type.

The Kandosols on site generally consisted of brown to black clayey sand to light medium clay A horizons (topsoil) with weak to strong structure, overlying a sandy clay loam to medium clay B2 horizon with weak to strong angular to sub angular blocky structure. The topsoil showed very strongly acidic, non-sodic and very low saline properties, similarly, the B2 horizon generally showed very strongly acidic, non-sodic and very low saline properties.

4.1.4 Rudosols

Rudosols are other soils with negligible (rudimentary), if any, pedologic organisation apart from the minimal development of an A1 horizon or the presence of less than 10% of B horizon material. There is little or no texture or colour change with depth.

Clastic Rudosols were identified as the only Rudosol soil type.

The Rudosols on site generally consisted of sandy clay loam A horizons (topsoil) with weak structure, overlying a sandy clay loam to clayey sand B2 horizon with weak sub angular blocky structure. The topsoil showed strongly acidic, non-sodic and very low saline properties, and similarly the B2 horizon showed strongly acidic, non-sodic and very low saline properties.

4.2 Soil Map Units

Within the Project, a total of five Soil Map Units (SMU) were identified based on the dominant ASC soil types as presented in **Figure 10**. The majority soil type within the Project is a Eutrophic Brown Dermosol, which has been split into 2A and 2B to represent the changes between Zone 2 and Zone 3. The other SMUs are made up of smaller areas of Magnesic Brown Kandosols, Clastic Rudosols and Crusty Brown Vertosols. The dominant and sub-dominant soil types per SMU is shown in **Table 6**.

Table 6 SMU Soil Types

Soil Map Unit	Dominant Soil Type	Sub-Dominant Soil Type	Hectares (ha)	Percentage of Area (%)
1	Crusty Brown Vertosol	-	25	5
2A	Eutrophic Brown Dermosols	Magnesic Brown Dermosols, Dystrophic Red Dermosols	172	32
2B	Eutrophic Brown Dermosols	Eutrophic Black Dermosols, Eutrophic Grey Dermosols, Dystrophic Red Dermosols	182	33
3	Magnesic Brown Kandosols	Dystrophic Brown Kandosols	108	20



Soil Map Unit	Dominant Soil Type	Sub-Dominant Soil Type	Hectares (ha)	Percentage of Area (%)
4	Clastic Rudosols	-	55	10
Total			542	100

SMUs with their associated detailed and check sites are summarised in **Table 7**. **Figure 11** shows sampling sites and ASC soil type.

Table 7 Field Investigation Sites

Soil Map Unit	ASC Dominant Soil Type	Detailed Site	Check Site
1	Crusty Brown Vertosol	BH16	-
2A	Eutrophic Brown Dermosols	BH05, BH08, BH09, BH15	CH07, CH08, CH09, CH10, CH22, CH23, CH24, CH26
2B	Eutrophic Brown Dermosols	BH10, BH11, BH12, BH13, BH14	CH14, CH15, CH16, CH17, CH18, CH19, CH20, CH21
3	Magnesian Brown Kandosols	BH01, BH02, BH03	CH01, CH06, CH11, CH12, CH13
4	Clastic Rudosols	BH04, BH06, BH07	CH02, CH03, CH04, CH05

\\au.slr.local\corporate\Projects\SLR\620-BNE\620-BNE\620-30686-00000 Soils and Land Assessment\06 SLR Data\01 CAD\GIS\GIS\Soils\62030686 F09 Soil Unit Map.mxd



Coordinate System: GDA 1994 MGA Zone 55
Scale: 1:50,000 at A4
Project Number: 620.30686
Date: 23-Feb-2022
Drawn by: JG

- Zone 2
- Zone 3
- Mine Spoil Area
- Mining Leases



Soil Type

- 1 - Crusty Brown Vertosol
- 2A - Eutrophic Brown Dermosol
- 2B - Eutrophic Brown Dermosol
- 3 - Magnesic Brown Kandosol
- 4 - Clastic Rudosol

620.30686 ENSHAM SOIL SURVEY

Soil Map Units





Coordinate System: GDA 1994 MGA Zone 55
 Scale: 1:50,000 at A4
 Project Number: 620.30686
 Date: 15-Mar-2022
 Drawn by: JG



- Detailed Sites
- Check Sites
- ⊕ Analysed Sites
- Flare Exclusion Areas (80m x 20m)
- Zone 2
- Zone 3
- Mine Spoil Area
- Mining Leases

Detailed Soil Units

- RD - Red Dermosol
- BD - Brown Dermosols
- BLD - Black Dermosols
- GD - Grey Dermosols
- BK - Brown Kandosols
- BR - Rudosols
- BV - Brown Vertosols

620.30686 ENSHAM SOIL SURVEY

Sample Sites & ASC Soil Types

FIGURE 11

4.2.1 Soil Map Unit 1

4.2.1.1 Description

SMU 1 soil type included Crusty Brown Vertosols.

4.2.1.2 Location

SMU 1 is located in the southern portion of Zone 2 and comprises approximately 5% or 25 ha of the Project.

4.2.1.3 Land Use

At the time of the field assessment, the land use within SMU 1 was planted with *Leucaena* for cattle grazing.

4.2.1.4 Management Considerations

Generally, the topsoil does not exhibit any characteristics that require any non-standard management practices. The subsoil generally exhibits high alkalinity, high sodicity and high salinity. If the subsoil is exposed and not managed impacts may include:

- Erosion hazards including tunnel erosion
- Impeded soil infiltration and permeability, and
- Soil dispersion leading to soil structure breakdown, increased run-off and increased turbidity run-off.

4.2.2 Soil Map Unit 2A

4.2.2.1 Description

SMU 2A dominant soil type included Eutrophic Brown Dermosols and the subdominant soil types included Magnesic Brown Dermosols and Dystrophic Red Dermosols.

4.2.2.2 Location

SMU 2A is located across the middle portion of Zone 2 and comprises approximately 32% or 172 ha of the Project.

4.2.2.3 Land Use

At the time of the field assessment, the land use within SMU 2A was grazing and patches of remnant vegetation.

4.2.2.4 Management Considerations

Generally, the topsoil does not exhibit any characteristics that require any non-standard management practices. The subsoil generally exhibits high alkalinity, high sodicity and high salinity. If the subsoil is exposed and not managed, in addition to severe agricultural productivity limitations, impacts may include:

- Erosion hazards including tunnel erosion
- Impeded soil infiltration and permeability, and

- Soil dispersion leading to soil structure breakdown, increased run-off and increased turbidity run-off.

4.2.3 Soil Map Unit 2B

4.2.3.1 Description

SMU 2B dominant soil type included Eutrophic Brown Dermosols and the subdominant soil types included Eutrophic Black Dermosols, Eutrophic Grey Dermosols and Dystrophic Red Dermosols.

4.2.3.2 Location

SMU 2B is located across the entire portion of Zone 3 and comprises approximately 33% or 182 ha of the Project.

4.2.3.3 Land Use

At the time of the field assessment, the land use within SMU 2B was grazing.

4.2.3.4 Management Considerations

Generally, the topsoil or subsoil do not exhibit any characteristics that require any non-standard management practices.

4.2.4 Soil Map Unit 3

4.2.4.1 Description

SMU 3 dominant soil type included Magnesic Brown Kandosols and the subdominant soil types included Dystrophic Brown Kandosols.

4.2.4.2 Location

SMU 3 is located in the north-eastern portion of Zone 2 and comprises approximately 20% or 108 ha of the Project.

4.2.4.3 Land Use

At the time of the field assessment, the land use within SMU 3 was grazing and patches of remnant vegetation.

4.2.4.4 Management Considerations

Generally, the topsoil does exhibit highly acidic properties at the surface. The subsoil generally exhibits highly acidic, non-sodic and slightly-saline properties. The subsoil would have minimal impacts if exposed as it does not exhibit any characteristics that require any non-standard management practices.

4.2.5 Soil Map Unit 4

4.2.5.1 Description

SMU 4 soil type included Clastic Rudosols.

4.2.5.2 Location

SMU 4 is located in the north-western portion of Zone 2 and comprises approximately 10% or 55 ha of the Project Area.

4.2.5.3 Land Use

At the time of the field assessment, the land use within SMU 4 was grazing and patches of remnant vegetation.

4.2.5.4 Management Considerations

The topsoil and subsoil both exhibit strongly acidic properties. The non-uniformity and lack of structure typical of this soil types means impacts to management may include:

- Erosion hazards including tunnel erosion
- Impeded soil infiltration and permeability, and
- Soil dispersion leading to soil structure breakdown, increased run-off and increased turbidity run-off.

4.3 Erosion Potential

An Emerson Aggregate Test (EAT) semi-quantitatively classifies the coherence of soil aggregates in water to provide an indication of dispersive properties and susceptibility to erosion. The ratings are based on a hierarchical class system where a rating of 1 being the most dispersive and 8 being non-dispersive.

Approximately 64% of the analysed sites have topsoil with moderately high to high potential for dispersion and erosion, having EAT ratings of 2 and 3. The remaining 36% analysed topsoil sites have an EAT rating of 4, which indicates a negligible potential for dispersion and erosion. Approximately 78% of subsoil samples have EAT ratings of 2 and 3, indicating a moderately high to high potential for dispersion. The remaining 22% of subsoil samples have a negligible dispersion potential of EAT 4.

Once the dispersive subsoils are disturbed, the potential for erosion should be increased. If this disturbance occurs within the vicinity of a drainage line, this could impact on the health of downstream watercourses through an increase in sediment load. Full EAT results are shown in **Appendix D**.

4.4 Waste Rock Characterisation

4.4.1 Waste Rock Characterisation

The 12 samples from the Project were analysed for their GAI, the ASLP and Acid Mine Drainage AMD characteristics. Instructions were given to sample waste rock from above and below the coal seam. In addition to the standard parameters, samples were further assessed for their HCl-extractable sulphur concentrations. The incorporation of HCL extractable sulphur resulted in a reduction of the Maximum Potential Acidity (MPA) in all 12 samples, confirming the conservative nature of the calculated standard NAPP. Locations of the sampled drill core locations are presented in **Figure 6** and **Figure 7** and laboratory documents are provided in **Appendix A**.

The Project will place the waste rock into open cut Pit C and Pit D. The estimated volume of waste rock from the proposed Project over the life of the mine is 45,600 m³ in total which is approximately less than 0.13% of total approved waste rock volumes (36 million m³) currently approved for the rehabilitation of Pit C and Pit D. At less than 0.13% of total approved rock volume for Pit C and Pit D, it is not expected that this addition would impact the approved final landform outcomes in Appendix 3 of the EA.

Quality assurance of the sampling results was achieved by including two duplicate samples into the sampling suite. Results of the duplicates were in good agreement (less than 10% variance) with regards to the AMD characterisation and GAI classification involving total metal analysis. Duplicate sample analysis for the Australian Standard Leaching Procedure (ASLP) leachability of metals was generally not in agreement, showing a greater than 10% variance. The discrepancy with regards to metal leachability was uniform between major metals like aluminium and iron and minor metals like nickel and lead and may be due to sample slitting of the partially oxidised drill core, resulting in a greater fraction of leachable metals being present in one fraction of the QA samples.

4.4.2 Acid Producing Potential

The additional characterisation of 12 drill core waste rock samples from the Project suggests that 10 of 12 samples are NAF. One sample is classified as uncertain and one sample potentially acid generating (PAF). The NAPP of all 12 samples ranges from positive 6.2 to negative 91.3 kg/H₂SO₄/tonne. Combined with the mostly alkaline NAG pH (8 of 12 samples) the overwhelming negative NAPP indicates a strong and available alkaline buffering capacity. Comparison between total and HCl extractable sulphur shows that sulphur is present as primary reactive sulphide in 11 of the 12 samples, ranging from 44.4% to 97.4% with an average of 82.4%. The acid producing potential results are shown in **Figure 12** and **Table 8**.




Figure 12 Acid producing potential characteristics of total 12 waste rock samples

Table 8 Summary of results for 12 waste rock samples

Zone	Sample ID	NAG (pH units)	MPA (kg H ₂ SO ₄ /t based on total S)	MPA (kg H ₂ SO ₄ /t based on reactive S)	ANC (kg H ₂ SO ₄ /t)	NAPP (kg H ₂ SO ₄ /t based on total S)	NAPP (kg H ₂ SO ₄ /t based on reactive S)
Zone 2	C5348	8.3	5.513	5.053	34	-28.5	-28.9
Zone 2	C5296	8.4	1.593	1.378	21	-19.4	-19.6
Zone 2	C4842	7.6	33.688	32.616	41	-7.3	-8.4
Zone 2	C5288	5.3	9.494	9.249	6.6	2.9	2.6
Zone 2	C5231	8.5	0.551	0.337	9.2	-8.6	-8.9
Zone 2	C5293	4.1	7.044	6.707	0.5	6.5	6.2
Zone 3	C4815	4.8	0.888	0.812	2.6	-1.7	-1.8
Zone 3	C4823	8.1	0.827	0.368	11	-10.2	-10.6
Zone 3	C5336	6.4	1.072	0.827	4.0	-2.9	-3.2
Zone 3	C5338	9.0	0.214	-0.123	87	-86.8	-87.1
Zone 3	C5206	8.9	0.276	-0.153	86	-85.7	-86.2
Zone 3	C5434	8.4	0.184	-0.337	91	-90.8	-91.3

4.4.3 Geochemical Abundance Index (GAI)

The geochemical abundance index (GAI) can be used to estimate the enrichment of metals in the samples relative to median crustal concentration. The GAI is expressed on a log 2 scale. The GAI was developed by Förstner et al., (1993) and is defined as follows:

$$GAI = \log_2 \left(\frac{C}{(1.5 * B)} \right) \quad \begin{array}{l} C = \text{measured concentration in sample} \\ B = \text{average crustal abundance} \end{array}$$

The enrichment ranges of a metal based on the GAI values are interpreted as follow:

- GAI=0 indicates <3 times median crustal abundance
- GAI=1 indicates 3 to 6 times median crustal abundance
- GAI=2 indicates 6 to 12 times median crustal abundance
- GAI=3 indicates 12 to 24 times median crustal abundance
- GAI=4 indicates 24 to 48 times median crustal abundance
- GAI=5 indicates 48 to 96 times median crustal abundance
- GAI=6 indicates more than 96 times median crustal abundance

GAI value of 3 is taken as the threshold for predicting potential metalliferous drainage from samples. The median crustal abundances used to compare results against in the GAI are provided in **Table 9**.

Table 9 Median crustal abundance for trace metals (Berkman and Ryall, 1976; Bowen, 1979)

Name	Symbol	Median Crustal Abundance (mg/kg)
Aluminium	Al	71,000
Arsenic	As	6
Beryllium	Be	6
Boron	B	8.6
Cadmium	Cd	0.35
Cobalt	Co	8
Chromium	Cr	70
Copper	Cu	30
Iron	Fe	40,000
Manganese	Mn	1,000
Molybdenum	Mo	2
Nickel	Ni	50
Lead	Pb	35
Zinc	Zn	90
Selenium	Se	0.4
Vanadium	V	90

The GAI assessment of the 12 Drill core waste rock samples (presented in **Table 10**) shows that the waste rock is depleted with regards to most metals. A slight enrichment only exists for cobalt, molybdenum and selenium.

Table 10 GAI summary of 12 waste rock samples

Zone	Sample	Al	As	Be	B	Cd	Co	Cr	Cu	Fe	Pb	Mn	Mo	Ni	Zn	Se	V
Zone 2	C5348	-3	-2	-3	-5	-3	0	-3	0	0	-3	0	0.5	-1	-1	1	-2
Zone 2	C5296	-3	0	-3	-5	-3	0	-3	-1	-1	-6	0	0.5	-2	-2	1	-3
Zone 2	C4842	-4	0	-5	-5	-3	-1	-4	0	-2	-1	-2	1	-2	-2	1	-5
Zone 2	C5288	-3	0	-3	-5	-3	-1	-3	0	-2	-2	-3	0.5	-1	-1	1	-4
Zone 2	C5231	-3	0	-3	-5	-3	0	-3	0	-1	-2	-2	0.5	-1	-1	1	0
Zone 2	C5293	-3	0	-3	-5	-3	0	-3	0	-2	-2	-4	1	-1	-1	1	-3
Zone 3	C4815	-2	0	-3	-5	-3	0	-2	0	-1	-2	-3	0.5	-1	-1	1	-3
Zone 3	C4823	-3	0	-3	-5	-3	0	-2	0	0	-2	-1	0.5	-1	-1	1	-8
Zone 3	C5336	-3	-1	-3	-5	-3	0	-3	0	-2	-1	-4	0.5	-1	-1	1	0
Zone 3	C5338	-3	0	-3	-5	-3	0	-3	0	-1	-2	-2	0.5	-1	-1	1	-3
Zone 3	C5206	-3	0	-3	-5	-3	0	-2	0	0	-5	0	0.5	-1	-1	1	-6
Zone 3	C5434	-3	0	-3	-5	-3	0	-3	-1	-1	-7	0	0.5	-2	-2	1	-5

4.4.4 Waste Rock Leachate Characteristics

The ASLP results for the 12 samples from the Project are shown in **Table 11** and compared to the toxicant default guideline values for water quality in aquatic ecosystems (95% protection level) (Australian Government, 2022). Guideline exceedances in the leachate was reported for aluminium, arsenic, copper, cobalt, zinc, lead, molybdenum, nickel, selenium and vanadium. At the pH values measured (pH 8.4 – 9.8) most of these metals are unlikely be mobile and bioavailable. Hence, the exceedances of these metal are likely due to the presence of natural clays (Brookins; 1988, Meunier; 1994), which will disperse and potentially pass through the standard (0.45 µm) filtration as particles.

Table 11 ASLP results of the 12 drill core waste rock samples compared to the aquatic ecosystem 95% protection level

Parameter		pH	EC	Al	As	Cd	Cu	Pb	Mo	Zn	B	Cr	Co	Mn	Ni	Se	V
Unit		pH Unit	µS/cm	mg/L >pH6.5	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L (total)	mg/L
Guideline Value		-	-	0.055	0.024	0.0002	0.0014	0.0034	0.034	0.008	0.94	0.0033	0.0014	1.9	0.011	0.011	0.006
Zone 2	C5348	9.5	190	2.5	0.086	<0.0001	0.030	0.025	0.011	0.049	0.018	0.001	0.006	0.25	0.005	<0.003	0.022
Zone 2	C5296	8.9	140	3.1	0.16	0.0002	0.052	0.034	0.013	0.094	0.024	0.002	0.005	0.061	0.014	0.009	0.020
Zone 2	C4842	8.4	270	0.19	0.012	<0.0001	<0.001	<0.001	0.037	<0.005	0.050	<0.001	<0.001	<0.005	<0.001	0.015	0.008
Zone 2	C5288	9.7	200	6.8	0.20	<0.0001	0.001	<0.001	0.026	0.007	0.028	0.003	<0.001	<0.005	0.001	0.012	0.028
Zone 2	C5231	9.8	220	5.2	0.080	<0.0001	0.001	<0.001	0.005	<0.005	0.017	0.002	<0.001	0.006	<0.001	<0.003	0.019
Zone 2	C5293	9.4	190	2.2	0.038	<0.0001	0.018	0.013	0.006	0.035	0.015	0.002	0.005	0.28	0.008	<0.003	0.013
Zone 3	C4815	9.5	160	9.1	0.18	<0.0001	0.001	<0.001	0.010	0.018	0.027	0.003	<0.001	<0.005	0.001	0.006	0.024
Zone 3	C4823	8.8	88	8.5	0.11	<0.0001	0.002	<0.001	0.034	0.007	0.037	0.002	0.001	<0.005	0.002	0.008	0.027
Zone 3	C5336	9.1	140	1.5	0.099	<0.0001	<0.001	<0.001	0.011	<0.005	0.019	0.002	<0.001	<0.005	<0.001	0.004	0.012
Zone 3	C5338	9.4	150	3.9	0.061	<0.0001	<0.001	<0.001	0.013	<0.005	0.026	0.002	<0.001	<0.005	0.001	0.009	0.016
Zone 3	C5206	9.7	210	10	0.20	<0.0001	0.001	<0.001	0.045	0.009	0.033	0.003	0.002	<0.005	0.003	0.007	0.035
Zone 3	C5434	9.5	190	12	0.084	<0.0001	0.002	<0.001	0.028	0.011	0.035	0.002	0.002	0.009	0.003	0.011	0.015

Red denotes exceedance of aquatic ecosystem 95% protection level criteria

4.5 Soil Resources

Based on the soil survey results, topsoil and subsoil resources are summarised in **Table 12**. It is noted that there is no soil stripping proposed for the Project and the soil resources are presented for informative purposes only. Therefore, no changes in soil resource volumes will occur as a result of the Project.

Table 12 Available Topsoil Resource Summary

Topsoil Map Unit	ASC Soil Type	Hectares	Topsoil Strip Depth (m)	Topsoil Volume (m ³)
1	Crusty Brown Vertosols	25	0.1	25,000
2A	Eutrophic Brown Dermosols	172	0.4	688,000
2B	Eutrophic Brown Dermosols	182	0.32	582,400
3	Magnesian Brown Kandosols	108	0.175	189,000
4	Clastic Rudosols	55	0.2	110,000
Topsoil Volume Available				1,594,400

Table 13 Available Subsoil Resource Summary

Subsoil Map Unit	ASC Soil Type	Hectares	Subsoil Strip Depth (m)	Subsoil Volume (m ³)
1	Crusty Brown Vertosols	25	0.9	225,000
2A	Eutrophic Brown Dermosols	172	0.6	1,032,000
2B	Eutrophic Brown Dermosols	182	0.68	1,237,600
3	Magnesian Brown Kandosols	108	0.825	891,000
4	Clastic Rudosols	55	0.8	440,000
Subsoil Volume Available				3,825,600

5 Soil and Land Resource Impact Assessment

The Assessment takes into consideration Land Suitability and Agricultural Land Classifications associated with the Project. This includes a comparison between pre- and post-mining activities. As described in **Section 1.3**, the proposed construction footprint for the Project will consist of the establishment of four flares and associated exclusion areas i.e. a total of 0.64 ha. During the flare decommissioning process, flares and exclusion areas will be rehabilitated back to the land use (cattle grazing) specified in the current Environmental Authority (EA) EPML00732813.

5.1 Land Suitability Methodology

The information required for the land suitability assessment was collected and verified on the ground during the field survey, laboratory analysis program and the desktop assessment. The land suitability classification was applied across the Project in accordance with the *Regional Land Suitability Frameworks for Queensland* (DSITI & DNRM, 2015), in particular *Section 10 Suitability Framework for the Inland Fitzroy and Southern Burdekin Area*. This scheme uses the biophysical features of the land and soil to derive detailed rating tables for a range of land and soil hazards. The scheme consists of eight limitations that classify the land based on the severity against the suitability subclasses for various land management options. The eight limitations associated with the biophysical features that are assessed by the scheme are:

- Water erosion (E)
- Erosion hazard, subsoil erodibility (Es)
- Soil water availability (M)
- Narrow moisture range (Pm)
- Surface condition (Ps)
- Rockiness (R)
- Microrelief (Tm), and
- Wetness (W).

The suitability framework provides the detail for assessing which crops are suitable for individual mapped areas of land or soil, in addition the suitability of the land for grazing is also considered. Each hazard was assessed against a set of criteria tables, as described in the guideline, with each hazard ranked from 1 (most suitable) through to 5 (least suitable) with the overall ranking of the land determined by its most significant limitation, as described in **Table 14**.

Table 14 Land Suitability Classes

Class	Description
1	Suitable land with negligible limitations and is highly productive requiring only simple management practices.
2	Suitable land with minor limitations which either reduce production or require more than simple management practices to sustain the use.
3	Suitable land with moderate limitations. Land which is moderately suited to a proposed use but which requires significant inputs to ensure sustainable use.
4	Marginal land with severe limitations which make it doubtful whether the inputs required to achieve and maintain production outweigh the benefits in the long term.
5	Unsuitable land with extreme limitations that precludes its use.

5.2 Pre-Mining Land Suitability Results

5.2.1 Pre-Mining Land Suitability for Cropping

The land suitability assessment for cropping indicates the main limitations for the Project are soil wetness (w) and soil water availability (m). Soil wetness is predominantly influenced by the permeability and drainage capacity of the soil. Soil water availability is predominately influenced by the soil texture. The land suitability ratings are as follows:

- Approximately 25 ha of land associated with SMU 1 is rated as Class 4, and
- Approximately 517 ha of land associated with SMUs 2A, 2B, 3 & 4 is rated as Class 5.

Results for the Land Suitability Assessment for cropping are outlined in **Table 15** and shown in **Figure 13**, with the detailed Land Suitability Assessment provided in **Appendix E**.

5.2.2 Pre-Mining Land Suitability for Grazing

The land suitability assessment for grazing indicates the main limitations for the Project are soil wetness (w) and soil water availability (m) and ratings as follows:

- Approximately 25 ha of land associated with SMU 1 is rated as Class 2
- Approximately 462 ha of land associated with SMU 2A, 2B & 3 is rated as Class 3, and
- Approximately 55 ha of land associated with SMU 4 is rated as Class 5.

Results for the Land Suitability Assessment for grazing are outlined in **Table 16** and shown in **Figure 13**, with the detailed Land Suitability Assessment provided in **Appendix E**.

5.2.3 Post-Mining

Land suitability classes for areas not scheduled for the proposed mining minor construction footprint (ie 4 flares) will remain the same. Surface disturbance predicted for this Project will be limited to the flare construction footprint. Upon flare decommission, these classes will remain the same post-mining.

Changes in the areas of land suitability classes within the Project Area between pre- and post-mining are summarised in **Table 15** and **Table 16** and also include the mine spoil areas.


Table 15 Pre- and Post-Mining Cropping Land Suitability Class

Cropping Suitability Class	Pre-Mining		Post-Mining	
	ha	%	ha	%
1	0	0	0	0
2	0	0	0	0
3	0	0	0	0
4	25	4	25	4
5	517	86	517	86
Mine Spoil Area	61	10	61	10
Total	603	100	603	100

Table 16 Pre- and Post-Mining Grazing Land Suitability Class

Grazing Suitability Class	Pre-Mining		Post-Mining	
	ha	%	ha	%
1	0	0	0	0
2	25	4	25	4
3	462	77	462	77
4	0	0	0	0
5	55	9	55	9
Mine Spoil Area	61	10	61	10
Total	603	100	603	100

H:\Projects\SLR\620.30686\620.30686_000000 Soils and Land Assessment\06 SLR Data\01 CAD\GIS\GIS\Soils\620.30686 F13 Cropping Land Suitability Class.mxd






Coordinate System: GDA 1994 MGA Zone 55
Scale: 1:50,000 at A4
Project Number: 620.30686
Date: 08-Mar-2022
Drawn by: JG



-  Flare Exclusion Area (80m x 20m)
-  Zone 2
-  Zone 3
-  Mining Leases
-  Mine Spoil Area

Suitability Class

-  Cropping 4, Grazing 2 - 25 ha
-  Cropping 5, Grazing 3 - 489 ha
-  Cropping 5, Grazing 5 - 55 ha

620.30686 ENSHAM SOIL SURVEY

**Cropping and Grazing
Land Suitability Class**

FIGURE 13

5.3 Agricultural Land Class Assessment

Agricultural land classification in Queensland follows a simple hierarchical scheme that is applicable across the state. It allows the presentation of interpreted land evaluation data to indicate the location and extent of agricultural land that can be used sustainably for a wide range of land uses with minimal land degradation. Provision is also made to highlight areas that may be suitable for one specific crop considered important in a particular area. Three broad classes of agricultural land and one non-agricultural land class are identified in the *Agricultural Land Class system* (**Table 17**) (DSITI & DNRM, 2015):

- Class A – Crop land
 - Class A1 – Broadacre and horticultural crops
 - Class A2 – Horticultural crops only
- Class B – Limited crop land
- Class C – Pasture (grazing) land
 - Class C1 – Grazing sown pastures or native pastures on higher fertility soils
 - Class C2 – Grazing native pastures on with lower fertility soils than C1
 - Class C3 – light grazing of native pastures and land suited to forestry, and
- Class D – Non-agricultural land.

Table 17 Agricultural Land Classes

Class	Description
A	Crop land – Land that is suitable for current and potential crops with limitations to production which range from none to moderate levels.
A1	Suitable for a wide range of current and potential broadacre and horticultural crops.
A2	Suitable for a wide range of current and potential horticultural crops only.
B	Limited crop land – Land that is marginal for current and potential crops due to severe limitations; and suitable for pastures. Engineering and/or agronomic improvements may be required before the land is considered suitable for cropping.
C	Pasture land – Land that is suitable only for improved or native pastures due to limitations which preclude continuous cultivation for crop production; but some areas may tolerate a short period of ground disturbance for pasture establishment.
C1	Suitable for grazing sown pastures requiring ground disturbance for establishment; or native pastures on higher fertility soils.
C2	Suitable for grazing native pastures, with or without the introduction of pasture, and with lower fertility soils than C1.
C3	Suitable for light grazing of native pastures in accessible areas, and includes steep land more suited to forestry or catchment protection
D	Non-agricultural land – Land not suitable for agricultural uses due to extreme limitations. This may be undisturbed land with significant habitat, conservation and/or catchment values or land that may be unsuitable because of very steep slopes, shallow soils, rock outcrop or poor drainage.

5.4 Agricultural Land Class Results

5.4.1 Pre-Mining

The agricultural land class ratings for the Project are soil wetness (w) and soil water availability (m) with ratings as follows:

- Approximately 25 ha of land associated with SMU 1 is rated as Class A2
- Approximately 462 ha of land associated with SMU 2A, 2B & 3 is rated as Class C2, and
- Approximately 55 ha of land associated with SMU 4 is rated as Class C3.

Results for the pre-mining agricultural land classes are outlined in **Table 18** and shown in **Figure 14**, with the detailed agricultural land assessment provided in **Appendix E**.


5.4.2 Post-Mining

Agricultural land classes for areas not scheduled for the proposed mining construction footprint (e.g. flares) will remain the same. Surface disturbance predicted for this Project, will be limited to the flare construction footprint. Upon flare decommission, these classes will remain the same post-mining.

Changes in the areas of agricultural land classes within the Project between pre- and post-mining are summarised in **Table 18** and includes the mine spoil areas.






Table 18 Pre- and Post-Mining Agricultural Land Classes

Agricultural Land Class	Pre-Mining		Post-Mining	
	ha	%	ha	%
A1	0	0	0	0
A2	25	4	25	4
B	0	0	0	0
C1	0	0	0	0
C2	462	77	462	77
C3	55	9	55	9
D	0	0	0	0
Mine Spoil Area	61	10	61	10
Total	603	100	603	100






Coordinate System: GDA 1994 MGA Zone 55
Scale: 1:50,000 at A4
Project Number: 620.30686
Date: 23-Feb-2022
Drawn by: JG



-  Flare Exclusion Area (80m x 20m)
-  Zone 2
-  Zone 3
-  Mining Leases
-  Mine Spoil Area

Agricultural Land Class

-  Class A2 - 25 ha
-  Class C2 - 489 ha
-  Class C3 - 55 ha

620.30686 ENSHAM SOIL SURVEY

Agricultural Land Classes

FIGURE 14

6 Conclusions

Five Soil Map Units (SMU) were identified in the Assessment, comprising of the following:

- SMU 1 Crusty Brown Vertosol (25 ha)
- SMU 2A Eutrophic Brown Dermosol (172 ha)
- SMU 2B Eutrophic Brown Dermosol (182 ha)
- SMU 3 Magnesic Brown Kandosol (108 ha), and
- SMU 4 Clastic Rudosol (55 ha).

The mine spoil area extent and other open cut disturbance within Zones 2 and 3 was 61 ha and was not characterised in the Assessment.

The land suitability assessment indicates:

- SMU 1 (25 ha) is rated as Class 4 (marginal land with severe limitations) for cropping and Class 2 (suitable land with minor limitations) for grazing
- SMU 2A, 2B and 3 (462 ha) are rated as Class 5 (unsuitable land) for cropping and Class 3 for grazing (marginal land with moderate limitations)
- SMU 4 is rated as Class 5 for cropping and grazing (55 ha), and
- The main limitations of the soil in the Project were soil wetness (w) and soil water availability (m). There will be no decrease in quality of suitability class land within the Project resulting from the proposed flares, post-rehabilitation.

The agricultural land assessment indicates:

- SMU 1 is rated as Agricultural Land Class A2 (25 ha), a wide range of crops and/or horticultural crops only
- SMU 2A, 2B and 3 are rated as Agricultural Land Class C2 (462 ha), grazing native pastures on with lower fertility soils than C1
- SMU 4 is rated as Agricultural Land Class C3 (55 ha), light grazing of native pastures and land suited to forestry, and
- There will be no decrease in quality of agricultural land within the Project resulting from the proposed flares, post-rehabilitation.

The assessment of soil resources indicates:

- A topsoil volume of 1,594,400 m³
- A subsoil volume of 3,825,600 m³, and
- No soil stripping is proposed in the Project. No changes in soil resource volumes will occur.

The geochemical assessment of waste rock indicates:

- Confirmation of the previous waste rock assessments by URS in 2005 and 2015
- The waste rock is non-acid generating and has significant buffering capacity
- The GAI results showed very low and depleted metal concentrations for most metals

-
- ASLP metal concentrations showed several exceedances of guideline values for aquatic ecosystem protection, particularly aluminium and vanadium. Such exceedances are unlikely at the reported pH and are likely to be the result of colloid transport through the 0.45µm filter membrane
 - Waste rock produced will not be placed on agricultural land, but be buried within the open cut pit and results indicate any adverse impact from metals concentration and leachability is unlikely, and
 - The estimated volume of waste rock from the Project over the life of the mine is 45,600 m³ in total, which is approximately less than 0.13% of total waste rock volumes (36 million m³) currently approved for the rehabilitation of open cut Pit C and Pit D. It is not expected to impact the approved final landform outcomes in Appendix 3 Rehabilitation Success Criteria of the EA.

7 References

- Australian Government, (2022). Toxicant default guideline values for water quality in aquatic ecosystems. <https://www.waterquality.gov.au/anz-uidelines/guideline-values/default/water-quality-toxicants/search#tox-289>. Accessed 07.02.2022.
- Brookins D. G. (1988). Eh-pH Diagrams for Geochemistry. Springer-Verlag, Berlin.
- DNRM and DSIT. (2013). Regional Land Suitability Frameworks for Queensland. Department of Natural Resources and Mines and the Department of Science, Information Technology, Innovation and the Arts.
- DSITI & DNRM (2015). Guidelines for agricultural land evaluation in Queensland (2nd ed). Queensland Government (Department of Science, Information Technology and Innovation and Department of Natural Resources and Mines), Brisbane, Queensland.
- Förstner, U., Ahlf, W., & Calmano, W., 1993, "Sediment Quality Objectives and Criteria Development in Germany", Water Science & Technology, 28:307-316.
- Gunn and Fitzpatrick. (1967). Land of the Isaac-Comet Area. Queensland.
- Geological Survey of Queensland (GSQ). (1969). Emerald, Sheet SF 5515. First Edition. Queensland, Brisbane.
- Gordon Geotechniques Pty Ltd, 2022, Subsidence Report for the Ensham Life of Mine Extension – Zone 2 and 3, prepared for Ensham Resources Pty Ltd 2022.
- Idemitsu Australia, 2022. Supporting documentation for EA Amendment Report.
- Idemitsu Australia Resources. (2021). Ensham Life of Mine Extension Project Environmental Impact Statement, Chapter 10 – Surface Water Resources.
- Independent Expert Steering Committee (IESC), 2015. Monitoring and Management of Subsidence Induced by Longwall Coal Mining Activity. Report to the Department of the Environment.
- Isbell, R. F. (2021). The Australian Soil Classification Third Edition. Australia: CSIRO Publishing.
- MEND (2009). Prediction Manual for Drainage Chemistry from sulphidic Geologic Materials. MEND Report 1.20.1.
- Meunier, J.D. (1994). The Composition and Origin of Vanadium-Rich Clay Minerals in Colorado Plateau Jurassic Sandstones. Clays and Clay Minerals, Volume 42, pages391–401.
- NCST. (2008). Guidelines for Surveying Soil and Land Resources, 2nd edition. Australia: National Committee on Soil and Terrain CSIRO Publishing.
- NCST. (2009). Australian Soil and Land Survey Field Handbook, 3rd edition. Collingwood, Australia: National Committee on Soil and Terrain CSIRO Publishing.
- Queensland Land Use Mapping Program (QLUMP). (2017). Australian Bureau of Agricultural and Resource Economics and Sciences. Queensland Government.
- SLR. (2021). DRAFT SLR – Terrestrial Ecology Report – Ensham Life Of Mine Extension. Sydney: SLR Consulting Australia (Pty) Ltd.

URS (2005). Geochemical Characterisation and Assessment of Overburden and Potential Coal Reject material at the Ensham Central Project. Prepared for Hansen Consulting. 24 October, 2005. 42625576/R001-Final.DOC.

URS (2015). Geochemical Characterisation of Overburden and Potential Rejects. Prepared for Ensham Resources Pty. Ltd., 19 March 2015. 42627460/R001/A

APPENDIX A

Soil Laboratory Certificates of Analysis

AGRICULTURAL SOIL ANALYSIS REPORT

81 samples supplied by SLR Consulting Australia Pty Ltd on 6/12/2021 . Lab Job No.M4178

Analysis requested by Alex Koeman. Your Job: PO: 620.30686

Level 2, 15 Astor Terrace BRISBANE QLD 4000

Analysis requested by Alex Rodman, Plot 6001, 01/02/2020

Level 2, 15 Astor Terrace BRISBANE QLD 4000

		Sample ID:	Sample 1	Sample 2	Sample 3	Sample 4	Sample 5	Sample 6
		Crop:	BH02_0-10	BH02_20-30	BH02_50-60	BH02_90-100	BH03_0-10	BH03_20-30
		Client:	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd
	Parameter	Method reference	M4178/1	M4178/2	M4178/3	M4178/4	M4178/5	M4178/6
	Phosphorus (mg/kg P)	**Rayment & Lyons 2011 - 9E2 (Bray 1)	8.3	7.2	5.8	1.9	8.4	7.0
	pH	Rayment & Lyons 2011 - 4A1 (1:5 Water)	5.28	5.02	5.06	4.90	4.68	4.88
	Electrical Conductivity (dS/m)	Rayment & Lyons 2011 - 3A1 (1:5 Water)	0.058	0.031	0.054	0.118	0.030	0.031
	Estimated Organic Matter (% OM)	**Calculation: Total Carbon x 1.75	2.21	1.43	1.02	1.17	2.40	2.63
	Exchangeable Calcium (cmol./kg) (kg/ha) (mg/kg)	Rayment & Lyons 2011 - 15D3 (Ammonium Acetate)	1.0	0.33	0.37	0.76	0.14	0.18
			459	147	166	343	63	82
			205	66	74	153	28	37
	Exchangeable Magnesium (cmol./kg) (kg/ha) (mg/kg)		0.36	0.15	0.89	2.3	0.08	0.07
			97	42	243	632	23	19
			43	19	108	282	10	8.7
	Exchangeable Potassium (cmol./kg) (kg/ha) (mg/kg)		0.41	0.28	0.30	0.40	0.19	0.23
			358	247	260	352	166	199
			160	110	116	157	74	89
	Exchangeable Sodium (cmol./kg) (kg/ha) (mg/kg)		<0.065	<0.065	0.14	0.40	<0.065	<0.065
			<33	<33	70	205	<33	<33
			<15	<15	31	92	<15	<15
Exchangeable Aluminium (cmol./kg) (kg/ha) (mg/kg)	**Inhouse S37 (KCl)	0.15	0.41	0.47	0.34	1.6	1.7	
		30	83	95	68	313	341	
		13	37	42	30	140	152	
Exchangeable Hydrogen (cmol./kg) (kg/ha) (mg/kg)	**Rayment & Lyons 2011 - 15G1 (Acidity Titration)	0.14	0.59	0.36	0.30	0.83	0.70	
		3.2	13	8.1	6.8	19	16	
		1.4	5.9	3.6	3.0	8.3	7.0	
	Effective Cation Exchange Capacity (ECEC) (cmol./kg)	**Calculation: Sum of Ca,Mg,K,Na,Al,H (cmol./kg)	2.1	1.8	2.5	4.5	2.8	2.9
	Calcium (%)	**Base Saturation Calculations - Cation cmol./kg / ECEC x 100	48	18	15	17	4.9	6.3
	Magnesium (%)		17	8.5	35	51	3.0	2.5
	Potassium (%)		19	16	12	8.9	6.7	7.9
	Sodium - ESP (%)		2.5	2.4	5.4	8.8	0.90	0.74
	Aluminium (%)		6.9	23	19	7.5	55	58
	Hydrogen (%)		6.7	33	14	6.7	29	24
	Calcium/Magnesium Ratio	**Calculation: Calcium / Magnesium (cmol./kg)	2.9	2.1	0.41	0.33	1.7	2.6
	Total Carbon (%)	Inhouse S4a (LECO Trumac Analyser)	1.26	0.82	0.58	0.67	1.37	1.50
	Total Nitrogen (%)		0.08	0.03	0.06	0.06	0.09	0.10
	Carbon/Nitrogen Ratio	**Calculation: Total Carbon/Total Nitrogen	16.8	30.2	9.4	10.5	15.1	15.5
	Chloride Estimate (equiv. mg/kg)	**Calculation: Electrical Conductivity x 640	37	20	35	76	19	20

AGRICULTURAL SOIL ANALYSIS REPORT

81 samples supplied by SLR Consulting Australia Pty Ltd on 6/12/2021 . Lab Job No.M4178

Analysis requested by Alex Koeman. Your Job: PO: 620.30686

Level 2, 15 Astor Terrace BRISBANE QLD 4000

Sample ID:	Sample 1	Sample 2	Sample 3	Sample 4	Sample 5	Sample 6
	BH02_0-10	BH02_20-30	BH02_50-60	BH02_90-100	BH03_0-10	BH03_20-30
Crop:	Soil	Soil	Soil	Soil	Soil	Soil
Client:	SLR Consulting Australia Pty Ltd	SLR Consulting Australia Pty Ltd	SLR Consulting Australia Pty Ltd	SLR Consulting Australia Pty Ltd	SLR Consulting Australia Pty Ltd	SLR Consulting Australia Pty Ltd
Parameter	Method reference					
	M4178/1	M4178/2	M4178/3	M4178/4	M4178/5	M4178/6

Notes:

- All results presented as a 40°C oven dried weight. Soil sieved and lightly crushed to < 2 mm.
- Methods from Rayment and Lyons, 2011. *Soil Chemical Methods - Australasia*. CSIRO Publishing: Collingwood.
- Soluble Salts included in Exchangeable Cations - NO PRE-WASH (unless requested).
- 'Morgan 1 Extract' adapted from 'Science in Agriculture', 'Non-Toxic Farming' and LaMotte Soil Handbook.
- Guidelines for phosphorus have been reduced for Australian soils.
- Indicative guidelines are based on 'Albrecht' and 'Reams' concepts.
- Total Acid Extractable Nutrients indicate a store of nutrients.
- National Environmental Protection (Assessment of Site Contamination) Measure 2013, Schedule B(1) - Guideline on Investigation Levels for Soil and Groundwater. Table 5-A Background Ranges.
- Information relating to testing colour codes is available on sheet 2 - 'Understanding your agricultural soil results'.
- Conversions for 1 cmol_e/kg = 230 mg/kg Sodium, 390 mg/kg Potassium, 122 mg/kg Magnesium, 200 mg/kg Calcium
- Conversions to kg/ha = mg/kg x 2.24
- The chloride calculation of Cl mg/L = EC x 640 is considered an estimate, and most likely an over-estimate
- ** NATA accreditation does not cover the performance of this service.
- Analysis conducted between sample arrival date and reporting date.
- This report is not to be reproduced except in full. Results only relate to the item tested.
- All services undertaken by EAL are covered by the EAL Laboratory Services Terms and Conditions (refer SCU.edu.au/eal/t&cs).
- This report was issued on 14/12/2021.

Quality Checked: Kris Saville
 Agricultural Co-Ordinator

KS



AGRICULTURAL SOIL ANALYSIS REPORT

81 samples supplied by SLR Consulting Australia Pty Ltd on 6/12/2021 . Lab Job No.M4178

Analysis requested by Alex Koeman. Your Job: PO: 620.30686

Level 2, 15 Astor Terrace BRISBANE QLD 4000

Analysis requested by Alex Rodman, Plot 6001, 01-02-000000

Level 2, 15 Astor Terrace BRISBANE QLD 4000

		Sample ID:	Sample 7	Sample 8	Sample 9	Sample 10	Sample 11	Sample 12
		Crop:	BH03_30-40	BH04_0-10	BH04_15-25	BH05_0-10	BH05_20-30	BH05_50-60
		Client:	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd
	Parameter	Method reference	M4178/7	M4178/8	M4178/9	M4178/10	M4178/11	M4178/12
	Phosphorus (mg/kg P)	**Rayment & Lyons 2011 - 9E2 (Bray 1)	4.9	14	11	5.3	7.8	3.5
	pH	Rayment & Lyons 2011 - 4A1 (1:5 Water)	4.58	5.26	5.03	5.31	4.93	4.81
	Electrical Conductivity (dS/m)	Rayment & Lyons 2011 - 3A1 (1:5 Water)	0.028	0.031	0.030	1.618	0.497	0.577
	Estimated Organic Matter (% OM)	**Calculation: Total Carbon x 1.75	2.28	3.54	4.31	2.17	2.12	0.90
	Exchangeable Calcium (cmol./kg) (kg/ha) (mg/kg)	Rayment & Lyons 2011 - 15D3 (Ammonium Acetate)	0.19	0.71	0.67	1.5	0.59	0.17
			87	320	302	662	267	78
			39	143	135	295	119	35
	Exchangeable Magnesium (cmol./kg) (kg/ha) (mg/kg)		0.09	0.18	0.17	12	7.7	8.3
			24	49	47	3,261	2,095	2,264
			11	22	21	1,456	935	1,011
	Exchangeable Potassium (cmol./kg) (kg/ha) (mg/kg)		0.19	0.22	0.22	0.25	0.24	0.33
			169	191	190	222	209	286
			75	85	85	99	93	127
	Exchangeable Sodium (cmol./kg) (kg/ha) (mg/kg)		<0.065	<0.065	<0.065	5.2	3.3	3.9
			<33	<33	<33	2,700	1,676	2,032
			<15	<15	<15	1,205	748	907
Exchangeable Aluminium (cmol./kg) (kg/ha) (mg/kg)	**Inhouse S37 (KCl)	1.9	0.87	1.4	0.08	0.67	0.74	
		386	176	280	17	135	149	
		172	79	125	7.5	60	67	
Exchangeable Hydrogen (cmol./kg) (kg/ha) (mg/kg)	**Rayment & Lyons 2011 - 15G1 (Acidity Titration)	0.91	0.52	0.73	0.08	0.56	0.66	
		20	12	16	1.8	13	15	
		9.1	5.2	7.3	<1	5.6	6.6	
	Effective Cation Exchange Capacity (ECEC) (cmol./kg)	**Calculation: Sum of Ca,Mg,K,Na,Al,H (cmol./kg)	3.3	2.5	3.2	19	13	14
	Calcium (%)	**Base Saturation Calculations - Cation cmol./kg / ECEC x 100	5.8	28	21	7.7	4.6	1.2
	Magnesium (%)		2.6	7.2	5.4	63	59	59
	Potassium (%)		5.8	8.6	6.8	1.3	1.8	2.3
	Sodium - ESP (%)		1.1	0.82	0.70	27	25	28
	Aluminium (%)		57	35	43	0.44	5.1	5.2
	Hydrogen (%)		27	21	23	0.42	4.3	4.7
	Calcium/Magnesium Ratio	**Calculation: Calcium / Magnesium (cmol./kg)	2.2	3.9	3.9	0.12	0.08	0.02
	Total Carbon (%)	Inhouse S4a (LECO Trumac Analyser)	1.30	2.02	2.46	1.24	1.21	0.52
	Total Nitrogen (%)		0.12	0.10	0.12	0.12	0.09	0.06
	Carbon/Nitrogen Ratio	**Calculation: Total Carbon/Total Nitrogen	11.1	19.4	21.2	10.0	13.0	9.4
	Chloride Estimate (equiv. mg/kg)	**Calculation: Electrical Conductivity x 640	18	20	19	1,036	318	369

AGRICULTURAL SOIL ANALYSIS REPORT

81 samples supplied by SLR Consulting Australia Pty Ltd on 6/12/2021 . Lab Job No.M4178

Analysis requested by Alex Koeman. Your Job: PO: 620.30686

Level 2, 15 Astor Terrace BRISBANE QLD 4000

Sample ID:

Crop:

Client:

Sample 7	Sample 8	Sample 9	Sample 10	Sample 11	Sample 12
BH03_30-40	BH04_0-10	BH04_15-25	BH05_0-10	BH05_20-30	BH05_50-60
Soil	Soil	Soil	Soil	Soil	Soil
SLR Consulting Australia Pty Ltd	SLR Consulting Australia Pty Ltd	SLR Consulting Australia Pty Ltd	SLR Consulting Australia Pty Ltd	SLR Consulting Australia Pty Ltd	SLR Consulting Australia Pty Ltd
M4178/7	M4178/8	M4178/9	M4178/10	M4178/11	M4178/12

Parameter	Method reference
-----------	------------------

Notes:

- All results presented as a 40°C oven dried weight. Soil sieved and lightly crushed to < 2 mm.
- Methods from Rayment and Lyons, 2011. *Soil Chemical Methods - Australasia*. CSIRO Publishing: Collingwood.
- Soluble Salts included in Exchangeable Cations - NO PRE-WASH (unless requested).
- 'Morgan 1 Extract' adapted from 'Science in Agriculture', 'Non-Toxic Farming' and LaMotte Soil Handbook.
- Guidelines for phosphorus have been reduced for Australian soils.
- Indicative guidelines are based on 'Albrecht' and 'Reams' concepts.
- Total Acid Extractable Nutrients indicate a store of nutrients.
- National Environmental Protection (Assessment of Site Contamination) Measure 2013, Schedule B(1) - Guideline on Investigation Levels for Soil and Groundwater. Table 5-A Background Ranges.
- Information relating to testing colour codes is available on sheet 2 - 'Understanding your agricultural soil results'.
- Conversions for 1 cmol_e/kg = 230 mg/kg Sodium, 390 mg/kg Potassium, 122 mg/kg Magnesium, 200 mg/kg Calcium
- Conversions to kg/ha = mg/kg x 2.24
- The chloride calculation of Cl mg/L = EC x 640 is considered an estimate, and most likely an over-estimate.
- ** NATA accreditation does not cover the performance of this service.
- Analysis conducted between sample arrival date and reporting date.
- This report is not to be reproduced except in full. Results only relate to the item tested.
- All services undertaken by EAL are covered by the EAL Laboratory Services Terms and Conditions.
- This report was issued on 14/12/2021.

Quality Checked: Kris Saville
 Agricultural Co-Ordinator



AGRICULTURAL SOIL ANALYSIS REPORT

81 samples supplied by SLR Consulting Australia Pty Ltd on 6/12/2021 . Lab Job No.M4178

Analysis requested by Alex Koeman. Your Job: PO: 620.30686

Level 2, 15 Astor Terrace BRISBANE QLD 4000

Analysis requested by Alex Rodman, Plot 6087, 01-02-2020

Level 2, 15 Astor Terrace BRISBANE QLD 4000

		Sample ID:	Sample 13	Sample 14	Sample 15	Sample 16	Sample 17	Sample 18
		Crop:	BH05_90-100	BH08_0-10	BH08_20-30	BH08_50-60	BH08_90-100	BH09_0-10
		Client:	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd
	Parameter	Method reference	M4178/13	M4178/14	M4178/15	M4178/16	M4178/17	M4178/18
	Phosphorus (mg/kg P)	**Rayment & Lyons 2011 - 9E2 (Bray 1)	2.9	5.4	2.9	2.4	2.5	1.5
	pH	Rayment & Lyons 2011 - 4A1 (1:5 Water)	4.95	8.95	8.94	8.82	9.01	9.45
	Electrical Conductivity (dS/m)	Rayment & Lyons 2011 - 3A1 (1:5 Water)	0.679	0.470	0.997	1.246	0.726	0.218
	Estimated Organic Matter (% OM)	**Calculation: Total Carbon x 1.75	0.56	2.22	1.73	0.87	1.04	1.50
	Exchangeable Calcium (cmol./kg) (kg/ha) (mg/kg)	Rayment & Lyons 2011 - 15D3 (Ammonium Acetate)	0.05	22	22	12	15	23
			23	9,867	9,862	5,506	6,597	10,150
			10	4,405	4,403	2,458	2,945	4,531
	Exchangeable Magnesium (cmol./kg) (kg/ha) (mg/kg)		8.7	11	12	14	13	12
			2,364	2,868	3,228	3,811	3,470	3,204
			1,056	1,280	1,441	1,701	1,549	1,430
	Exchangeable Potassium (cmol./kg) (kg/ha) (mg/kg)		0.39	0.53	0.43	0.39	0.41	0.44
			341	467	373	343	355	384
			152	209	167	153	158	171
	Exchangeable Sodium (cmol./kg) (kg/ha) (mg/kg)		5.0	3.4	5.8	8.5	5.6	2.4
			2,599	1,745	2,968	4,393	2,865	1,244
			1,160	779	1,325	1,961	1,279	555
Exchangeable Aluminium (cmol./kg) (kg/ha) (mg/kg)	**Inhouse S37 (KCl)	0.49	0.02	<0.01	<0.01	<0.01	<0.01	
		99	3.9	1.1	<1	<1	<1	
		44	1.7	<1	<1	<1	<1	
Exchangeable Hydrogen (cmol./kg) (kg/ha) (mg/kg)	**Rayment & Lyons 2011 - 15G1 (Acidity Titration)	0.74	<0.01	<0.01	<0.01	<0.01	<0.01	
		17	<1	<1	<1	<1	<1	
		7.4	<1	<1	<1	<1	<1	
	Effective Cation Exchange Capacity (ECEC) (cmol./kg)	**Calculation: Sum of Ca,Mg,K,Na,Al,H (cmol./kg)	15	36	40	35	33	37
	Calcium (%)	**Base Saturation Calculations - Cation cmol./kg / ECEC x 100	0.33	60	55	35	44	61
	Magnesium (%)		56	29	30	40	38	32
	Potassium (%)		2.5	1.5	1.1	1.1	1.2	1.2
	Sodium - ESP (%)		33	9.3	14	24	17	6.5
	Aluminium (%)		3.2	0.05	0.01	0.01	0.01	0.00
	Hydrogen (%)		4.8	0.00	0.00	0.00	0.00	0.00
	Calcium/Magnesium Ratio	**Calculation: Calcium / Magnesium (cmol./kg)	0.01	2.1	1.9	0.88	1.2	1.9
	Total Carbon (%)	Inhouse S4a (LECO Trumac Analyser)	0.32	1.27	0.99	0.50	0.59	0.86
	Total Nitrogen (%)		0.06	0.10	0.07	0.08	0.08	0.06
	Carbon/Nitrogen Ratio	**Calculation: Total Carbon/Total Nitrogen	5.6	12.2	13.7	6.7	7.3	15.5
	Chloride Estimate (equiv. mg/kg)	**Calculation: Electrical Conductivity x 640	435	301	638	797	465	140

AGRICULTURAL SOIL ANALYSIS REPORT

81 samples supplied by SLR Consulting Australia Pty Ltd on 6/12/2021 . Lab Job No.M4178

Analysis requested by Alex Koeman. Your Job: PO: 620.30686

Level 2, 15 Astor Terrace BRISBANE QLD 4000

Sample ID:

Crop:

Client:

Sample 13	Sample 14	Sample 15	Sample 16	Sample 17	Sample 18
BH05_90-100	BH08_0-10	BH08_20-30	BH08_50-60	BH08_90-100	BH09_0-10
Soil	Soil	Soil	Soil	Soil	Soil
SLR Consulting Australia Pty Ltd	SLR Consulting Australia Pty Ltd	SLR Consulting Australia Pty Ltd	SLR Consulting Australia Pty Ltd	SLR Consulting Australia Pty Ltd	SLR Consulting Australia Pty Ltd
M4178/13	M4178/14	M4178/15	M4178/16	M4178/17	M4178/18

Parameter	Method reference
-----------	------------------

Notes:

- All results presented as a 40°C oven dried weight. Soil sieved and lightly crushed to < 2 mm.
- Methods from Rayment and Lyons, 2011. *Soil Chemical Methods - Australasia*. CSIRO Publishing: Collingwood.
- Soluble Salts included in Exchangeable Cations - NO PRE-WASH (unless requested).
- 'Morgan 1 Extract' adapted from 'Science in Agriculture', 'Non-Toxic Farming' and LaMotte Soil Handbook.
- Guidelines for phosphorus have been reduced for Australian soils.
- Indicative guidelines are based on 'Albrecht' and 'Reams' concepts.
- Total Acid Extractable Nutrients indicate a store of nutrients.
- National Environmental Protection (Assessment of Site Contamination) Measure 2013, Schedule B(1) - Guideline on Investigation Levels for Soil and Groundwater. Table 5-A Background Ranges.
- Information relating to testing colour codes is available on sheet 2 - 'Understanding your agricultural soil results'.
- Conversions for 1 cmol_e/kg = 230 mg/kg Sodium, 390 mg/kg Potassium, 122 mg/kg Magnesium, 200 mg/kg Calcium
- Conversions to kg/ha = mg/kg x 2.24
- The chloride calculation of Cl mg/L = EC x 640 is considered an estimate, and most likely an over-estimate.
- ** NATA accreditation does not cover the performance of this service.
- Analysis conducted between sample arrival date and reporting date.
- This report is not to be reproduced except in full. Results only relate to the item tested.
- All services undertaken by EAL are covered by the EAL Laboratory Services Terms and Conditions.
- This report was issued on 14/12/2021.

Quality Checked: Kris Saville
 Agricultural Co-Ordinator

KS

AGRICULTURAL SOIL ANALYSIS REPORT

81 samples supplied by SLR Consulting Australia Pty Ltd on 6/12/2021 . Lab Job No.M4178

Analysis requested by Alex Koeman. Your Job: PO: 620.30686

Level 2, 15 Astor Terrace BRISBANE QLD 4000

		Sample ID:	Sample 19	Sample 20	Sample 21	Sample 22	Sample 23	Sample 24
		Crop:	BH09_20-30	BH09_50-60	BH09_90-100	BH11_0-10	BH11_20-30	BH11_50-60
		Client:	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd
Parameter	Method reference		M4178/19	M4178/20	M4178/21	M4178/22	M4178/23	M4178/24
Phosphorus (mg/kg P)	**Rayment & Lyons 2011 - 9E2 (Bray 1)		1.6	1.3	1.5	22	1.5	<1
pH	Rayment & Lyons 2011 - 4A1 (1:5 Water)		9.45	9.80	9.83	8.62	9.17	9.06
Electrical Conductivity (dS/m)	Rayment & Lyons 2011 - 3A1 (1:5 Water)		0.213	0.184	0.569	0.131	0.190	0.354
Estimated Organic Matter (% OM)	**Calculation: Total Carbon x 1.75		1.28	0.55	0.36	2.22	1.15	2.42
Exchangeable Calcium	(cmol./kg)	Rayment & Lyons 2011 - 15D3 (Ammonium Acetate)	22	7.8	4.9	20	14	24
	(kg/ha)		9,776	3,512	2,183	8,812	6,188	10,887
Exchangeable Magnesium	(cmol./kg)		4,364	1,568	974	3,934	2,763	4,860
	(kg/ha)		12	9.0	6.9	5.4	3.9	6.8
Exchangeable Potassium	(cmol./kg)		3,310	2,437	1,866	1,461	1,073	1,859
	(kg/ha)		1,478	1,088	833	652	479	830
Exchangeable Sodium	(cmol./kg)		0.42	0.23	0.22	1.3	0.35	0.29
	(kg/ha)		372	198	194	1,142	309	252
Exchangeable Aluminium	(cmol./kg)		166	88	87	510	138	112
	(kg/ha)		2.4	2.4	7.5	0.27	2.3	2.1
Exchangeable Hydrogen	(cmol./kg)		1,244	1,217	3,873	137	1,164	1,090
	(mg/kg)		555	543	1,729	61	520	487
Exchangeable Aluminium	(cmol./kg)	**Inhouse S37 (KCl)	<0.01	<0.01	<0.01	<0.01	<0.01	<0.01
	(kg/ha)		<1	<1	<1	<1	<1	<1
Exchangeable Hydrogen	(cmol./kg)	**Rayment & Lyons 2011 - 15G1 (Acidity Titration)	<1	<1	<1	<1	<1	<1
	(mg/kg)		<1	<1	<1	<1	<1	<1
Effective Cation Exchange Capacity (ECEC) (cmol./kg)	**Calculation: Sum of Ca,Mg,K,Na,Al,H (cmol./kg)		37	19	19	27	20	33
Calcium (%)	**Base Saturation Calculations - Cation cmol./kg / ECEC x 100		59	40	25	74	68	72
Magnesium (%)			33	46	35	20	19	20
Potassium (%)			1.2	1.2	1.1	4.9	1.7	0.86
Sodium - ESP (%)			6.6	12	39	1.0	11	6.3
Aluminium (%)			0.00	0.01	0.02	0.00	0.01	0.00
Hydrogen (%)			0.00	0.00	0.00	0.00	0.00	0.00
Calcium/Magnesium Ratio	**Calculation: Calcium / Magnesium (cmol./kg)		1.8	0.87	0.71	3.7	3.5	3.6
Total Carbon (%)	Inhouse S4a (LECO Trumac Analyser)		0.73	0.31	0.20	1.27	0.66	1.38
Total Nitrogen (%)			0.05	0.03	0.03	0.11	0.05	0.09
Carbon/Nitrogen Ratio	**Calculation: Total Carbon/Total Nitrogen		15.6	9.5	6.0	12.1	12.6	15.2
Chloride Estimate (equiv. mg/kg)	**Calculation: Electrical Conductivity x 640		136	118	364	84	122	227

AGRICULTURAL SOIL ANALYSIS REPORT

81 samples supplied by SLR Consulting Australia Pty Ltd on 6/12/2021 . Lab Job No.M4178

Analysis requested by Alex Koeman. Your Job: PO: 620.30686

Level 2, 15 Astor Terrace BRISBANE QLD 4000

Sample ID:

Crop:

Client:

Sample 19	Sample 20	Sample 21	Sample 22	Sample 23	Sample 24
BH09_20-30	BH09_50-60	BH09_90-100	BH11_0-10	BH11_20-30	BH11_50-60
Soil	Soil	Soil	Soil	Soil	Soil
SLR Consulting Australia Pty Ltd	SLR Consulting Australia Pty Ltd	SLR Consulting Australia Pty Ltd	SLR Consulting Australia Pty Ltd	SLR Consulting Australia Pty Ltd	SLR Consulting Australia Pty Ltd
M4178/19	M4178/20	M4178/21	M4178/22	M4178/23	M4178/24

Parameter	Method reference
-----------	------------------

Notes:

- All results presented as a 40°C oven dried weight. Soil sieved and lightly crushed to < 2 mm.
- Methods from Rayment and Lyons, 2011. *Soil Chemical Methods - Australasia*. CSIRO Publishing: Collingwood.
- Soluble Salts included in Exchangeable Cations - NO PRE-WASH (unless requested).
- 'Morgan 1 Extract' adapted from 'Science in Agriculture', 'Non-Toxic Farming' and LaMotte Soil Handbook.
- Guidelines for phosphorus have been reduced for Australian soils.
- Indicative guidelines are based on 'Albrecht' and 'Reams' concepts.
- Total Acid Extractable Nutrients indicate a store of nutrients.
- National Environmental Protection (Assessment of Site Contamination) Measure 2013, Schedule B(1) - Guideline on Investigation Levels for Soil and Groundwater. Table 5-A Background Ranges.
- Information relating to testing colour codes is available on sheet 2 - 'Understanding your agricultural soil results'.
- Conversions for 1 cmol_e/kg = 230 mg/kg Sodium, 390 mg/kg Potassium, 122 mg/kg Magnesium, 200 mg/kg Calcium
- Conversions to kg/ha = mg/kg x 2.24
- The chloride calculation of Cl mg/L = EC x 640 is considered an estimate, and most likely an over-estimate.
- ** NATA accreditation does not cover the performance of this service.
- Analysis conducted between sample arrival date and reporting date.
- This report is not to be reproduced except in full. Results only relate to the item tested.
- All services undertaken by EAL are covered by the EAL Laboratory Services Terms and Conditions.
- This report was issued on 14/12/2021.

Quality Checked: Kris Saville
 Agricultural Co-Ordinator

KS

AGRICULTURAL SOIL ANALYSIS REPORT

81 samples supplied by SLR Consulting Australia Pty Ltd on 6/12/2021 . Lab Job No.M4178

Analysis requested by Alex Koeman. Your Job: PO: 620.30686

Level 2, 15 Astor Terrace BRISBANE QLD 4000

		Sample ID:	Sample 25	Sample 26	Sample 27	Sample 28	Sample 29	Sample 30
		Crop:	BH11_90-100	BH12_0-10	BH12_20-30	BH12_50-60	BH12_90-100	BH13_0-10
		Client:	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd
Parameter	Method reference		M4178/25	M4178/26	M4178/27	M4178/28	M4178/29	M4178/30
Phosphorus (mg/kg P)	**Rayment & Lyons 2011 - 9E2 (Bray 1)		1.4	4.7	1.4	1.2	1.2	3.0
pH	Rayment & Lyons 2011 - 4A1 (1:5 Water)		9.04	7.66	7.41	7.45	7.89	7.58
Electrical Conductivity (dS/m)	Rayment & Lyons 2011 - 3A1 (1:5 Water)		0.796	0.060	0.019	0.028	0.030	0.020
Estimated Organic Matter (% OM)	**Calculation: Total Carbon x 1.75		2.21	1.32	0.76	0.43	0.41	0.74
Exchangeable Calcium (cmol./kg) (kg/ha) (mg/kg)	Rayment & Lyons 2011 - 15D3 (Ammonium Acetate)		21	3.7	2.6	3.3	4.5	2.8
			9,293	1,657	1,158	1,490	1,998	1,242
			4,149	740	517	665	892	554
			10	0.88	0.46	0.46	0.93	0.21
			2,816	239	126	126	254	56
			1,257	107	56	56	113	25
Exchangeable Potassium (cmol./kg) (kg/ha) (mg/kg)			0.25	0.51	0.23	0.32	0.16	0.19
			221	445	203	276	138	165
			98	199	91	123	61	74
Exchangeable Sodium (cmol./kg) (kg/ha) (mg/kg)			4.4	<0.065	<0.065	<0.065	0.07	<0.065
			2,263	<33	<33	<33	<33	<33
			1,010	<15	<15	<15	<15	<15
Exchangeable Aluminium (cmol./kg) (kg/ha) (mg/kg)	**Inhouse S37 (KCl)		<0.01	<0.01	<0.01	<0.01	<0.01	<0.01
			<1	<1	<1	<1	<1	<1
			<1	<1	<1	<1	<1	<1
Exchangeable Hydrogen (cmol./kg) (kg/ha) (mg/kg)	**Rayment & Lyons 2011 - 15G1 (Acidity Titration)		<0.01	<0.01	<0.01	<0.01	<0.01	<0.01
			<1	<1	<1	<1	<1	<1
			<1	<1	<1	<1	<1	<1
Effective Cation Exchange Capacity (ECEC) (cmol./kg)	**Calculation: Sum of Ca,Mg,K,Na,Al,H (cmol./kg)		36	5.1	3.3	4.1	5.6	3.2
Calcium (%)	**Base Saturation Calculations - Cation cmol./kg / ECEC x 100		58	72	78	80	79	87
Magnesium (%)			29	17	14	11	17	6.4
Potassium (%)			0.71	9.9	7.0	7.6	2.8	5.9
Sodium - ESP (%)			12	1.0	0.77	0.85	1.2	0.65
Aluminium (%)			0.00	0.05	0.08	0.08	0.07	0.13
Hydrogen (%)			0.00	0.00	0.00	0.00	0.00	0.00
Calcium/Magnesium Ratio	**Calculation: Calcium / Magnesium (cmol./kg)		2.0	4.2	5.6	7.2	4.8	13
Total Carbon (%)	Inhouse S4a (LECO Trumac Analyser)		1.26	0.76	0.43	0.25	0.24	0.43
Total Nitrogen (%)			0.04	0.08	0.04	0.04	0.03	0.03
Carbon/Nitrogen Ratio	**Calculation: Total Carbon/Total Nitrogen		30.0	10.0	11.7	6.9	9.0	12.9
Chloride Estimate (equiv. mg/kg)	**Calculation: Electrical Conductivity x 640		509	38	12	18	19	13

AGRICULTURAL SOIL ANALYSIS REPORT

81 samples supplied by SLR Consulting Australia Pty Ltd on 6/12/2021 . Lab Job No.M4178

Analysis requested by Alex Koeman. Your Job: PO: 620.30686

Level 2, 15 Astor Terrace BRISBANE QLD 4000

Sample ID:

Crop:

Client:

Sample 25	Sample 26	Sample 27	Sample 28	Sample 29	Sample 30
BH11_90-100	BH12_0-10	BH12_20-30	BH12_50-60	BH12_90-100	BH13_0-10
Soil	Soil	Soil	Soil	Soil	Soil
SLR Consulting Australia Pty Ltd	SLR Consulting Australia Pty Ltd	SLR Consulting Australia Pty Ltd	SLR Consulting Australia Pty Ltd	SLR Consulting Australia Pty Ltd	SLR Consulting Australia Pty Ltd
M4178/25	M4178/26	M4178/27	M4178/28	M4178/29	M4178/30

Parameter	Method reference
-----------	------------------

Notes:

- All results presented as a 40°C oven dried weight. Soil sieved and lightly crushed to < 2 mm.
- Methods from Rayment and Lyons, 2011. *Soil Chemical Methods - Australasia*. CSIRO Publishing: Collingwood.
- Soluble Salts included in Exchangeable Cations - NO PRE-WASH (unless requested).
- 'Morgan 1 Extract' adapted from 'Science in Agriculture', 'Non-Toxic Farming' and LaMotte Soil Handbook.
- Guidelines for phosphorus have been reduced for Australian soils.
- Indicative guidelines are based on 'Albrecht' and 'Reams' concepts.
- Total Acid Extractable Nutrients indicate a store of nutrients.
- National Environmental Protection (Assessment of Site Contamination) Measure 2013, Schedule B(1) - Guideline on Investigation Levels for Soil and Groundwater. Table 5-A Background Ranges.
- Information relating to testing colour codes is available on sheet 2 - 'Understanding your agricultural soil results'.
- Conversions for 1 cmol_e/kg = 230 mg/kg Sodium, 390 mg/kg Potassium, 122 mg/kg Magnesium, 200 mg/kg Calcium
- Conversions to kg/ha = mg/kg x 2.24
- The chloride calculation of Cl mg/L = EC x 640 is considered an estimate, and most likely an over-estimate.
- ** NATA accreditation does not cover the performance of this service.
- Analysis conducted between sample arrival date and reporting date.
- This report is not to be reproduced except in full. Results only relate to the item tested.
- All services undertaken by EAL are covered by the EAL Laboratory Services Terms and Conditions.
- This report was issued on 14/12/2021.

Quality Checked: Kris Saville
 Agricultural Co-Ordinator



AGRICULTURAL SOIL ANALYSIS REPORT

81 samples supplied by SLR Consulting Australia Pty Ltd on 6/12/2021 . Lab Job No.M4178

Analysis requested by Alex Koeman. Your Job: PO: 620.30686

Level 2, 15 Astor Terrace BRISBANE QLD 4000

Level 2, 15 Astor Terrace BRISBANE QLD 4000

		Sample ID:	Sample 31	Sample 32	Sample 33	Sample 34	Sample 35	Sample 36
		Crop:	BH13_20-30	BH13_50-60	BH13_90-100	BH14_0-10	BH14_20-30	BH14_50-60
		Client:	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd
	Parameter	Method reference	M4178/31	M4178/32	M4178/33	M4178/34	M4178/35	M4178/36
	Phosphorus (mg/kg P)	**Rayment & Lyons 2011 - 9E2 (Bray 1)	2.0	1.8	2.5	5.5	2.9	1.0
	pH	Rayment & Lyons 2011 - 4A1 (1:5 Water)	7.85	8.35	8.69	6.61	6.47	8.18
	Electrical Conductivity (dS/m)	Rayment & Lyons 2011 - 3A1 (1:5 Water)	0.023	0.040	0.058	0.038	0.022	0.093
	Estimated Organic Matter (% OM)	**Calculation: Total Carbon x 1.75	0.46	0.55	0.38	1.69	1.27	0.62
	Exchangeable Calcium (cmol./kg) (kg/ha) (mg/kg)	Rayment & Lyons 2011 - 15D3 (Ammonium Acetate)	2.5	2.9	4.0	3.1	3.0	11
			1,141	1,322	1,802	1,385	1,338	5,149
			509	590	804	618	597	2,298
	Exchangeable Magnesium (cmol./kg) (kg/ha) (mg/kg)		0.26	0.42	0.71	0.96	0.68	3.3
			70	115	193	261	184	887
			31	51	86	116	82	396
	Exchangeable Potassium (cmol./kg) (kg/ha) (mg/kg)		0.23	0.41	0.74	0.49	0.33	0.26
			204	358	648	426	288	226
			91	160	289	190	129	101
	Exchangeable Sodium (cmol./kg) (kg/ha) (mg/kg)		<0.065	0.07	<0.065	<0.065	<0.065	0.25
			<33	36	<33	<33	<33	129
			<15	16	<15	<15	<15	58
Exchangeable Aluminium (cmol./kg) (kg/ha) (mg/kg)	**Inhouse S37 (KCl)	<0.01	<0.01	<0.01	<0.01	<0.01	<0.01	
		<1	1.3	1.0	<1	<1	1.3	
		<1	<1	<1	<1	<1	<1	
Exchangeable Hydrogen (cmol./kg) (kg/ha) (mg/kg)	**Rayment & Lyons 2011 - 15G1 (Acidity Titration)	<0.01	<0.01	<0.01	<0.01	0.02	<0.01	
		<1	<1	<1	<1	<1	<1	
		<1	<1	<1	<1	<1	<1	
Effective Cation Exchange Capacity (ECEC) (cmol./kg)		**Calculation: Sum of Ca,Mg,K,Na,Al,H (cmol./kg)	3.1	3.9	5.5	4.6	4.0	15
	Calcium (%)	**Base Saturation Calculations - Cation cmol./kg / ECEC x 100	83	76	73	68	74	75
	Magnesium (%)		8.4	11	13	21	17	21
	Potassium (%)		7.6	11	13	11	8.2	1.7
	Sodium - ESP (%)		1.1	1.8	0.80	0.56	0.51	1.6
	Aluminium (%)		0.14	0.16	0.09	0.08	0.08	0.04
	Hydrogen (%)		0.00	0.00	0.00	0.00	0.50	0.00
Calcium/Magnesium Ratio		**Calculation: Calcium / Magnesium (cmol./kg)	9.9	7.0	5.7	3.2	4.4	3.5
Total Carbon (%)		Inhouse S4a (LECO Trumac Analyser)	0.26	0.32	0.22	0.97	0.72	0.35
Total Nitrogen (%)			0.04	0.04	0.04	0.11	0.06	0.04
Carbon/Nitrogen Ratio		**Calculation: Total Carbon/Total Nitrogen	6.5	8.6	6.0	9.0	11.9	8.4
Chloride Estimate (equiv. mg/kg)		**Calculation: Electrical Conductivity x 640	15	26	37	24	14	60

AGRICULTURAL SOIL ANALYSIS REPORT

81 samples supplied by SLR Consulting Australia Pty Ltd on 6/12/2021 . Lab Job No.M4178

Analysis requested by Alex Koeman. Your Job: PO: 620.30686

Level 2, 15 Astor Terrace BRISBANE QLD 4000

Sample ID:

Crop:

Client:

Sample 31	Sample 32	Sample 33	Sample 34	Sample 35	Sample 36
BH13_20-30	BH13_50-60	BH13_90-100	BH14_0-10	BH14_20-30	BH14_50-60
Soil	Soil	Soil	Soil	Soil	Soil
SLR Consulting Australia Pty Ltd	SLR Consulting Australia Pty Ltd	SLR Consulting Australia Pty Ltd	SLR Consulting Australia Pty Ltd	SLR Consulting Australia Pty Ltd	SLR Consulting Australia Pty Ltd
M4178/31	M4178/32	M4178/33	M4178/34	M4178/35	M4178/36

Parameter	Method reference
-----------	------------------

Notes:

- All results presented as a 40°C oven dried weight. Soil sieved and lightly crushed to < 2 mm.
- Methods from Rayment and Lyons, 2011. *Soil Chemical Methods - Australasia*. CSIRO Publishing: Collingwood.
- Soluble Salts included in Exchangeable Cations - NO PRE-WASH (unless requested).
- 'Morgan 1 Extract' adapted from 'Science in Agriculture', 'Non-Toxic Farming' and LaMotte Soil Handbook.
- Guidelines for phosphorus have been reduced for Australian soils.
- Indicative guidelines are based on 'Albrecht' and 'Reams' concepts.
- Total Acid Extractable Nutrients indicate a store of nutrients.
- National Environmental Protection (Assessment of Site Contamination) Measure 2013, Schedule B(1) - Guideline on Investigation Levels for Soil and Groundwater. Table 5-A Background Ranges.
- Information relating to testing colour codes is available on sheet 2 - 'Understanding your agricultural soil results'.
- Conversions for 1 cmol_e/kg = 230 mg/kg Sodium, 390 mg/kg Potassium, 122 mg/kg Magnesium, 200 mg/kg Calcium
- Conversions to kg/ha = mg/kg x 2.24
- The chloride calculation of Cl mg/L = EC x 640 is considered an estimate, and most likely an over-estimate.
- ** NATA accreditation does not cover the performance of this service.
- Analysis conducted between sample arrival date and reporting date.
- This report is not to be reproduced except in full. Results only relate to the item tested.
- All services undertaken by EAL are covered by the EAL Laboratory Services Terms and Conditions.
- This report was issued on 14/12/2021.

Quality Checked: Kris Saville
 Agricultural Co-Ordinator

KS

AGRICULTURAL SOIL ANALYSIS REPORT

81 samples supplied by SLR Consulting Australia Pty Ltd on 6/12/2021 . Lab Job No.M4178

Analysis requested by Alex Koeman. Your Job: PO: 620.30686

Level 2, 15 Astor Terrace BRISBANE QLD 4000

		Sample ID:	Sample 37	Sample 38	Sample 39	Sample 40	Sample 41	Sample 42
		Crop:	BH14_90-100	BH16_0-10	BH16_20-30	BH16_50-60	BH16_90-100	BH18_0-10
		Client:	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd
Parameter	Method reference		M4178/37	M4178/38	M4178/39	M4178/40	M4178/41	M4178/42
Phosphorus (mg/kg P)	**Rayment & Lyons 2011 - 9E2 (Bray 1)		<1	9.5	4.2	7.6	17	21
pH	Rayment & Lyons 2011 - 4A1 (1:5 Water)		8.89	8.90	9.01	8.71	8.58	8.81
Electrical Conductivity (dS/m)	Rayment & Lyons 2011 - 3A1 (1:5 Water)		0.094	0.152	0.272	0.904	0.914	0.216
Estimated Organic Matter (% OM)	**Calculation: Total Carbon x 1.75		0.35	2.54	2.24	1.47	0.65	1.50
Exchangeable Calcium (cmol./kg)			7.3	31	28	20	13	30
			3,286	14,026	12,602	9,000	5,713	13,674
Exchangeable Magnesium (cmol./kg)			1,467	6,262	5,626	4,018	2,550	6,104
			4.6	9.8	12	13	10	8.7
Exchangeable Potassium (cmol./kg)			1,249	2,680	3,249	3,498	2,748	2,379
			557	1,196	1,450	1,562	1,227	1,062
Exchangeable Sodium (cmol./kg)			0.38	1.1	0.90	0.77	0.58	1.2
			332	973	789	673	510	1,051
Exchangeable Aluminium (cmol./kg)			148	435	352	300	228	469
			0.62	1.4	3.0	5.5	5.0	1.3
Exchangeable Hydrogen (cmol./kg)			318	696	1,536	2,827	2,590	665
			142	311	686	1,262	1,156	297
Exchangeable Calcium (kg/ha)			<0.01	<0.01	<0.01	<0.01	<0.01	<0.01
			<1	<1	<1	<1	<1	<1
Exchangeable Magnesium (kg/ha)			<1	<1	<1	<1	<1	<1
			<1	<1	<1	<1	<1	<1
Exchangeable Potassium (kg/ha)			<0.01	<0.01	<0.01	<0.01	<0.01	<0.01
			<1	<1	<1	<1	<1	<1
Exchangeable Sodium (kg/ha)			<1	<1	<1	<1	<1	<1
			<1	<1	<1	<1	<1	<1
Effective Cation Exchange Capacity (CEC) (cmol./kg)	**Calculation: Sum of Ca,Mg,K,Na,Al,H (cmol./kg)		13	44	44	39	28	42
Calcium (%)	**Base Saturation Calculations - Cation cmol./kg / ECEC x 100		57	72	64	51	45	73
Magnesium (%)			36	23	27	33	35	21
Potassium (%)			2.9	2.6	2.1	2.0	2.0	2.9
Sodium - ESP (%)			4.8	3.1	6.8	14	18	3.1
Aluminium (%)			0.03	0.00	0.00	0.00	0.01	0.00
Hydrogen (%)			0.00	0.00	0.00	0.00	0.00	0.00
Calcium/Magnesium Ratio	**Calculation: Calcium / Magnesium (cmol./kg)		1.6	3.2	2.4	1.6	1.3	3.5
Total Carbon (%)	Inhouse S4a (LECO Trumac Analyser)		0.20	1.45	1.28	0.84	0.37	0.86
Total Nitrogen (%)			0.08	0.09	0.08	0.03	0.02	0.06
Carbon/Nitrogen Ratio	**Calculation: Total Carbon/Total Nitrogen		2.6	16.3	15.6	27.9	17.7	14.5
Chloride Estimate (equiv. mg/kg)	**Calculation: Electrical Conductivity x 640		60	97	174	579	585	138

AGRICULTURAL SOIL ANALYSIS REPORT

81 samples supplied by SLR Consulting Australia Pty Ltd on 6/12/2021 . Lab Job No.M4178

Analysis requested by Alex Koeman. Your Job: PO: 620.30686

Level 2, 15 Astor Terrace BRISBANE QLD 4000

Sample ID:

Crop:

Client:

Sample 37	Sample 38	Sample 39	Sample 40	Sample 41	Sample 42
BH14_90-100	BH16_0-10	BH16_20-30	BH16_50-60	BH16_90-100	BH18_0-10
Soil	Soil	Soil	Soil	Soil	Soil
SLR Consulting Australia Pty Ltd	SLR Consulting Australia Pty Ltd	SLR Consulting Australia Pty Ltd	SLR Consulting Australia Pty Ltd	SLR Consulting Australia Pty Ltd	SLR Consulting Australia Pty Ltd
M4178/37	M4178/38	M4178/39	M4178/40	M4178/41	M4178/42

Parameter	Method reference
-----------	------------------

Notes:

- All results presented as a 40°C oven dried weight. Soil sieved and lightly crushed to < 2 mm.
- Methods from Rayment and Lyons, 2011. *Soil Chemical Methods - Australasia*. CSIRO Publishing: Collingwood.
- Soluble Salts included in Exchangeable Cations - NO PRE-WASH (unless requested).
- 'Morgan 1 Extract' adapted from 'Science in Agriculture', 'Non-Toxic Farming' and LaMotte Soil Handbook.
- Guidelines for phosphorus have been reduced for Australian soils.
- Indicative guidelines are based on 'Albrecht' and 'Reams' concepts.
- Total Acid Extractable Nutrients indicate a store of nutrients.
- National Environmental Protection (Assessment of Site Contamination) Measure 2013, Schedule B(1) - Guideline on Investigation Levels for Soil and Groundwater. Table 5-A Background Ranges.
- Information relating to testing colour codes is available on sheet 2 - 'Understanding your agricultural soil results'.
- Conversions for 1 cmol_e/kg = 230 mg/kg Sodium, 390 mg/kg Potassium, 122 mg/kg Magnesium, 200 mg/kg Calcium
- Conversions to kg/ha = mg/kg x 2.24
- The chloride calculation of Cl mg/L = EC x 640 is considered an estimate, and most likely an over-estimate.
- ** NATA accreditation does not cover the performance of this service.
- Analysis conducted between sample arrival date and reporting date.
- This report is not to be reproduced except in full. Results only relate to the item tested.
- All services undertaken by EAL are covered by the EAL Laboratory Services Terms and Conditions.
- This report was issued on 14/12/2021.

Quality Checked: Kris Saville
 Agricultural Co-Ordinator

KS

AGRICULTURAL SOIL ANALYSIS REPORT

81 samples supplied by SLR Consulting Australia Pty Ltd on 6/12/2021 . Lab Job No.M4178

Analysis requested by Alex Koeman. Your Job: PO: 620.30686

Level 2, 15 Astor Terrace BRISBANE QLD 4000

		Sample ID:	Sample 43	Sample 44	Sample 45	Sample 46	Sample 47	Sample 48
		Crop:	BH18_20-30	BH18_50-60	BH18_90-100	BH22_0-10	BH22_20-30	BH22_50-60
		Client:	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd
Parameter	Method reference		M4178/43	M4178/44	M4178/45	M4178/46	M4178/47	M4178/48
Phosphorus (mg/kg P)	**Rayment & Lyons 2011 - 9E2 (Bray 1)		20	21	24	15	7.6	4.3
pH	Rayment & Lyons 2011 - 4A1 (1:5 Water)		8.78	8.71	8.44	8.65	8.64	8.68
Electrical Conductivity (dS/m)	Rayment & Lyons 2011 - 3A1 (1:5 Water)		0.366	0.533	0.993	0.521	0.527	0.476
Estimated Organic Matter (% OM)	**Calculation: Total Carbon x 1.75		1.59	1.54	1.12	2.03	1.56	1.82
Exchangeable Calcium (cmol./kg)			31	31	22	32	31	30
			14,004	13,898	9,778	14,344	13,706	13,386
Exchangeable Magnesium (cmol./kg)			6,252	6,205	4,365	6,404	6,119	5,976
			11	14	13	10	11	12
Exchangeable Potassium (cmol./kg)			3,065	3,823	3,637	2,797	2,880	3,138
			1,368	1,707	1,624	1,249	1,285	1,401
Exchangeable Sodium (cmol./kg)			1.3	1.1	0.88	1.2	1.0	0.89
			1,097	935	771	1,033	910	780
Exchangeable Aluminium (cmol./kg)			490	417	344	461	406	348
			2.8	3.7	4.8	3.2	3.3	3.6
Exchangeable Hydrogen (cmol./kg)			1,465	1,912	2,460	1,625	1,715	1,855
			654	854	1,098	725	765	828
Exchangeable Calcium (kg/ha)			<0.01	<0.01	<0.01	<0.01	<0.01	<0.01
			<1	<1	<1	<1	<1	<1
Exchangeable Magnesium (kg/ha)			<1	<1	<1	<1	<1	<1
			<1	<1	<1	<1	<1	<1
Exchangeable Potassium (kg/ha)			<0.01	<0.01	<0.01	<0.01	<0.01	<0.01
			<1	<1	<1	<1	<1	<1
Exchangeable Sodium (kg/ha)			<1	<1	<1	<1	<1	<1
			<1	<1	<1	<1	<1	<1
Effective Cation Exchange Capacity (CEC) (cmol./kg)	**Calculation: Sum of Ca,Mg,K,Na,Al,H (cmol./kg)		47	50	41	47	45	46
Calcium (%)	**Base Saturation Calculations - Cation cmol./kg / ECEC x 100		67	62	53	69	67	65
Magnesium (%)			24	28	33	22	23	25
Potassium (%)			2.7	2.1	2.2	2.5	2.3	1.9
Sodium - ESP (%)			6.1	7.5	12	6.8	7.3	7.9
Aluminium (%)			0.00	0.00	0.00	0.00	0.00	0.00
Hydrogen (%)			0.00	0.00	0.00	0.00	0.00	0.00
Calcium/Magnesium Ratio	**Calculation: Calcium / Magnesium (cmol./kg)		2.8	2.2	1.6	3.1	2.9	2.6
Total Carbon (%)	Inhouse S4a (LECO Trumac Analyser)		0.91	0.88	0.64	1.16	0.89	1.04
Total Nitrogen (%)			0.06	0.07	0.74	0.12	0.11	0.10
Carbon/Nitrogen Ratio	**Calculation: Total Carbon/Total Nitrogen		15.4	12.2	0.9	9.7	8.4	10.1
Chloride Estimate (equiv. mg/kg)	**Calculation: Electrical Conductivity x 640		234	341	636	333	337	305

AGRICULTURAL SOIL ANALYSIS REPORT

81 samples supplied by SLR Consulting Australia Pty Ltd on 6/12/2021 . Lab Job No.M4178

Analysis requested by Alex Koeman. Your Job: PO: 620.30686

Level 2, 15 Astor Terrace BRISBANE QLD 4000

Sample ID:

Crop:

Client:

Sample 43	Sample 44	Sample 45	Sample 46	Sample 47	Sample 48
BH18_20-30	BH18_50-60	BH18_90-100	BH22_0-10	BH22_20-30	BH22_50-60
Soil	Soil	Soil	Soil	Soil	Soil
SLR Consulting Australia Pty Ltd	SLR Consulting Australia Pty Ltd	SLR Consulting Australia Pty Ltd	SLR Consulting Australia Pty Ltd	SLR Consulting Australia Pty Ltd	SLR Consulting Australia Pty Ltd
M4178/43	M4178/44	M4178/45	M4178/46	M4178/47	M4178/48

Parameter	Method reference
-----------	------------------

Notes:

- All results presented as a 40°C oven dried weight. Soil sieved and lightly crushed to < 2 mm.
- Methods from Rayment and Lyons, 2011. *Soil Chemical Methods - Australasia*. CSIRO Publishing: Collingwood.
- Soluble Salts included in Exchangeable Cations - NO PRE-WASH (unless requested).
- 'Morgan 1 Extract' adapted from 'Science in Agriculture', 'Non-Toxic Farming' and LaMotte Soil Handbook.
- Guidelines for phosphorus have been reduced for Australian soils.
- Indicative guidelines are based on 'Albrecht' and 'Reams' concepts.
- Total Acid Extractable Nutrients indicate a store of nutrients.
- National Environmental Protection (Assessment of Site Contamination) Measure 2013, Schedule B(1) - Guideline on Investigation Levels for Soil and Groundwater. Table 5-A Background Ranges.
- Information relating to testing colour codes is available on sheet 2 - 'Understanding your agricultural soil results'.
- Conversions for 1 cmol_e/kg = 230 mg/kg Sodium, 390 mg/kg Potassium, 122 mg/kg Magnesium, 200 mg/kg Calcium
- Conversions to kg/ha = mg/kg x 2.24
- The chloride calculation of Cl mg/L = EC x 640 is considered an estimate, and most likely an over-estimate.
- ** NATA accreditation does not cover the performance of this service.
- Analysis conducted between sample arrival date and reporting date.
- This report is not to be reproduced except in full. Results only relate to the item tested.
- All services undertaken by EAL are covered by the EAL Laboratory Services Terms and Conditions.
- This report was issued on 14/12/2021.

Quality Checked: Kris Saville
 Agricultural Co-Ordinator

KS

AGRICULTURAL SOIL ANALYSIS REPORT

81 samples supplied by SLR Consulting Australia Pty Ltd on 6/12/2021 . Lab Job No.M4178

Analysis requested by Alex Koeman. Your Job: PO: 620.30686

Level 2, 15 Astor Terrace BRISBANE QLD 4000

Analysis requested by Alex Rodman, Plot 6087, 616266666

Level 2, 15 Astor Terrace BRISBANE QLD 4000

		Sample ID:	Sample 49	Sample 50	Sample 51	Sample 52	Sample 53	Sample 54
		Crop:	BH22_90-100	BH26_0-10	BH26_20-30	BH26_50-60	BH26_90-100	BH29_0-10
		Client:	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd
	Parameter	Method reference	M4178/49	M4178/50	M4178/51	M4178/52	M4178/53	M4178/54
	Phosphorus (mg/kg P)	**Rayment & Lyons 2011 - 9E2 (Bray 1)	2.9	27	18	5.8	16	11
	pH	Rayment & Lyons 2011 - 4A1 (1:5 Water)	8.74	8.49	8.14	8.90	9.17	7.76
	Electrical Conductivity (dS/m)	Rayment & Lyons 2011 - 3A1 (1:5 Water)	0.350	0.082	0.330	0.302	0.232	0.084
	Estimated Organic Matter (% OM)	**Calculation: Total Carbon x 1.75	1.28	1.40	1.72	1.54	0.95	3.94
	Exchangeable Calcium (cmol./kg) (kg/ha) (mg/kg)	Rayment & Lyons 2011 - 15D3 (Ammonium Acetate)	23	23	22	26	18	29
			10,490	10,407	10,091	11,543	7,938	13,043
			4,683	4,646	4,505	5,153	3,544	5,823
	Exchangeable Magnesium (cmol./kg) (kg/ha) (mg/kg)		13	6.8	8.2	11	7.7	11
			3,602	1,853	2,232	3,094	2,106	2,969
			1,608	827	996	1,381	940	1,325
	Exchangeable Potassium (cmol./kg) (kg/ha) (mg/kg)		0.76	1.1	0.81	0.49	0.42	1.6
			666	980	706	427	366	1,406
			297	437	315	190	163	628
	Exchangeable Sodium (cmol./kg) (kg/ha) (mg/kg)		5.0	0.38	2.2	2.9	2.2	0.27
			2,570	198	1,142	1,481	1,130	138
			1,147	89	510	661	504	62
Exchangeable Aluminium (cmol./kg) (kg/ha) (mg/kg)	**Inhouse S37 (KCl)	<0.01	<0.01	<0.01	<0.01	<0.01	<0.01	
		<1	<1	<1	<1	<1	<1	
		<1	<1	<1	<1	<1	<1	
Exchangeable Hydrogen (cmol./kg) (kg/ha) (mg/kg)	**Rayment & Lyons 2011 - 15G1 (Acidity Titration)	<0.01	<0.01	<0.01	<0.01	<0.01	<0.01	
		<1	<1	<1	<1	<1	<1	
		<1	<1	<1	<1	<1	<1	
	Effective Cation Exchange Capacity (ECEC) (cmol./kg)	**Calculation: Sum of Ca,Mg,K,Na,Al,H (cmol./kg)	42	31	34	40	28	42
	Calcium (%)	**Base Saturation Calculations - Cation cmol./kg / ECEC x 100	55	74	67	64	63	69
	Magnesium (%)		31	22	24	28	28	26
	Potassium (%)		1.8	3.6	2.4	1.2	1.5	3.8
	Sodium - ESP (%)		12	1.2	6.6	7.1	7.8	0.64
	Aluminium (%)		0.00	0.00	0.00	0.00	0.00	0.00
	Hydrogen (%)		0.00	0.00	0.00	0.00	0.00	0.00
	Calcium/Magnesium Ratio	**Calculation: Calcium / Magnesium (cmol./kg)	1.8	3.4	2.7	2.3	2.3	2.7
	Total Carbon (%)	Inhouse S4a (LECO Trumac Analyser)	0.73	0.80	0.98	0.88	0.54	2.25
	Total Nitrogen (%)		0.08	0.08	0.10	0.09	0.05	0.18
	Carbon/Nitrogen Ratio	**Calculation: Total Carbon/Total Nitrogen	9.8	10.7	9.5	10.4	10.6	12.6
	Chloride Estimate (equiv. mg/kg)	**Calculation: Electrical Conductivity x 640	224	52	211	193	148	54

AGRICULTURAL SOIL ANALYSIS REPORT

81 samples supplied by SLR Consulting Australia Pty Ltd on 6/12/2021 . Lab Job No.M4178

Analysis requested by Alex Koeman. Your Job: PO: 620.30686

Level 2, 15 Astor Terrace BRISBANE QLD 4000

Sample ID:

Crop:

Client:

Sample 49	Sample 50	Sample 51	Sample 52	Sample 53	Sample 54
BH22_90-100	BH26_0-10	BH26_20-30	BH26_50-60	BH26_90-100	BH29_0-10
Soil	Soil	Soil	Soil	Soil	Soil
SLR Consulting Australia Pty Ltd	SLR Consulting Australia Pty Ltd	SLR Consulting Australia Pty Ltd	SLR Consulting Australia Pty Ltd	SLR Consulting Australia Pty Ltd	SLR Consulting Australia Pty Ltd
M4178/49	M4178/50	M4178/51	M4178/52	M4178/53	M4178/54

Parameter	Method reference
-----------	------------------

Notes:

- All results presented as a 40°C oven dried weight. Soil sieved and lightly crushed to < 2 mm.
- Methods from Rayment and Lyons, 2011. *Soil Chemical Methods - Australasia*. CSIRO Publishing: Collingwood.
- Soluble Salts included in Exchangeable Cations - NO PRE-WASH (unless requested).
- 'Morgan 1 Extract' adapted from 'Science in Agriculture', 'Non-Toxic Farming' and LaMotte Soil Handbook.
- Guidelines for phosphorus have been reduced for Australian soils.
- Indicative guidelines are based on 'Albrecht' and 'Reams' concepts.
- Total Acid Extractable Nutrients indicate a store of nutrients.
- National Environmental Protection (Assessment of Site Contamination) Measure 2013, Schedule B(1) - Guideline on Investigation Levels for Soil and Groundwater. Table 5-A Background Ranges.
- Information relating to testing colour codes is available on sheet 2 - 'Understanding your agricultural soil results'.
- Conversions for 1 cmol_e/kg = 230 mg/kg Sodium, 390 mg/kg Potassium, 122 mg/kg Magnesium, 200 mg/kg Calcium
- Conversions to kg/ha = mg/kg x 2.24
- The chloride calculation of Cl mg/L = EC x 640 is considered an estimate, and most likely an over-estimate.
- ** NATA accreditation does not cover the performance of this service.
- Analysis conducted between sample arrival date and reporting date.
- This report is not to be reproduced except in full. Results only relate to the item tested.
- All services undertaken by EAL are covered by the EAL Laboratory Services Terms and Conditions.
- This report was issued on 14/12/2021.

Quality Checked: Kris Saville
Agricultural Co-Ordinator



AGRICULTURAL SOIL ANALYSIS REPORT

81 samples supplied by SLR Consulting Australia Pty Ltd on 6/12/2021 . Lab Job No.M4178

Analysis requested by Alex Koeman. Your Job: PO: 620.30686

Level 2, 15 Astor Terrace BRISBANE QLD 4000

		Sample ID:	Sample 55	Sample 56	Sample 57	Sample 58	Sample 59	Sample 60
		Crop:	BH29_20-30	BH29_50-60	BH29_90-100	BH30_0-10	BH30_20-30	BH30_50-60
		Client:	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd
Parameter	Method reference		M4178/55	M4178/56	M4178/57	M4178/58	M4178/59	M4178/60
Phosphorus (mg/kg P)	**Rayment & Lyons 2011 - 9E2 (Bray 1)		15	31	35	2.1	1.5	1.1
pH	Rayment & Lyons 2011 - 4A1 (1:5 Water)		8.19	8.28	8.34	7.31	7.97	8.11
Electrical Conductivity (dS/m)	Rayment & Lyons 2011 - 3A1 (1:5 Water)		0.099	0.084	0.069	0.026	0.022	0.022
Estimated Organic Matter (% OM)	**Calculation: Total Carbon x 1.75		3.66	2.57	2.29	0.89	0.46	0.30
Exchangeable Calcium (cmol./kg)			24	21	20	20	13	12
			10,821	9,298	8,761	9,167	5,994	5,198
Exchangeable Magnesium (cmol./kg)			4,831	4,151	3,911	4,093	2,676	2,320
			8.3	7.6	7.2	8.8	7.5	8.1
Exchangeable Potassium (cmol./kg)			2,257	2,073	1,947	2,407	2,048	2,199
			1,008	925	869	1,074	914	982
Exchangeable Sodium (cmol./kg)			0.86	0.91	1.0	0.28	0.23	0.23
			755	797	881	248	203	198
Exchangeable Aluminium (cmol./kg)			337	356	393	111	91	88
			0.32	0.32	0.30	0.20	0.25	0.22
Exchangeable Hydrogen (cmol./kg)			164	165	154	103	130	114
			73	74	69	46	58	51
Exchangeable Calcium (kg/ha)			<0.01	<0.01	<0.01	<0.01	<0.01	<0.01
			<1	<1	<1	<1	<1	<1
Exchangeable Magnesium (kg/ha)			<1	<1	<1	<1	<1	<1
			<1	<1	<1	<1	<1	<1
Exchangeable Potassium (kg/ha)			<0.01	<0.01	<0.01	<0.01	<0.01	<0.01
			<1	<1	<1	<1	<1	<1
Exchangeable Sodium (kg/ha)			<1	<1	<1	<1	<1	<1
			<1	<1	<1	<1	<1	<1
Effective Cation Exchange Capacity (ECEC) (cmol./kg)	**Calculation: Sum of Ca,Mg,K,Na,Al,H (cmol./kg)		34	30	28	30	21	20
Calcium (%)	**Base Saturation Calculations - Cation cmol./kg / ECEC x 100		72	70	70	69	63	58
Magnesium (%)			25	26	26	30	35	40
Potassium (%)			2.6	3.1	3.6	0.95	1.1	1.1
Sodium - ESP (%)			0.95	1.1	1.1	0.67	1.2	1.1
Aluminium (%)			0.00	0.00	0.00	0.01	0.01	0.01
Hydrogen (%)			0.00	0.00	0.00	0.00	0.00	0.00
Calcium/Magnesium Ratio	**Calculation: Calcium / Magnesium (cmol./kg)		2.9	2.7	2.7	2.3	1.8	1.4
Total Carbon (%)	Inhouse S4a (LECO Trumac Analyser)		2.09	1.47	1.31	0.51	0.27	0.17
Total Nitrogen (%)			0.15	0.12	0.13	0.11	0.09	0.07
Carbon/Nitrogen Ratio	**Calculation: Total Carbon/Total Nitrogen		14.4	12.5	10.2	4.5	3.1	2.4
Chloride Estimate (equiv. mg/kg)	**Calculation: Electrical Conductivity x 640		63	54	44	17	14	14

AGRICULTURAL SOIL ANALYSIS REPORT

81 samples supplied by SLR Consulting Australia Pty Ltd on 6/12/2021 . Lab Job No.M4178

Analysis requested by Alex Koeman. Your Job: PO: 620.30686

Level 2, 15 Astor Terrace BRISBANE QLD 4000

Sample ID:

Crop:

Client:

Sample 55	Sample 56	Sample 57	Sample 58	Sample 59	Sample 60
BH29_20-30	BH29_50-60	BH29_90-100	BH30_0-10	BH30_20-30	BH30_50-60
Soil	Soil	Soil	Soil	Soil	Soil
SLR Consulting Australia Pty Ltd	SLR Consulting Australia Pty Ltd	SLR Consulting Australia Pty Ltd	SLR Consulting Australia Pty Ltd	SLR Consulting Australia Pty Ltd	SLR Consulting Australia Pty Ltd
M4178/55	M4178/56	M4178/57	M4178/58	M4178/59	M4178/60

Parameter	Method reference
-----------	------------------

Notes:

- All results presented as a 40°C oven dried weight. Soil sieved and lightly crushed to < 2 mm.
- Methods from Rayment and Lyons, 2011. *Soil Chemical Methods - Australasia*. CSIRO Publishing: Collingwood.
- Soluble Salts included in Exchangeable Cations - NO PRE-WASH (unless requested).
- 'Morgan 1 Extract' adapted from 'Science in Agriculture', 'Non-Toxic Farming' and LaMotte Soil Handbook.
- Guidelines for phosphorus have been reduced for Australian soils.
- Indicative guidelines are based on 'Albrecht' and 'Reams' concepts.
- Total Acid Extractable Nutrients indicate a store of nutrients.
- National Environmental Protection (Assessment of Site Contamination) Measure 2013, Schedule B(1) - Guideline on Investigation Levels for Soil and Groundwater. Table 5-A Background Ranges.
- Information relating to testing colour codes is available on sheet 2 - 'Understanding your agricultural soil results'.
- Conversions for 1 cmol_e/kg = 230 mg/kg Sodium, 390 mg/kg Potassium, 122 mg/kg Magnesium, 200 mg/kg Calcium
- Conversions to kg/ha = mg/kg x 2.24
- The chloride calculation of Cl mg/L = EC x 640 is considered an estimate, and most likely an over-estimate.
- ** NATA accreditation does not cover the performance of this service.
- Analysis conducted between sample arrival date and reporting date.
- This report is not to be reproduced except in full. Results only relate to the item tested.
- All services undertaken by EAL are covered by the EAL Laboratory Services Terms and Conditions.
- This report was issued on 14/12/2021.

Quality Checked: Kris Saville
 Agricultural Co-Ordinator



AGRICULTURAL SOIL ANALYSIS REPORT

81 samples supplied by SLR Consulting Australia Pty Ltd on 6/12/2021 . Lab Job No.M4178

Analysis requested by Alex Koeman. Your Job: PO: 620.30686

Level 2, 15 Astor Terrace BRISBANE QLD 4000

		Sample ID:	Sample 61	Sample 62	Sample 63	Sample 64	Sample 65	Sample 66
		Crop:	BH30_70-80	BH32_0-10	BH32_20-30	BH32_50-60	BH32_90-100	BH34_0-10
		Client:	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd
Parameter	Method reference		M4178/61	M4178/62	M4178/63	M4178/64	M4178/65	M4178/66
Phosphorus (mg/kg P)	**Rayment & Lyons 2011 - 9E2 (Bray 1)		1.3	11	5.3	1.7	2.6	9.3
pH	Rayment & Lyons 2011 - 4A1 (1:5 Water)		8.86	7.02	7.39	8.44	8.81	5.97
Electrical Conductivity (dS/m)	Rayment & Lyons 2011 - 3A1 (1:5 Water)		0.125	0.025	0.026	0.070	0.159	0.910
Estimated Organic Matter (% OM)	**Calculation: Total Carbon x 1.75		0.55	1.23	1.30	0.89	0.87	1.75
Exchangeable Calcium (cmol./kg)			17	3.8	4.6	8.9	13	5.6
			7,842	1,685	2,044	4,003	6,043	2,497
Exchangeable Magnesium (cmol./kg)			3,501	752	913	1,787	2,698	1,115
			11	0.80	0.80	2.4	3.2	3.9
Exchangeable Potassium (cmol./kg)			2,990	218	218	667	865	1,074
			1,335	98	97	298	386	480
Exchangeable Sodium (cmol./kg)			0.33	0.70	0.46	0.49	0.45	0.53
			288	610	407	428	396	463
Exchangeable Aluminium (cmol./kg)			129	272	182	191	177	207
			0.35	<0.065	0.07	0.30	0.36	1.8
Exchangeable Hydrogen (cmol./kg)			180	<33	34	156	186	921
			81	<15	15	69	83	411
Exchangeable Calcium (kg/ha)			<0.01	<0.01	<0.01	<0.01	<0.01	<0.01
			<1	<1	<1	<1	<1	<1
Exchangeable Magnesium (kg/ha)			<1	<1	<1	<1	<1	<1
			<1	<1	<1	<1	<1	<1
Exchangeable Potassium (kg/ha)			<0.01	<0.01	<0.01	<0.01	<0.01	0.01
			<1	<1	<1	<1	<1	<1
Exchangeable Sodium (kg/ha)			<1	<1	<1	<1	<1	<1
			<1	<1	<1	<1	<1	<1
Effective Cation Exchange Capacity (CEC) (cmol./kg)	**Calculation: Sum of Ca,Mg,K,Na,Al,H (cmol./kg)		29	5.3	5.9	12	17	12
Calcium (%)	**Base Saturation Calculations - Cation cmol./kg / ECEC x 100		60	71	77	73	77	47
Magnesium (%)			38	15	14	20	18	33
Potassium (%)			1.1	13	7.9	4.0	2.6	4.5
Sodium - ESP (%)			1.2	1.1	1.1	2.5	2.1	15
Aluminium (%)			0.01	0.06	0.06	0.02	0.02	0.03
Hydrogen (%)			0.00	0.00	0.00	0.00	0.00	0.10
Calcium/Magnesium Ratio	**Calculation: Calcium / Magnesium (cmol./kg)		1.6	4.7	5.7	3.6	4.2	1.4
Total Carbon (%)	Inhouse S4a (LECO Trumac Analyser)		0.32	0.71	0.74	0.51	0.50	1.00
Total Nitrogen (%)			0.08	0.10	0.09	0.10	0.07	0.14
Carbon/Nitrogen Ratio	**Calculation: Total Carbon/Total Nitrogen		3.8	7.3	8.0	5.1	7.0	7.4
Chloride Estimate (equiv. mg/kg)	**Calculation: Electrical Conductivity x 640		80	16	17	45	102	582

AGRICULTURAL SOIL ANALYSIS REPORT

81 samples supplied by SLR Consulting Australia Pty Ltd on 6/12/2021 . Lab Job No.M4178

Analysis requested by Alex Koeman. Your Job: PO: 620.30686

Level 2, 15 Astor Terrace BRISBANE QLD 4000

Sample ID:

Crop:

Client:

Sample 61	Sample 62	Sample 63	Sample 64	Sample 65	Sample 66
BH30_70-80	BH32_0-10	BH32_20-30	BH32_50-60	BH32_90-100	BH34_0-10
Soil	Soil	Soil	Soil	Soil	Soil
SLR Consulting Australia Pty Ltd	SLR Consulting Australia Pty Ltd	SLR Consulting Australia Pty Ltd	SLR Consulting Australia Pty Ltd	SLR Consulting Australia Pty Ltd	SLR Consulting Australia Pty Ltd
M4178/61	M4178/62	M4178/63	M4178/64	M4178/65	M4178/66

Parameter	Method reference
-----------	------------------

Notes:

- All results presented as a 40°C oven dried weight. Soil sieved and lightly crushed to < 2 mm.
- Methods from Rayment and Lyons, 2011. *Soil Chemical Methods - Australasia*. CSIRO Publishing: Collingwood.
- Soluble Salts included in Exchangeable Cations - NO PRE-WASH (unless requested).
- 'Morgan 1 Extract' adapted from 'Science in Agriculture', 'Non-Toxic Farming' and LaMotte Soil Handbook.
- Guidelines for phosphorus have been reduced for Australian soils.
- Indicative guidelines are based on 'Albrecht' and 'Reams' concepts.
- Total Acid Extractable Nutrients indicate a store of nutrients.
- National Environmental Protection (Assessment of Site Contamination) Measure 2013, Schedule B(1) - Guideline on Investigation Levels for Soil and Groundwater. Table 5-A Background Ranges.
- Information relating to testing colour codes is available on sheet 2 - 'Understanding your agricultural soil results'.
- Conversions for 1 cmol_e/kg = 230 mg/kg Sodium, 390 mg/kg Potassium, 122 mg/kg Magnesium, 200 mg/kg Calcium
- Conversions to kg/ha = mg/kg x 2.24
- The chloride calculation of Cl mg/L = EC x 640 is considered an estimate, and most likely an over-estimate.
- ** NATA accreditation does not cover the performance of this service.
- Analysis conducted between sample arrival date and reporting date.
- This report is not to be reproduced except in full. Results only relate to the item tested.
- All services undertaken by EAL are covered by the EAL Laboratory Services Terms and Conditions.
- This report was issued on 14/12/2021.

Quality Checked: Kris Saville
Agricultural Co-Ordinator



AGRICULTURAL SOIL ANALYSIS REPORT

81 samples supplied by SLR Consulting Australia Pty Ltd on 6/12/2021 . Lab Job No.M4178

Analysis requested by Alex Koeman. Your Job: PO: 620.30686

Level 2, 15 Astor Terrace BRISBANE QLD 4000

Analysis requested by Alex Rodman, Plot 6087, 01-02-00000

Level 2, 15 Astor Terrace BRISBANE QLD 4000

		Sample ID:	Sample 67	Sample 68	Sample 69	Sample 70	Sample 71	Sample 72
		Crop:	BH34_20-30	BH34_50-60	BH34_90-100	BH36_0-10	BH36_20-30	BH36_50-60
		Client:	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd
	Parameter	Method reference	M4178/67	M4178/68	M4178/69	M4178/70	M4178/71	M4178/72
	Phosphorus (mg/kg P)	**Rayment & Lyons 2011 - 9E2 (Bray 1)	3.9	2.4	4.6	2.9	2.0	1.1
	pH	Rayment & Lyons 2011 - 4A1 (1:5 Water)	6.05	8.17	8.60	7.14	7.17	5.88
	Electrical Conductivity (dS/m)	Rayment & Lyons 2011 - 3A1 (1:5 Water)	1.132	0.335	0.226	0.041	0.025	0.046
	Estimated Organic Matter (% OM)	**Calculation: Total Carbon x 1.75	1.39	0.78	0.50	1.98	0.79	0.59
	Exchangeable Calcium (cmol./kg) (kg/ha) (mg/kg)	Rayment & Lyons 2011 - 15D3 (Ammonium Acetate)	6.1	3.6	1.8	4.7	4.2	4.0
			2,741	1,634	790	2,119	1,887	1,798
			1,224	730	353	946	842	803
	Exchangeable Magnesium (cmol./kg) (kg/ha) (mg/kg)		6.5	5.8	3.3	0.47	0.71	2.1
			1,773	1,589	903	128	193	581
			792	709	403	57	86	259
	Exchangeable Potassium (cmol./kg) (kg/ha) (mg/kg)		<0.12	<0.12	<0.12	0.46	0.13	0.17
			<112	<112	<112	406	<112	152
			<50	<50	<50	181	<50	68
	Exchangeable Sodium (cmol./kg) (kg/ha) (mg/kg)		3.6	3.1	1.9	<0.065	<0.065	0.20
			1,879	1,615	996	<33	<33	103
			839	721	445	<15	<15	46
Exchangeable Aluminium (cmol./kg) (kg/ha) (mg/kg)	**Inhouse S37 (KCl)	<0.01	<0.01	<0.01	<0.01	<0.01	<0.01	
		<1	<1	<1	<1	<1	1.7	
		<1	<1	<1	<1	<1	<1	
Exchangeable Hydrogen (cmol./kg) (kg/ha) (mg/kg)	**Rayment & Lyons 2011 - 15G1 (Acidity Titration)	0.01	<0.01	<0.01	<0.01	<0.01	0.03	
		<1	<1	<1	<1	<1	<1	
		<1	<1	<1	<1	<1	<1	
	Effective Cation Exchange Capacity (ECEC) (cmol./kg)	**Calculation: Sum of Ca,Mg,K,Na,Al,H (cmol./kg)	16	13	7.1	5.7	5.1	6.6
	Calcium (%)	**Base Saturation Calculations - Cation cmol./kg / ECEC x 100	37	29	25	83	83	61
	Magnesium (%)		40	46	47	8.3	14	33
	Potassium (%)		0.67	0.88	0.99	8.1	2.5	2.6
	Sodium - ESP (%)		22	25	27	0.67	0.94	3.0
	Aluminium (%)		0.02	0.03	0.04	0.06	0.07	0.13
	Hydrogen (%)		0.07	0.00	0.00	0.00	0.00	0.47
	Calcium/Magnesium Ratio	**Calculation: Calcium / Magnesium (cmol./kg)	0.94	0.62	0.53	10	5.9	1.9
	Total Carbon (%)	Inhouse S4a (LECO Trumac Analyser)	0.80	0.45	0.29	1.13	0.45	0.34
	Total Nitrogen (%)		0.13	0.09	0.09	0.14	0.10	0.10
	Carbon/Nitrogen Ratio	**Calculation: Total Carbon/Total Nitrogen	6.3	4.8	3.1	7.9	4.8	3.3
	Chloride Estimate (equiv. mg/kg)	**Calculation: Electrical Conductivity x 640	724	214	145	26	16	29

AGRICULTURAL SOIL ANALYSIS REPORT

81 samples supplied by SLR Consulting Australia Pty Ltd on 6/12/2021 . Lab Job No.M4178

Analysis requested by Alex Koeman. Your Job: PO: 620.30686

Level 2, 15 Astor Terrace BRISBANE QLD 4000

Sample ID:

Crop:

Client:

Sample 67	Sample 68	Sample 69	Sample 70	Sample 71	Sample 72
BH34_20-30	BH34_50-60	BH34_90-100	BH36_0-10	BH36_20-30	BH36_50-60
Soil	Soil	Soil	Soil	Soil	Soil
SLR Consulting Australia Pty Ltd	SLR Consulting Australia Pty Ltd	SLR Consulting Australia Pty Ltd	SLR Consulting Australia Pty Ltd	SLR Consulting Australia Pty Ltd	SLR Consulting Australia Pty Ltd
M4178/67	M4178/68	M4178/69	M4178/70	M4178/71	M4178/72

Parameter	Method reference
-----------	------------------

Notes:

- All results presented as a 40°C oven dried weight. Soil sieved and lightly crushed to < 2 mm.
- Methods from Rayment and Lyons, 2011. *Soil Chemical Methods - Australasia*. CSIRO Publishing: Collingwood.
- Soluble Salts included in Exchangeable Cations - NO PRE-WASH (unless requested).
- 'Morgan 1 Extract' adapted from 'Science in Agriculture', 'Non-Toxic Farming' and LaMotte Soil Handbook.
- Guidelines for phosphorus have been reduced for Australian soils.
- Indicative guidelines are based on 'Albrecht' and 'Reams' concepts.
- Total Acid Extractable Nutrients indicate a store of nutrients.
- National Environmental Protection (Assessment of Site Contamination) Measure 2013, Schedule B(1) - Guideline on Investigation Levels for Soil and Groundwater. Table 5-A Background Ranges.
- Information relating to testing colour codes is available on sheet 2 - 'Understanding your agricultural soil results'.
- Conversions for 1 cmol_e/kg = 230 mg/kg Sodium, 390 mg/kg Potassium, 122 mg/kg Magnesium, 200 mg/kg Calcium
- Conversions to kg/ha = mg/kg x 2.24
- The chloride calculation of Cl mg/L = EC x 640 is considered an estimate, and most likely an over-estimate.
- ** NATA accreditation does not cover the performance of this service.
- Analysis conducted between sample arrival date and reporting date.
- This report is not to be reproduced except in full. Results only relate to the item tested.
- All services undertaken by EAL are covered by the EAL Laboratory Services Terms and Conditions.
- This report was issued on 14/12/2021.

Quality Checked: Kris Saville
 Agricultural Co-Ordinator



AGRICULTURAL SOIL ANALYSIS REPORT

81 samples supplied by SLR Consulting Australia Pty Ltd on 6/12/2021 . Lab Job No.M4178

Analysis requested by Alex Koeman. Your Job: PO: 620.30686

Level 2, 15 Astor Terrace BRISBANE QLD 4000

Analysis requested by Alex Rodman, Plot 6081, 01-02-2020

Level 2, 15 Astor Terrace BRISBANE QLD 4000

		Sample ID:	Sample 73	Sample 74	Sample 75	Sample 76	Sample 77	Sample 78
		Crop:	BH36_90-100	BH38_0-10	BH38_20-30	BH38_50-60	BH38_90-100	BH39_0-10
		Client:	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd
	Parameter	Method reference	M4178/73	M4178/74	M4178/75	M4178/76	M4178/77	M4178/78
	Phosphorus (mg/kg P)	**Rayment & Lyons 2011 - 9E2 (Bray 1)	1.1	14	9.4	2.0	1.7	4.6
	pH	Rayment & Lyons 2011 - 4A1 (1:5 Water)	6.66	5.63	4.96	4.58	4.63	8.74
	Electrical Conductivity (dS/m)	Rayment & Lyons 2011 - 3A1 (1:5 Water)	0.091	0.324	0.635	0.849	0.944	0.126
	Estimated Organic Matter (% OM)	**Calculation: Total Carbon x 1.75	0.41	5.43	3.41	1.13	0.60	2.14
	Exchangeable Calcium (cmol./kg) (kg/ha) (mg/kg)	Rayment & Lyons 2011 - 15D3 (Ammonium Acetate)	4.8	2.7	0.89	0.18	0.13	31
			2,160	1,225	399	81	57	13,883
			964	547	178	36	25	6,198
	Exchangeable Magnesium (cmol./kg) (kg/ha) (mg/kg)		3.6	6.4	7.1	8.7	9.3	9.2
			969	1,738	1,926	2,356	2,536	2,496
			433	776	860	1,052	1,132	1,114
	Exchangeable Potassium (cmol./kg) (kg/ha) (mg/kg)		0.16	0.62	0.37	0.30	0.31	1.0
			138	539	328	261	272	883
			61	241	147	117	121	394
	Exchangeable Sodium (cmol./kg) (kg/ha) (mg/kg)		0.78	0.78	1.9	3.9	5.6	1.2
			402	402	987	2,009	2,872	618
			179	180	441	897	1,282	276
Exchangeable Aluminium (cmol./kg) (kg/ha) (mg/kg)	**Inhouse S37 (KCl)	<0.01	0.02	0.29	0.48	0.48	<0.01	
		1.1	4.9	59	98	98	<1	
		<1	2.2	26	44	44	<1	
Exchangeable Hydrogen (cmol./kg) (kg/ha) (mg/kg)	**Rayment & Lyons 2011 - 15G1 (Acidity Titration)	<0.01	0.04	0.28	0.46	0.60	<0.01	
		<1	<1	6.2	10	14	<1	
		<1	<1	2.8	4.6	6.0	<1	
	Effective Cation Exchange Capacity (ECEC) (cmol./kg)	**Calculation: Sum of Ca,Mg,K,Na,Al,H (cmol./kg)	9.3	11	11	14	16	42
	Calcium (%)	**Base Saturation Calculations - Cation cmol./kg / ECEC x 100	52	26	8.2	1.3	0.77	73
	Magnesium (%)		38	60	65	62	57	22
	Potassium (%)		1.7	5.8	3.5	2.1	1.9	2.4
	Sodium - ESP (%)		8.4	7.4	18	28	34	2.8
	Aluminium (%)		0.06	0.23	2.7	3.5	3.0	0.00
	Hydrogen (%)		0.00	0.36	2.6	3.3	3.7	0.00
	Calcium/Magnesium Ratio	**Calculation: Calcium / Magnesium (cmol./kg)	1.4	0.43	0.13	0.02	0.01	3.4
	Total Carbon (%)	Inhouse S4a (LECO Trumac Analyser)	0.24	3.10	1.95	0.65	0.34	1.22
	Total Nitrogen (%)		0.08	0.22	0.17	0.11	0.03	0.06
	Carbon/Nitrogen Ratio	**Calculation: Total Carbon/Total Nitrogen	2.8	14.4	11.8	5.8	13.8	20.3
	Chloride Estimate (equiv. mg/kg)	**Calculation: Electrical Conductivity x 640	58	207	406	543	604	81

AGRICULTURAL SOIL ANALYSIS REPORT

81 samples supplied by SLR Consulting Australia Pty Ltd on 6/12/2021 . Lab Job No.M4178

Analysis requested by Alex Koeman. Your Job: PO: 620.30686

Level 2, 15 Astor Terrace BRISBANE QLD 4000

Sample ID:

Crop:

Client:

Sample 73	Sample 74	Sample 75	Sample 76	Sample 77	Sample 78
BH36_90-100	BH38_0-10	BH38_20-30	BH38_50-60	BH38_90-100	BH39_0-10
Soil	Soil	Soil	Soil	Soil	Soil
SLR Consulting Australia Pty Ltd	SLR Consulting Australia Pty Ltd	SLR Consulting Australia Pty Ltd	SLR Consulting Australia Pty Ltd	SLR Consulting Australia Pty Ltd	SLR Consulting Australia Pty Ltd
M4178/73	M4178/74	M4178/75	M4178/76	M4178/77	M4178/78

Parameter	Method reference
-----------	------------------

Notes:

- All results presented as a 40°C oven dried weight. Soil sieved and lightly crushed to < 2 mm.
- Methods from Rayment and Lyons, 2011. *Soil Chemical Methods - Australasia*. CSIRO Publishing: Collingwood.
- Soluble Salts included in Exchangeable Cations - NO PRE-WASH (unless requested).
- 'Morgan 1 Extract' adapted from 'Science in Agriculture', 'Non-Toxic Farming' and LaMotte Soil Handbook.
- Guidelines for phosphorus have been reduced for Australian soils.
- Indicative guidelines are based on 'Albrecht' and 'Reams' concepts.
- Total Acid Extractable Nutrients indicate a store of nutrients.
- National Environmental Protection (Assessment of Site Contamination) Measure 2013, Schedule B(1) - Guideline on Investigation Levels for Soil and Groundwater. Table 5-A Background Ranges.
- Information relating to testing colour codes is available on sheet 2 - 'Understanding your agricultural soil results'.
- Conversions for 1 cmol_e/kg = 230 mg/kg Sodium, 390 mg/kg Potassium, 122 mg/kg Magnesium, 200 mg/kg Calcium
- Conversions to kg/ha = mg/kg x 2.24
- The chloride calculation of Cl mg/L = EC x 640 is considered an estimate, and most likely an over-estimate.
- ** NATA accreditation does not cover the performance of this service.
- Analysis conducted between sample arrival date and reporting date.
- This report is not to be reproduced except in full. Results only relate to the item tested.
- All services undertaken by EAL are covered by the EAL Laboratory Services Terms and Conditions.
- This report was issued on 14/12/2021.

Quality Checked: Kris Saville
 Agricultural Co-Ordinator

KS

AGRICULTURAL SOIL ANALYSIS REPORT

81 samples supplied by SLR Consulting Australia Pty Ltd on 6/12/2021 . Lab Job No.M4178

Analysis requested by Alex Koeman. Your Job: PO: 620.30686

Level 2, 15 Astor Terrace BRISBANE QLD 4000

		Sample ID:	Sample 79	Sample 80	Sample 81	Heavy Soil	Medium Soil	Light Soil	Sandy Soil
		Crop:	BH39_20-30	BH39_50-60	BH39_90-100				
		Client:	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd	Clay	Clay Loam	Loam	Loamy Sand
Parameter		Method reference	M4178/79	M4178/80	M4178/81	Indicative guidelines - refer to Notes 6 and 8			
Phosphorus (mg/kg P)		**Rayment & Lyons 2011 - 9E2 (Bray 1)	5.4	2.0	7.0	45 ^{note 8}	30 ^{note 8}	24 ^{note 8}	20 ^{note 8}
pH		Rayment & Lyons 2011 - 4A1 (1:5 Water)	8.70	8.66	8.62	6.5	6.5	6.3	6.3
Electrical Conductivity (dS/m)		Rayment & Lyons 2011 - 3A1 (1:5 Water)	0.210	0.384	0.671	0.200	0.150	0.120	0.100
Estimated Organic Matter (% OM)		**Calculation: Total Carbon x 1.75	2.17	1.74	1.54	> 5.5	>4.5	> 3.5	> 2.5
Exchangeable Calcium	(cmol./kg)	Rayment & Lyons 2011 - 15D3 (Ammonium Acetate)	28	29	22	15.6	10.8	5.0	1.9
	(kg/ha)		12,656	13,041	9,887	7000	4816	2240	840
	(mg/kg)		5,650	5,822	4,414	3125	2150	1000	375
Exchangeable Magnesium	(cmol./kg)		10	12	9.9	2.4	1.7	1.2	0.60
	(kg/ha)		2,743	3,242	2,689	650	448	325	168
	(mg/kg)		1,225	1,447	1,200	290	200	145	75
Exchangeable Potassium	(cmol./kg)		0.90	0.72	0.65	0.60	0.50	0.40	0.30
	(kg/ha)		790	631	573	526	426	336	224
	(mg/kg)		353	281	256	235	190	150	100
Exchangeable Sodium	(cmol./kg)		2.4	4.0	4.6	0.3	0.26	0.22	0.11
	(kg/ha)		1,213	2,079	2,348	155	134	113	57
	(mg/kg)		542	928	1,048	69	60	51	25
Exchangeable Aluminium	(cmol./kg)	**Inhouse S37 (KCl)	<0.01	<0.01	<0.01	0.6	0.5	0.4	0.2
	(kg/ha)		<1	<1	<1	121	101	73	30
	(mg/kg)		<1	<1	<1	54	45	32	14
Exchangeable Hydrogen	(cmol./kg)	**Rayment & Lyons 2011 - 15G1 (Acidity Titration)	<0.01	<0.01	<0.01	0.6	0.5	0.4	0.2
	(kg/ha)		<1	<1	<1	13	11	8	3
	(mg/kg)		<1	<1	<1	6	5	4	2
Effective Cation Exchange Capacity (CEC) (cmol./kg)		**Calculation: Sum of Ca,Mg,K,Na,Al,H (cmol./kg)	42	46	37	20.1	14.3	7.8	3.3
Calcium (%)		**Base Saturation Calculations - Cation cmol./kg / CEC x 100	68	64	59	77.6	75.7	65.6	57.4
Magnesium (%)			24	26	27	11.9	11.9	15.7	18.1
Potassium (%)			2.2	1.6	1.8	3.0	3.5	5.2	9.1
Sodium - ESP (%)			5.7	8.8	12	1.5	1.8	2.9	3.3
Aluminium (%)			0.00	0.00	0.00	6.0	7.1	10.5	12.1
Hydrogen (%)			0.00	0.00	0.00				
Calcium/Magnesium Ratio		**Calculation: Calcium / Magnesium (cmol./kg)	2.8	2.4	2.2	6.5	6.4	4.2	3.2
Total Carbon (%)		Inhouse S4a (LECO Trumac Analyser)	1.24	1.00	0.88	> 3.1	> 2.6	> 2.0	> 1.4
Total Nitrogen (%)			0.06	0.05	0.02	> 0.30	> 0.25	> 0.20	> 0.15
Carbon/Nitrogen Ratio		**Calculation: Total Carbon/Total Nitrogen	20.7	18.8	36.6	10-12	10-12	10-12	10-12
Chloride Estimate (equiv. mg/kg)		**Calculation: Electrical Conductivity x 640	134	246	429

AGRICULTURAL SOIL ANALYSIS REPORT

81 samples supplied by SLR Consulting Australia Pty Ltd on 6/12/2021 . Lab Job No.M4178
 Analysis requested by Alex Koeman. Your Job: PO: 620.30686
 Level 2, 15 Astor Terrace BRISBANE QLD 4000

	Sample ID:	Sample 79	Sample 80	Sample 81	Heavy Soil	Medium Soil	Light Soil	Sandy Soil
	Crop:	BH39_20-30	BH39_50-60	BH39_90-100				
	Client:	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd	Soil SLR Consulting Australia Pty Ltd	Clay	Clay Loam	Loam	Loamy Sand
Parameter	Method reference	M4178/79	M4178/80	M4178/81	Indicative guidelines - refer to Notes 6 and 8			

Notes:

- All results presented as a 40°C oven dried weight. Soil sieved and lightly crushed to < 2 mm.
- Methods from Rayment and Lyons, 2011. *Soil Chemical Methods - Australasia*. CSIRO Publishing: Collingwood.
- Soluble Salts included in Exchangeable Cations - NO PRE-WASH (unless requested).
- 'Morgan 1 Extract' adapted from 'Science in Agriculture', 'Non-Toxic Farming' and LaMotte Soil Handbook.
- Guidelines for phosphorus have been reduced for Australian soils.
- Indicative guidelines are based on 'Albrecht' and 'Reams' concepts.
- Total Acid Extractable Nutrients indicate a store of nutrients.
- National Environmental Protection (Assessment of Site Contamination) Measure 2013, Schedule B(1) - Guideline on Investigation Levels for Soil and Groundwater. Table 5-A Background Ranges.
- Information relating to testing colour codes is available on sheet 2 - 'Understanding your agricultural soil results'.
- Conversions for 1 cmol_e/kg = 230 mg/kg Sodium, 390 mg/kg Potassium, 122 mg/kg Magnesium, 200 mg/kg Calcium
- Conversions to kg/ha = mg/kg x 2.24
- The chloride calculation of Cl mg/L = EC x 640 is considered an estimate, and most likely an over-estimate.
- ** NATA accreditation does not cover the performance of this service.
- Analysis conducted between sample arrival date and reporting date.
- This report is not to be reproduced except in full. Results only relate to the item tested.
- All services undertaken by EAL are covered by the EAL Laboratory Services Terms and Conditions.
- This report was issued on 14/12/2021.

Quality Checked: Kris Saville
 Agricultural Co-Ordinator

KS

APPENDIX B

Detailed Profile Descriptions

BH01

Brown Kandosol

Table 1 Summary Brown Kandosol



Overview	
Landscape SMU 3	
	
Coordinates (GDA94 Zone55)	650406 m E, 7407082 m N,
ASC Name	Brown Kandosol
Representative SMU	3
Survey Type	Detailed
Dominant Land Use	Reserve
Microrelief	Nil
Vegetation	Eucalyptus
Slope (%)	6%
Slope Method	Clinometer
Surface Condition	Crusting

Table 2 Profile: Brown Kandosol

Profile	
	
Horizon / Depth (cm)	Description
A1 0-10cm	Dark greyish brown (10YR 4/2) clayey sand, moderate structure of subangular blocky peds with a rough fabric and firm consistence. 6 field pH. fragment size (medium gravel, 2-10%). Nil segregations. Sampled 0-10cm
B21 10-45cm	Brown (10YR 5/3) clay loam (sandy), weak structure of <2mm angular blocky peds with a rough fabric and firm consistence. 4.5 field pH. fragment size (fine gravel, 10-20%). Nil segregations. Sampled 20-30cm, 40-45cm
A2 45-50cm	Pale brown (10YR 5/3) clayey sand, weak structure of <2mm angular blocky peds with a rough fabric and a firm consistence. 4 field pH. fragment size (fine gravel, 20-50%). Nil segregations. Sampled 45-50 cm

BH02

Magnesian Brown Kandosol

Table 3 Summary Magnesian Brown Kandosol



Overview	
Landscape SMU 3	
	
Coordinates (GDA94 Zone55)	650559 m E, 7407168 m N
ASC Name	Magnesian Brown Kandosol
Representative SMU	3
Survey Type	Detailed
Dominant Land Use	Reserve
Microrelief	Nil
Vegetation	Eucalyptus
Slope (%)	3%
Slope Method	Clinometer
Surface Condition	Crusting

Table 4 Profile: Magnesian Brown Kandosol

Profile	
	
Horizon / Depth (cm)	Description
A1 0-25cm	Dark brown (10YR 3/3) sandy loam clay, moderate structure of angular blocky peds with a rough fabric and firm consistence. 6 field pH, fragment size (medium gravel, 10-20%). Nil segregations. Sampled 0-10cm, 20-25cm
A2 25-55cm	Brown (10YR 5/3) loamy sand, weak structure of <2mm angular blocky peds with a rough fabric and firm consistence. 5.5 field pH, fragment size (fine gravel, 10-20%). Nil segregations. Sampled 25-30cm, 50-55cm

Profile	
B2 55cm-100cm	Strong brown (7.5YR 5/6) sandy loam, weak structure of angular blocky peds with a rough fabric and firm consistence. 5 field pH, fragment size (fine gravel, 20-50%). Nil segregations. Sampled 90 – 100cm

BH03

Dystrophic Brown Kandosol

Table 5 Summary Dystrophic Brown Kandosol



Overview	
Landscape SMU 3	
	
Coordinates (GDA94 Zone55)	650548 m E, 7407911 m N
ASC Name	Dystrophic Brown Kandosol
Representative SMU	3
Survey Type	Detailed
Dominant Land Use	Reserve
Microrelief	Nil
Vegetation	Brigalow
Slope (%)	3%
Slope Method	Clinometer
Surface Condition	Firm

Table 6 Profile: Dystrophic Brown Kandosol

Profile	
	
Horizon / Depth (cm)	Description
A1 0-20cm	Dark brown (7.5YR 3/4) light medium clay, weak structure of 2-6mm subangular blocky peds with a rough fabric and firm consistence. 4.5 field pH. 2-10% faint orange mottling. 6-20mm fragment size (medium gravel, 2-10%). Nil segregations. Sampled 0-10cm
A12 20-40cm	Dark brown (7.5YR 3/1) light clay, weak structure of <2mm subangular blocky peds with a rough fabric and firm consistence. 2-10% Faint orange mottling. 2-6mm fragment size (fine gravel, 2-10%). Nil segregations. Refusal on rock at 40cm. Sampled 20-30cm, 30-40cm

BH04

Clastic Rudosol

Table 7 Summary Clastic Rudosol



Overview	
Landscape SMU 4	
	
Coordinates (GDA94 Zone55)	650016 m E, 7408165 N
ASC Name	Clastic Rudosol
Representative SMU	4
Survey Type	Detailed
Dominant Land Use	Grazing
Microrelief	Nil
Vegetation	Brigalow
Slope (%)	5%
Slope Method	Clinometer
Surface Condition	Loose

Table 8 Profile: Clastic Rudosol

Profile	
	
Horizon / Depth (cm)	Description
A1 0-25cm	Very dark grey (10YR 3/1) sandy clay loam, weak structure of <2mm angular blocky peds with a rough fabric and loose consistence. 4.5 field pH. 10-20% faint grey mottling. 20-60mm fragment size (coarse gravel, 50-90%). Nil segregations. Sampled 0-10cm & 15-25cm

BH05

Magnesian Brown Dermosol

Table 9 Summary Magnesian Brown Dermosol



Overview	
Landscape SMU 2A	
	
Coordinates (GDA94 Zone55)	649909 m E, 7407716 m N
ASC Name	Magnesian Brown Dermosol
Representative SMU	2A
Survey Type	Detailed
Dominant Land Use	Grazing
Microrelief	Nil
Vegetation	Brigalow
Slope (%)	4%
Slope Method	Clinometer
Surface Condition	Firm

Table 10 Profile: Magnesian Brown Dermosol

Profile	
	
Horizon / Depth (cm)	Description
A1 0-10cm	Yellowish brown (5YR 4/6) light medium clay, moderate structure of 2-5mm subangular blocky peds with a rough fabric and firm consistence. 7 field pH. 10-20% distinct brown mottling. 6-20mm fragment size (medium gravel, 10-20%). Nil segregations. Sampled 0-10cm
A2 10-45cm	Dark yellowish brown (10YR 3/6) sandy clay loam, strong structure of <2mm angular blocky peds with a rough fabric and firm consistence. 4.5 field pH. 2-10% faint grey mottling. 20-60mm fragment size (medium gravel, 10-20%). Nil segregations. Sampled 20-30cm.
B21 45-90cm	Strong brown (7.5YR 5/6) medium clay, moderate structure of <2mm subangular blocky peds with a rough fabric and firm consistence. 4.5 field pH. 20-50% faint orange mottling. 20-60mm fragment size (medium gravel, 10-20%). Nil segregations. Sampled 50-60cm.

Profile	
B22 90-100cm	Light brownish grey (10YR 6/2) medium clay, moderate structure of <2mm subangular blocky peds with a rough fabric and firm consistence. 4.5 field pH. 20-50% distinct red mottling. 20-60mm fragment size (medium gravel, 20-50%). Nil segregations. Sampled 90-100cm.

BH06

Magnesian Rudosol

Table 11 Magnesian Rudosol



Overview	
Landscape SMU 4	
	
Coordinates (GDA94 Zone55)	649917 m E, 7407869 m N
ASC Name	Magnesian Rudosol
Representative SMU	4
Survey Type	Detailed
Dominant Land Use	Grazing
Microrelief	Nil
Vegetation	Brigalow
Slope (%)	4%
Slope Method	Clinometer
Surface Condition	Loose

Table 12 Profile: Magnesic Rudosol

Profile	
	
Horizon / Depth (cm)	Description
A11 0-10cm	Dark Brown (10YR 3/3) sandy clay loam, weak structure of <2mm subangular blocky peds with a rough fabric and loose consistence. 4.5 field pH. 2-6mm fragment size (fine gravel, 2-10%). Nil segregations. Sampled 0-10cm.
A12 10-20cm	Brown (10YR 4/3) clayey sand, weak structure of <2mm polyhedral peds with a rough fabric and loose consistence. 4.5 field pH. 6-20mm fragment size (medium gravel, 2-10%). Nil segregations. Refusal on rock at 20cm. Sampled 10-20cm.

BH07

Magnesian Rudosol

Table 13 Summary Magnesian Rudosol



Overview	
Landscape SMU 4	
	
Coordinates (GDA94 Zone55)	650087 m E, 7407966 m N
ASC Name	Magnesian Rudosol
Representative SMU	4
Survey Type	Detailed
Dominant Land Use	Reserve
Microrelief	Nil
Vegetation	Brigalow
Slope (%)	5%
Slope Method	Clinometer
Surface Condition	Firm

Table 14 Profile: Magnesic Rudosol

Profile	
	
Horizon / Depth (cm)	Description
A11 0-20cm	Very dark brown (10YR 2/2) sandy clayey loam, weak structure of <2mm subangular blocky peds with a rough fabric and firm consistence. 6 field pH. 6-20mm fragment size (medium gravel, 20-50%). Nil segregations. Sampled 0-10cm & 10-20cm.
A12 20-60cm	Very pale brown (10YR 8/3) clayey sand, moderate structure with a rough fabric and firm consistence. 4.5 field pH. 20-50% distinct grey mottling. 20-60mm fragment size (coarse gravel, 50-90%). Nil segregations. Refusal on rock at 60cm. Sampled 30-40cm, 50 – 60cm.

BH08

Eutrophic Brown Dermosol

Table 15 Summary Eutrophic Brown Dermosol



Overview	
Landscape SMU 2A	
	
Coordinates (GDA94 Zone55)	649480 m E, 7407421 m N
ASC Name	Eutrophic Brown Dermosol
Representative SMU	2A
Survey Type	Detailed
Dominant Land Use	Grazing
Microrelief	Nil
Vegetation	Brigalow
Slope (%)	4%
Slope Method	Clinometer
Surface Condition	Very Fine

Table 16 Profile: Eutrophic Brown Dermosol

Profile	
	
Horizon / Depth (cm)	Description
A1 0-20cm	Dark yellowish brown (10YR 3/6) medium clay, moderate structure of <2mm angular blocky peds with a rough fabric and soft consistence. 7.5 field pH. 2-10% faint dark mottling. 6-20mm fragment size (coarse gravel, 2-10%). Nil segregations. Sampled 0-10cm
B21 20-85cm	Yellowish brown (10YR 5/6) medium clay, moderate structure of 2-5mm angular blocky peds with a rough fabric and soft consistence. 8.5 field pH. 20-50% distinct yellow mottling. 2-6mm fragment size (fine gravel, 10-20%). Nil segregations. Sampled 20-30cm, 50-60cm

Profile	
<p>B22 85cm-130cm</p>	<p>Brownish yellow (10YR 6/6) medium clay, strong structure of 2-5mm angular blocky peds with a rough fabric and soft consistence. 9 field pH. 20-50% distinct brown mottling. 20-60mm fragment size (fine gravel, 10-20%). Nil segregations. Sampled 90-100cm</p>
<p>B23 130cm-150cm</p>	<p>Light grey (10YR 7/2) medium heavy clay, moderate structure of <2mm subangular blocky peds with a rough fabric and soft consistence. 6 field pH. 50-90% prominent other mottling. 20-60mm fragment size (fine gravel, 10-20%). Nil segregations.</p>

BH09

Eutrophic Brown Dermosol

Table 17 Summary Eutrophic Brown Dermosol



Overview	
Landscape SMU 2A	
	
Coordinates (GDA94 Zone55)	649583 m E, 7406395 m N
ASC Name	Eutrophic Brown Dermosol
Representative SMU	2A
Survey Type	Detailed
Dominant Land Use	Grazing
Microrelief	Nil
Vegetation	Brigalow
Slope (%)	2%
Slope Method	Clinometer
Surface Condition	Very Fine

Table 18 Profile: Eutrophic Brown Dermosol

Profile	
	
Horizon / Depth (cm)	Description
A1 0-50cm	Dark brown (7.5YR 3/4) light clay, moderate structure of <2mm subangular blocky peds with a rough fabric and soft consistence. 7.5 field pH. 20-60mm fragment size (coarse gravel, 10-20%). Nil segregations. Sampled 0-10cm, 20-30cm
B21 50-150cm	Brown (10YR 5/3) light medium clay, strong structure of 2-5mm angular blocky peds with a rough fabric and soft consistence. 9 field pH. 10-20% distinct brown mottling. 2-6mm fragment size (fine gravel, 10-20%). Nil segregations. Sampled 50-60cm, 90-100cm

Profile	
B22 150-180cm	Dark greyish brown (2.5YR 4/2) clay loam (sandy), strong structure of <2mm angular blocky peds with a rough fabric and soft consistence. 9 field pH. 2-6mm fragment size (fine gravel, 10-20%). Nil segregations.

BH10

Eutrophic Grey Dermosol

Table 19 Summary Eutrophic Grey Dermosol



Overview	
Landscape SMU 2B	
	
Coordinates (GDA94 Zone55)	648803 m E, 7399553 m N
ASC Name	Eutrophic Grey Dermosol
Representative SMU	2B
Survey Type	Detailed
Dominant Land Use	Grazing
Microrelief	Nil
Vegetation	Brigalow
Slope (%)	<1%
Slope Method	Clinometer
Surface Condition	Very Fine

Table 20 Profile: Eutrophic Grey Dermosol

Profile	
	
Horizon / Depth (cm)	Description
A1 0-10cm	Very dark greyish brown (10YR 3/2) medium clay, moderate structure of <2mm subangular blocky peds with a rough fabric and soft consistence. 7.5 field pH. 2-10% faint grey mottling. 2-6mm fragment size (fine gravel, <2%). Nil segregations. Sampled 0-10cm
A2 10-70cm	Dark grey (10YR 4/1) light medium clay, moderate structure of <2mm subangular blocky peds with a rough fabric and soft consistence. 6.5 field pH. 2-10% faint brown mottling. 2-6mm fragment size (fine gravel, <2%). Nil segregations. Sampled 20-30cm, 50-60cm
B2 70 – 100cm	Brown (10YR 3/4) medium clay, strong structure of <2mm angular blocky peds with a rough fabric and soft consistence. 7 field pH. 10-20% distinct dark mottling. 2-6mm fragment size (fine gravel, 2-10%). Nil segregations. Sampled 70-80cm, 90cm –100cm.

BH11

Eutrophic Black Dermosol

Table 21 Summary Eutrophic Black Dermosol


Overview	
Landscape SMU 2B	
	
Coordinates (GDA94 Zone55)	649297 m E, 7399085 m N
ASC Name	Eutrophic Black Dermosol
Representative SMU	2B
Survey Type	Detailed
Dominant Land Use	Grazing
Microrelief	Nil
Vegetation	Brigalow
Slope (%)	2%
Slope Method	Clinometer
Surface Condition	Very Fine

Table 22 Profile: Eutrophic Black Dermosol

Profile	
	
Horizon / Depth (cm)	Description
A1 0-10cm	Dark yellowish brown (10YR 4/4) light medium clay, moderate structure of <2mm subangular blocky peds with a rough fabric and soft consistence. 9 field pH. 20-50% distinct dark mottling. 6-20mm fragment size (medium gravel, 2-10%). Nil segregations. Sampled 0-10cm.
B21 10-15cm	Very dark brown (10YR 2/2) sandy clay loam, weak structure of <2mm angular blocky peds with a rough fabric and soft consistence. 10.5 field pH. 20-50% distinct dark mottling. 6-20mm fragment size (medium gravel, 2-10%). Nil segregations.

Profile	
<p>B22 15cm-100cm</p>	<p>Dark yellowish brown (10YR 3/4) medium clay, moderate structure of <2mm angular blocky peds with a rough fabric and soft consistence. 9 field pH. 20-50% prominent pale mottling. 6-20mm fragment size (medium gravel, 2-10%). Nil segregations.</p> <p>Sampled 20-30cm, 50-60cm, 90cm-100cm.</p>

BH12

Dystrophic Red Dermosol

Table 23 Summary Dystrophic Red Dermosol


Overview	
Landscape SMU 2B	
	
Coordinates (GDA94 Zone55)	649271 m E, 7397655 m N
ASC Name	Dystrophic Red Dermosol
Representative SMU	2B
Survey Type	Detailed
Dominant Land Use	Grazing
Microrelief	Nil
Vegetation	Brigalow
Slope (%)	12%
Slope Method	Clinometer
Surface Condition	Loose

Table 24 Profile: Dystrophic Red Dermosol

Profile	
	
Horizon / Depth (cm)	Description
A1 0-10cm	Dark yellowish brown (10YR 3/4) sandy clay loam, weak structure of <2mm angular blocky peds with a rough fabric and loose consistence. 7 field pH. <2% faint orange mottling 2-6mm fragment size (fine gravel, <2%). Nil segregations. Sampled 0-10cm.
B21 10-25cm	Dark red (10YR 3/6) sandy clay loam, weak structure of <2mm angular blocky peds with a rough fabric and loose consistence. 7 field pH. <2% faint brown mottling. 2-6mm fragment size (fine gravel, 2-10%). Nil segregations. Sampled 20-25cm

Profile	
<p>B22 25-90cm</p>	<p>Dark red (2.5YR 3/6) medium clay, moderate structure of <2mm subangular blocky peds with a rough fabric and loose consistence. 7 field pH. 2-10% distinct brown mottling. 2-6mm fragment size (fine gravel, 2-10%). Nil segregations.</p> <p>Sampled 50-60cm</p>
<p>B23 90-100cm</p>	<p>Dark red (2.5YR 3/6) light medium clay, weak structure of <2mm subangular blocky peds with a rough fabric and loose consistence. 7 field pH. 2-10% faint orange mottling. 6-20mm fragment size (medium gravel, 2-10%). Nil segregations.</p> <p>Sampled 90-100cm</p>

BH13

Dystrophic Red Dermosol

Table 25 Summary Dystrophic Red Dermosol



Overview	
Landscape SMU 2B	
	
Coordinates (GDA94 Zone55)	648807 m E, 7398036 m N
ASC Name	Dystrophic Red Dermosol
Representative SMU	2B
Survey Type	Detailed
Dominant Land Use	Grazing
Microrelief	Nil
Vegetation	Brigalow
Slope (%)	3%
Slope Method	Clinometer
Surface Condition	Firm

Table 26 Profile: Dystrophic Red Dermosol

Profile	
	
Horizon / Depth (cm)	Description
A1 0-80cm	Reddish brown (2.5YR 4/4) sandy loam, weak structure of <2mm angular blocky peds with a rough fabric and firm consistence. 9 field pH. 2-10% faint brown mottling. 2-6mm fragment size (fine gravel, 2-10%). Nil segregations. Sampled 0-10cm, 20-30cm, 50-60cm
B21 80-200cm	Dark red (2.5YR 3/6) clay loam (sandy), moderate structure of <2mm subangular blocky peds with a rough fabric and firm consistence. 9 field pH. 10-20% distinct brown mottling. 6-20mm fragment size (medium gravel, 2-10%). Nil segregations. Sampled 90-100cm
B22 200-260cm	Dark red (2.5YR 3/6) clayey sand, weak structure of <2mm angular blocky peds with a rough fabric and firm consistence. 9 field pH. 20-60mm fragment size (coarse gravel, 10-20%). Nil segregations.

BH14

Eutrophic Brown Dermosol

Table 27 Summary Eutrophic Brown Dermosol


Overview	
Landscape SMU 2B	
	
Coordinates (GDA94 Zone55)	648772 m E, 7398507 m N
ASC Name	Eutrophic Brown Dermosol
Representative SMU	2B
Survey Type	Detailed
Dominant Land Use	Grazing
Microrelief	Nil
Vegetation	Brigalow
Slope (%)	<1%
Slope Method	Clinometer
Surface Condition	Very Fine

Table 28 Profile: Eutrophic Brown Dermosol

Profile	
	
Horizon / Depth (cm)	Description
A1 0-50cm	Very dark brown (10YR 2/2) light clay, weak structure of <2mm subangular blocky peds with a rough fabric and loose consistence. 7 field pH. No mottling. 2-6mm fragment size (fine gravel, <2%). Nil segregations. Sampled 0-10cm, 20-30cm
B21 50-75cm	Dark yellowish brown (10YR 4/6) medium clay, strong structure of <2mm subangular blocky peds with a rough fabric and loose consistence. 7.5 field pH. 10-20% distinct dark mottling. 2-6mm fragment size (fine gravel, 2-10%). Nil segregations. Sampled 50-60cm.
B22 75-100cm	Yellowish brown (10YR 5/8) medium heavy clay, strong structure of <2mm angular blocky peds with a rough fabric and loose consistence. 7 field pH. 20-50% distinct dark mottling. 6-20mm fragment size (fine gravel, 2-10%). Nil segregations. Sampled 90-100cm.

BH15

Eutrophic Brown Dermosol

Table 29 Summary Eutrophic Brown Dermosol


Overview	
Landscape SMU 2	
	
Coordinates (GDA94 Zone55)	649736 m E, 7406550 m N
ASC Name	Eutrophic Brown Dermosol
Representative SMU	2A
Survey Type	Detailed
Dominant Land Use	Grazing
Microrelief	Nil
Vegetation	Brigalow
Slope (%)	3%
Slope Method	Clinometer
Surface Condition	Very Fine

Table 30 Profile: Eutrophic Brown Dermosol

Profile	
	
Horizon / Depth (cm)	Description
A1 0-80cm	Dark yellowish brown (10YR 4/6) light medium clay, strong structure of <2mm angular blocky peds with a rough fabric and loose consistence. 7.5 field pH. <2% faint brown mottling. 6-20mm fragment size (medium gravel, 2-10%). Nil segregations. Sampled 0-10cm, 20-30cm, 50-60cm
A2 80-100cm	Dark yellowish brown (10YR 3/6) light clay, weak structure of <2mm subangular blocky peds with a rough fabric and loose consistence. 7 field pH. <2% faint brown mottling. 2-6mm fragment size (fine gravel, 2-10%). Nil segregations. Sampled 90-100cm.

BH16

Crusty Brown Vertosol

Table 31 Summary Crusty Brown Vertosol


Overview	
Landscape SMU 1	
	
Coordinates (GDA94 Zone55)	648554 m E, 7405873 m N
ASC Name	Crusty Brown Vertosol
Representative SMU	1
Survey Type	Detailed
Dominant Land Use	Leucaena cropping
Microrelief	Nil
Vegetation	Brigalow
Slope (%)	<1%
Slope Method	Clinometer
Surface Condition	Firm

Table 32 Profile: Crusty Brown Vertosol

Profile	
	
Horizon / Depth (cm)	Description
A1 0-10cm	Very dark greyish brown (10YR 3/2) medium clay, moderate structure of <2mm angular blocky peds with a rough fabric and cracking consistence. 8 field pH. 2-6mm fragment size (fine gravel, <2%). Nil segregations. Sampled 0-10cm.
B21 10-80cm	Very dark brown (10YR 2/2) medium clay, strong structure of angular blocky peds with a rough fabric and cracking consistence. 8.5 field pH. <2% faint orange mottling. 2-6mm fragment size (fine gravel, <2%). Nil segregations. Sampled 20-30cm, 50-60cm.


Profile	
B22 80-100cm	Dark yellowish brown (10YR 4/4) medium clay, moderate structure of angular blocky peds with a rough fabric and cracking consistence. 8.5 field pH. 2-6mm fragment size (fine gravel, 2-10%). Nil segregations. Sampled 90-100cm.

APPENDIX C

Check Site Descriptions


SMU 3 - Brown Kandosol

Table 1 Summary: Brown Kandosol (Check Site 1)

Overview		
ASC Name	Brown Kandosol	
Representative Site	CH01	
Soil Map Unit	3	
Survey Type	Check site	
Dominant Topography	Flat	
Dominant Land Use	Grazing	
Vegetation	Brigalow	
Slope (%)	10-32%	
Slope Type	Mid-slope	


SMU 4 - Rudosol

Table 2 Summary: Rudosol (Check Site 2)

Overview		
ASC Name	Rudosol	
Representative Site	CH02	
Soil Map Unit	4	
Survey Type	Check site	
Dominant Topography	Escarpment	
Dominant Land Use	Reserve	
Vegetation	Brigalow	
Slope (%)	10-32%	
Slope Type	Mid-slope	


SMU 4 - Rudosol

Table 3 Summary: Rudosol (Check Site 3)

Overview		
ASC Name	Rudosol	
Representative Site	CH03	
Soil Map Unit	4	
Survey Type	Check site	
Dominant Topography	Escarpment	
Dominant Land Use	Reserve	
Vegetation	Brigalow	
Slope (%)	10-32%	
Slope Type	Mid-slope	


SMU 4 - Rudosol

Table 4 Summary: Rudosol (Check Site 4)

Overview		
ASC Name	Rudosol	
Representative Site	CH04	
Soil Map Unit	4	
Survey Type	Check site	
Dominant Topography	Escarpment	
Dominant Land Use	Grazing	
Vegetation	Brigalow	
Slope (%)	3-10%	
Slope Type	Mid-slope	

SMU 4 - Rudosol

Table 5 Summary: Rudosol (Check Site 5)

Overview		
ASC Name	Rudosol	
Representative Site	CH05	
Soil Map Unit	4	
Survey Type	Check site	
Dominant Topography	Lower Slope	
Dominant Land Use	Grazing	
Vegetation	Brigalow	
Slope (%)	3-10%	
Slope Type	Lower slope	


SMU 3 - Brown Kandosol

Table 6 Summary: Brown Kandosol (Check Site 6)

Overview		
ASC Name	Brown Kandosol	
Representative Site	CH06	
Soil Map Unit	3	
Survey Type	Check site	
Dominant Topography	Escarpment	
Dominant Land Use	Grazing	
Vegetation	Brigalow	
Slope (%)	35-56%	
Slope Type	Lower slope	


SMU 2A - Brown Dermosol

Table 7 Summary : Brown Dermosol (Check Site 7)

Overview		
ASC Name	Brown Dermosol	
Representative Site	CH07	
Soil Map Unit	2A	
Survey Type	Check site	
Dominant Topography	Escarpment	
Dominant Land Use	Grazing	
Vegetation	Brigalow	
Slope (%)	1-3%	
Slope Type	Flat	


SMU 2A - Brown Dermosol

Table 8 Summary : Brown Dermosol (Check Site 8)

Overview		
ASC Name	Brown Dermosol	
Representative Site	CH08	
Soil Map Unit	2A	
Survey Type	Check site	
Dominant Topography	Plains	
Dominant Land Use	Grazing	
Vegetation	Brigalow	
Slope (%)	1-3%	
Slope Type	Simple Slope	


SMU 2A - Brown Dermosol

Table 9 Summary: Brown Dermosol (Check Site 9)

Overview		
ASC Name	Brown Dermosol	
Representative Site	CH09	
Soil Map Unit	2A	
Survey Type	Check site	
Dominant Topography	Plains	
Dominant Land Use	Grazing	
Vegetation	Brigalow	
Slope (%)	1-3%	
Slope Type	Lower slope	


SMU 2A - Brown Dermosol

Table 10 Summary : Brown Dermosol (Check Site 10)

Overview		
ASC Name	Brown Dermosol	
Representative Site	CH10	
Soil Map Unit	2A	
Survey Type	Check site	
Dominant Topography	Plains	
Dominant Land Use	Grazing	
Vegetation	Brigalow	
Slope (%)	1-3%	
Slope Type	Open depression	


SMU 3 - Brown Kandosol

Table 11 Summary : Brown Kandosol (Check Site 11)

Overview		
ASC Name	Brown Kandosol	
Representative Site	CH11	
Soil Map Unit	3	
Survey Type	Check site	
Dominant Topography	Escarpment	
Dominant Land Use	Grazing	
Vegetation	Eucalyptus	
Slope (%)	3-10%	
Slope Type	Mid slope	


SMU 3 - Red Kandosol

Table 12 Summary : Red Kandosol (Check Site 12)

Overview		
ASC Name	Red Kandosol	
Representative Site	CH12	
Soil Map Unit	3	
Survey Type	Check site	
Dominant Topography	Crest	
Dominant Land Use	Grazing	
Vegetation	Brigalow	
Slope (%)	3-10%	
Slope Type	Crest	


SMU 3 - Red Kandosol

Table 13 Summary : Red Kandosol (Check Site 13)

Overview		
ASC Name	Red Kandosol	
Representative Site	CH13	
Soil Map Unit	3	
Survey Type	Check site	
Dominant Topography	Escarpment	
Dominant Land Use	Grazing	
Vegetation	Brigalow	
Slope (%)	35-56%	
Slope Type	Upper slope	


SMU 2B - Brown Dermosol

Table 14 Summary : Brown Dermosol (Check Site 14)

Overview		
ASC Name	Brown Dermosol	
Representative Site	CH14	
Soil Map Unit	2B	
Survey Type	Check site	
Dominant Topography	Plains	
Dominant Land Use	Grazing	
Vegetation	Brigalow	
Slope (%)	1-3%	
Slope Type	Simple slope	



SMU 2B - Brown Dermosol

Table 15 Summary : Brown Dermosol (Check Site 15)

Overview		
ASC Name	Brown Dermosol	
Representative Site	CH15	
Soil Map Unit	2B	
Survey Type	Check site	
Dominant Topography	Plains	
Dominant Land Use	Grazing	
Vegetation	Brigalow	
Slope (%)	<1%	
Slope Type	Simple Slope	

SMU 2B - Brown Dermosol

Table 16 Summary : Brown Dermosol (Check Site 16)

Overview		
ASC Name	Brown Dermosol	 
Representative Site	CH16	
Soil Map Unit	2B	
Survey Type	Check site	
Dominant Topography	Plains	
Dominant Land Use	Grazing	
Vegetation	Brigalow	
Slope (%)	1-3%	
Slope Type	Crest	



SMU 2B - Brown Dermosol

Table 17 Summary : Brown Dermosol (Check Site 17)

Overview		
ASC Name	Brown Dermosol	
Representative Site	CH17	
Soil Map Unit	2B	
Survey Type	Check site	
Dominant Topography	Upper slope	
Dominant Land Use	Grazing	
Vegetation	Brigalow	
Slope (%)	1-3%	
Slope Type	Upper slope	


SMU 2B - Brown Dermosol

Table 18 Summary : Brown Dermosol (Check Site 18)

Overview		
ASC Name	Brown Dermosol	 
Representative Site	CH18	
Soil Map Unit	2B	
Survey Type	Check site	
Dominant Topography	Mid slope	
Dominant Land Use	Grazing	
Vegetation	Brigalow	
Slope (%)	1-3%	
Slope Type	Mid slope	

SMU 2B - Brown Dermosol

Table 19 Summary : Brown Dermosol (Check Site 19)

Overview		
ASC Name	Brown Dermosol	
Representative Site	CH19	
Soil Map Unit	2B	
Survey Type	Check site	
Dominant Topography	Plains	
Dominant Land Use	Grazing	
Vegetation	Brigalow	
Slope (%)	1-3%	
Slope Type	Mid slope	


SMU 2B - Brown Dermosol

Table 20 Summary : Brown Dermosol (Check Site 20)

Overview		
ASC Name	Brown Dermosol	
Representative Site	CH20	
Soil Map Unit	2B	
Survey Type	Check site	
Dominant Topography	Mid slope	
Dominant Land Use	Grazing	
Vegetation	Brigalow	
Slope (%)	1-3%	
Slope Type	Mid slope	


SMU 2B - Brown Dermosol

Table 21 Summary : Brown Dermosol (Check Site 21)

Overview		
ASC Name	Brown Dermosol	
Representative Site	CH21	
Soil Map Unit	2B	
Survey Type	Check site	
Dominant Topography	Mid slope	
Dominant Land Use	Grazing	
Vegetation	Brigalow	
Slope (%)	1-3%	
Slope Type	Mid slope	


SMU 2A - Brown Dermosol

Table 22 Summary : Brown Dermosol (Check Site 22)

Overview		
ASC Name	Brown Dermosol	
Representative Site	CH22	
Soil Map Unit	2A	
Survey Type	Check site	
Dominant Topography	Depression	
Dominant Land Use	Grazing	
Vegetation	Brigalow	
Slope (%)	3-10%	
Slope Type	Open depression	


SMU 2A - Brown Dermosol

Table 23 Summary : Brown Dermosol (Check Site 23)

Overview		
ASC Name	Brown Dermosol	
Representative Site	CH23	
Soil Map Unit	2A	
Survey Type	Check site	
Dominant Topography	Closed depression	
Dominant Land Use	Grazing	
Vegetation	Brigalow	
Slope (%)	3-10%	
Slope Type	Closed depression	



SMU 2A - Brown Dermosol

Table 24 Summary : Brown Dermosol (Check Site 24)

Overview		
ASC Name	Brown Dermosol	
Representative Site	CH24	
Soil Map Unit	2A	
Survey Type	Check site	
Dominant Topography	Open depression	
Dominant Land Use	Grazing	
Vegetation	Brigalow	
Slope (%)	1-3%	
Slope Type	Open depression	

SMU 2A - Brown Dermosol

Table 25 Summary : Brown Dermosol (Check Site 26)

Overview		
ASC Name	Brown Dermosol	
Representative Site	CH26	
Soil Map Unit	2A	
Survey Type	Check site	
Dominant Topography	Closed depression	
Dominant Land Use	Reserve	
Vegetation	Eucalyptus	
Slope (%)	1-3%	
Slope Type	Closed depression	

APPENDIX D

Emerson Aggregate Test Ratings

GRAIN SIZE ANALYSIS (hydrometer and sieving techniques)

81 soil samples supplied by SLR Consulting Australia on 6 December, 2021 - Lab Job No. M4178

Analysis requested by Alex Koeman. Client reference: PO 620.30686

Level 2, 15 Astor Terrace BRISBANE QLD 4000

SAMPLE ID	Lab Code	EMERSON AGGREGATE CLASS	MOISTURE CONTENT (% of water in sample)	TOTAL GRAVEL > 2 mm (% of total oven- dry equivalent)	GRAVEL > 4.75 mm (% of total oven-dry equivalent)	GRAVEL 2.00-4.75 mm (% of total oven- dry equivalent)	COARSE SAND 200-2000 µm (0.2-2.0 mm) (% of total oven- dry equivalent)	FINE SAND 20-200 µm (0.02-0.2 mm) (% of total oven- dry equivalent)	SILT 2-20 µm ISSS (% of total oven-dry equivalent)	CLAY < 2 µm (% of total oven-dry equivalent)	Total soil fractions (incl. Gravel)
BH02_0-10	M4178/1	3	5.4%	1.2%	0.0%	1.2%	35.7%	50.1%	5.0%	8.0%	100.0%
BH02_20-30	M4178/2	3	2.7%	13.7%	7.1%	6.6%	29.7%	21.3%	4.4%	30.9%	100.0%
BH02_50-60	M4178/3	3	6.8%	0.5%	0.0%	0.5%	16.9%	30.3%	4.2%	48.1%	100.0%
BH02_90-100	M4178/4	3	9.3%	2.8%	0.5%	2.3%	38.9%	40.8%	4.7%	12.8%	100.0%
BH03_0-10	M4178/5	4	15.0%	27.2%	12.5%	14.6%	25.1%	20.7%	4.9%	22.1%	100.0%
BH03_20-30	M4178/6	4	9.9%	13.9%	8.2%	5.7%	24.5%	30.9%	4.1%	26.6%	100.0%
BH03_30-40	M4178/7	4	9.3%	21.7%	9.7%	12.0%	17.3%	22.2%	7.9%	30.9%	100.0%
BH04_0-10	M4178/8	3	8.5%	15.1%	7.4%	19.6%	17.3%	40.2%	10.8%	14.3%	100.0%
BH04_15-25	M4178/9	4	6.8%	10.8%	3.7%	7.1%	21.8%	42.1%	11.0%	14.2%	100.0%
BH05_0-10	M4178/10	2	12.1%	0.0%	0.0%	1.1%	2.8%	14.9%	18.7%	62.5%	100.0%
BH05_20-30	M4178/11	2	11.5%	0.6%	0.0%	0.6%	2.7%	16.0%	21.1%	59.5%	100.0%
BH05_50-60	M4178/12	2	14.2%	0.1%	0.0%	0.1%	3.3%	17.5%	27.2%	52.0%	100.0%
BH05_90-100	M4178/13	2	14.5%	0.2%	0.0%	0.2%	5.0%	43.9%	39.2%	11.8%	100.0%
BH08_0-10	M4178/14	3	14.7%	6.2%	1.5%	4.7%	6.4%	22.7%	19.6%	45.1%	100.0%
BH08_20-30	M4178/15	4	13.0%	4.1%	2.1%	2.0%	4.0%	18.1%	21.7%	52.1%	100.0%
BH08_50-60	M4178/16	4	13.7%	3.0%	1.8%	1.2%	2.9%	14.7%	24.1%	55.3%	100.0%
BH08_90-100	M4178/17	3	12.5%	1.9%	0.0%	1.9%	3.7%	17.9%	24.6%	52.0%	100.0%
BH09_0-10	M4178/18	4	12.6%	3.8%	0.0%	3.8%	6.0%	25.6%	22.2%	42.3%	100.0%
BH09_20-30	M4178/19	3	12.6%	3.7%	0.4%	3.3%	7.3%	26.1%	22.5%	40.0%	100.0%
BH09_50-60	M4178/20	3	4.0%	0.4%	0.3%	0.1%	27.3%	47.1%	11.9%	13.4%	100.0%
BH09_90-100	M4178/21	2	9.6%	1.4%	0.0%	1.4%	38.6%	41.7%	11.5%	6.8%	100.0%
BH11_0-10	M4178/22	4	15.3%	3.7%	1.7%	2.0%	25.3%	32.6%	9.6%	28.9%	100.0%
BH11_20-30	M4178/23	2	12.7%	7.6%	4.7%	2.9%	24.7%	39.8%	5.6%	22.3%	100.0%
BH11_50-60	M4178/24	4	10.9%	2.4%	0.6%	1.8%	21.4%	43.9%	8.3%	24.0%	100.0%
BH11_90-100	M4178/25	4	9.5%	2.6%	0.5%	2.0%	20.6%	43.9%	9.4%	23.6%	100.0%
BH12_0-10	M4178/26	3	4.0%	0.6%	0.0%	0.6%	56.5%	33.8%	5.2%	3.9%	100.0%
BH12_20-30	M4178/27	3	5.8%	1.5%	0.0%	1.5%	54.2%	31.2%	4.3%	8.8%	100.0%
BH12_50-60	M4178/28	2	6.5%	3.3%	2.3%	1.0%	47.4%	29.9%	3.8%	15.6%	100.0%
BH12_90-100	M4178/29	2	6.4%	3.1%	0.0%	3.1%	46.3%	28.8%	4.7%	17.2%	100.0%
BH13_0-10	M4178/30	3	2.1%	2.5%	0.0%	2.5%	59.2%	28.5%	1.4%	8.4%	100.0%
BH13_20-30	M4178/31	3	2.2%	3.5%	0.6%	2.9%	57.4%	26.9%	2.0%	10.3%	100.0%
BH13_50-60	M4178/32	3	2.2%	5.1%	1.6%	3.5%	54.3%	24.5%	2.8%	13.3%	100.0%
BH13_90-100	M4178/33	3	3.0%	5.1%	0.4%	4.7%	46.9%	26.2%	2.4%	19.4%	100.0%
BH14_0-10	M4178/34	3	7.5%	5.8%	2.0%	3.8%	41.8%	38.2%	9.2%	5.0%	100.0%
BH14_20-30	M4178/35	3	8.7%	7.2%	5.3%	1.9%	39.1%	38.4%	8.8%	6.5%	100.0%
BH14_50-60	M4178/36	2	17.9%	3.8%	0.0%	3.8%	29.0%	24.7%	19.4%	23.0%	100.0%
BH14_90-100	M4178/37	3	11.1%	2.1%	0.5%	1.6%	31.2%	30.4%	7.3%	29.1%	100.0%
BH16_0-10	M4178/38	4	19.2%	0.2%	0.0%	0.2%	1.2%	18.4%	26.2%	53.9%	100.0%
BH16_20-30	M4178/39	4	19.9%	0.0%	0.0%	0.0%	1.9%	54.0%	36.6%	7.5%	100.0%
BH16_50-60	M4178/40	3	12.5%	0.3%	0.0%	0.3%	2.3%	57.0%	35.5%	4.9%	100.0%
BH16_90-100	M4178/41	3	10.2%	0.1%	0.0%	0.1%	0.9%	53.6%	18.5%	26.8%	100.0%
BH18_0-10	M4178/42	4	17.8%	0.9%	0.0%	0.9%	2.8%	12.2%	29.4%	54.7%	100.0%
BH18_20-30	M4178/43	4	21.1%	0.5%	0.0%	0.5%	2.2%	34.3%	14.2%	48.9%	100.0%
BH18_50-60	M4178/44	4	25.3%	0.1%	0.0%	0.1%	1.2%	5.1%	26.2%	67.5%	100.0%
BH18_90-100	M4178/45	4	22.7%	0.1%	0.0%	0.1%	1.5%	10.8%	24.9%	62.8%	100.0%
BH22_0-10	M4178/46	4	21.9%	0.9%	0.0%	0.9%	1.9%	10.6%	21.5%	65.2%	100.0%
BH22_20-30	M4178/47	4	17.8%	0.6%	0.0%	0.6%	1.4%	17.0%	18.2%	62.8%	100.0%
BH22_50-60	M4178/48	4	21.5%	0.7%	0.0%	0.7%	1.3%	14.9%	18.7%	64.4%	100.0%
BH22_90-100	M4178/49	3	18.4%	0.3%	0.0%	0.3%	1.5%	16.2%	22.0%	60.1%	100.0%
BH26_0-10	M4178/50	4	8.2%	0.8%	0.0%	0.8%	2.4%	30.7%	23.3%	42.8%	100.0%
BH26_20-30	M4178/51	3	17.4%	0.0%	0.0%	0.0%	2.1%	29.5%	17.8%	50.7%	100.0%
BH26_50-60	M4178/52	4	17.5%	0.3%	0.0%	0.3%	3.2%	29.1%	15.9%	51.5%	100.0%
BH26_90-100	M4178/53	3	14.5%	0.3%	0.0%	0.3%	3.6%	51.0%	14.5%	30.5%	100.0%
BH29_0-10	M4178/54	4	17.7%	0.0%	0.0%	0.0%	0.3%	27.6%	21.5%	50.0%	100.0%
BH29_20-30	M4178/55	4	14.5%	0.0%	0.0%	0.0%	0.3%	36.6%	24.2%	38.9%	100.0%
BH29_50-60	M4178/56	4	12.6%	0.0%	0.0%	0.0%	0.4%	38.0%	22.1%	39.4%	100.0%
BH29_90-100	M4178/57	4	10.3%	0.1%	0.0%	0.1%	0.9%	45.4%	14.6%	39.0%	100.0%
BH30_0-10	M4178/58	4	7.8%	0.9%	0.0%	0.9%	3.2%	32.0%	27.2%	36.7%	100.0%
BH30_20-30	M4178/59	4	11.1%	0.4%	0.0%	0.4%	4.3%	53.7%	20.5%	21.1%	100.0%
BH30_50-60	M4178/60	4	8.9%	0.4%	0.0%	0.4%	3.1%	51.8%	26.9%	17.8%	100.0%
BH30_70-80	M4178/61	4	7.4%	2.1%	0.0%	2.1%	2.7%	37.0%	36.4%	21.9%	100.0%
BH32_0-10	M4178/62	3	2.8%	0.1%	0.0%	0.1%	14.0%	64.6%	8.3%	12.9%	100.0%
BH32_20-30	M4178/63	3	5.0%	0.2%	0.0%	0.2%	12.4%	65.7%	8.5%	13.2%	100.0%
BH32_50-60	M4178/64	3	7.0%	0.0%	0.0%	0.0%	4.8%	50.9%	10.4%	33.9%	100.0%
BH32_90-100	M4178/65	4	6.3%	0.1%	0.0%	0.1%	5.0%	58.2%	9.9%	26.9%	100.0%
BH34_0-10	M4178/66	2	3.0%	0.3%	0.0%	0.3%	12.5%	46.6%	16.4%	24.2%	100.0%
BH34_20-30	M4178/67	3	7.4%	0.3%	0.0%	0.3%	10.5%	27.9%	18.3%	43.1%	100.0%
BH34_50-60	M4178/68	2	5.3%	4.9%	1.7%	3.2%	15.4%	31.6%	10.4%	37.7%	100.0%
BH34_90-100	M4178/69	2	9.8%	18.4%	1.4%	17.0%	45.2%	10.3%	7.9%	18.3%	100.0%
BH36_0-10	M4178/70	3	5.3%	2.1%	0.5%	1.6%	20.2%	50.1%	11.8%	15.7%	100.0%
BH36_20-30	M4178/71	2	8.1%	3.1%	1.1%	2.0%	15.6%	48.1%	9.9%	23.3%	100.0%
BH36_50-60	M4178/72	4	9.8%	0.5%	0.0%	0.5%	10.7%	34.3%	4.5%	50.0%	100.0%
BH36_90-100	M4178/73	2	8.7%	0.2%	0.0%	0.2%	8.6%	36.7%	8.2%	46.2%	100.0%
BH38_0-10	M4178/74	3	7.1%	3.7%	1.3%	2.5%	9.9%	35.0%	15.7%	35.6%	100.0%
BH38_20-30	M4178/75	3	10.8%	2.4%	0.0%	2.4%	7.4%	29.9%	17.8%	42.5%	100.0%
BH38_50-60	M4178/76	4	12.3%	0.4%	0.0%	0.4%	1.2%	22.4%	18.8%	57.2%	100.0%
BH38_90-100	M4178/77	2	13.7%	0.0%	0.0%	0.0%	2.1%	31.0%	17.9%	49.0%	100.0%
BH39_0-10	M4178/78	3	15.6%	0.0%	0.0%	0.0%	2.1%	17.3%	21.9%	58.6%	100.0%
BH39_20-30	M4178/79	4	15.6%	0.2%	0.0%	0.2%	2.5%	16.9%	20.8%	59.5%	100.0%
BH39_50-60	M4178/80	3	14.7%	0.6%	0.0%	0.6%	2.4%	18.3%	20.9%	57.8%	100.0%
BH39_90-100	M4178/81	3	13.4%	1.3%	0.0%	1.3%	1.7%	29.3%	16.4%	51.4%	100.0%

Note:

- The Hydrometer Analysis method was used to determine the percentage sand, silt and clay, modified from SOP meth004 (California Dept of Pesticide Regulation), using method of Gee & Bauder (1986), in *Methods of Soil Analysis. Part 1* Agron. Monogr. 9 (2nd Ed). Klute, A., American Soc. of Agronomy Inc., Soil Sci. Soc. America Inc., Madison WI: 383-411.
- Australian Standard 1289.3.8.1-1997 (see attached)
- Analysis conducted between sample arrival date and reporting date.
- This report is not to be reproduced except in full. Results only relate to the item tested.
- All services undertaken by EAL are covered by the EAL Laboratory Services Terms and Conditions (refer scu.edu.au/eal).
- This report was issued on 06/01/2022.

APPENDIX E

Land Suitability and Agricultural Land Classification including methods from the *Suitability framework for the Inland Fitzroy and Southern Burdekin area*

SMU	E	Es	M	M	M	Pm	Ps	R	R	Tm	W	W	W	SUITABILITY CLASS - Cropping
	Water erosion	Erosion hazard, subsoil erodibility	Soil Water availability	Soil Water availability	Soil Water availability	Narrow moisture range	Surface condition	Rockiness	Rockiness	Microrelief	Wetness	Wetness	Wetness	
1	1	1	3	3	4	4	3	1	1	1	1	1	2	4
2A	5	4	4	5	5	4	3	2	3	1	4	4	4	5
2B	5	3	5	5	5	4	2	3	4	1	4	4	4	5
3	5	5	5	5	5	4	4	3	4	1	4	4	4	5
4	5	4	5	5	5	4	2	5	5	1	5	5	5	5

Dominant Soil Type	SMU	LAND SUITABILITY CLASS - Cropping	LAND SUITABILITY CLASS - Grazing	AGRICULTURAL LAND CLASS
Crusty Brown Vertosols	1	4	2	A2
Eutrophic Brown Dermosols	2A	5	3	C2
Eutrophic Brown Dermosols	2B	5	3	C2
Magnesian Brown Kandosols	3	5	3	C2
Clastic Rudosols	4	5	5	C3

Methods from the Suitability framework for the Inland Fitzroy and Southern Burdekin area

E – Water Erosion

E - Water erosion

Limitation		Suitability subclasses for various land management options	
Value	Description	Group A	
11	Slopes of 0-0.5% with non dispersive moderate to strongly coherent soil in the surface 200mm	1	
12	Slopes of 0-0.5% with non dispersive weakly coherent soil in the surface 200mm	1	
13	Slopes of 0-0.5% with dispersive soil in the surface 200mm	3	
21	Slopes of 0.5-1% with non dispersive moderate to strongly coherent soil in the surface 200mm	1	
22	Slopes of 0.5-1% with non dispersive weakly coherent soil in the surface 200mm	2	
23	Slopes of 0.5-1% with dispersive soil in the surface 200mm	4	
31	Slopes of 1-3% with non dispersive moderate to strongly coherent soil in the surface 200mm	2	
32	Slopes of 1-3% with non dispersive weakly coherent soil in the surface 200mm	3	
33	Slopes of 1-3% with dispersive soil in the surface 200mm	5	
41	Slopes of 3-5% with non dispersive moderate to strongly coherent soil in the surface 200mm	3	
42	Slopes of 3-5% with non dispersive weakly coherent soil in the surface 200mm	4	
43	Slopes of 3-5% with dispersive soil in the surface 200mm	5	
51	Slopes of 5-8% with non dispersive moderate to strongly coherent soil in the surface 200mm	3	
52	Slopes of 5-8% with non dispersive weakly coherent soil in the surface 200mm	4	
53	Slopes of 5-8% with dispersive soil in the surface 200mm	5	
61	Slopes greater than 8% with non dispersive moderate to strongly coherent soil in the surface 200mm	5	
62	Slopes greater than 8% with non dispersive weakly coherent soil in the surface 200mm	5	
63	Slopes greater than 8% with dispersive soil in the surface 200mm	5	

Group A	
Barley-Dryland	
Chickpea-Dryland	
Cotton-Furrow Irrigated	
Maize-Dryland	
Millet-Dryland	
Mungbean-Dryland	
Oat-Dryland	
Safflower-Dryland	
Sorghum-Dryland	
Soybean-Dryland	
Sunflower-Dryland	
Triticale-Dryland	
Wheat-Dryland	

Suitability framework for the Inland Fitzroy and Southern Burdekin area

Es – Erosion Subsoil

411

Es - Erosion hazard, subsoil erodibility

Limitation		Suitability subclasses for various land management options
Value	Description	Group A
11	Slopes of 0-0.5% with no subsoil (200-1000mm) dispersion	1
12	Slopes of 0-0.5% with low to moderate dispersive subsoil (200-1000mm) and clay content greater than 20%	1
13	Slopes of 0-0.5% with strongly dispersive subsoil (200-1000mm) on 2 or more tests and clay content greater than 20%	2
21	Slopes of 0.5-1% with no subsoil (200-1000mm) dispersion	1
22	Slopes of 0.5-1% with low to moderate dispersive subsoil (200-1000mm) and clay content greater than 20%	2
23	Slopes of 0.5-1% with strongly dispersive subsoil (200-1000mm) on 2 or more tests and clay content greater than 20%	3
31	Slopes of 1-3% with no subsoil (200-1000mm) dispersion	1
32	Slopes of 1-3% with low to moderate dispersive subsoil (200-1000mm) and clay content greater than 20%	3
33	Slopes of 1-3% with strongly dispersive subsoil (200-1000mm) on 2 or more tests and clay content greater than 20%	4
41	Slopes of 3-5% with no subsoil (200-1000mm) dispersion	3
42	Slopes of 3-5% with low to moderate dispersive subsoil (200-1000mm) and clay content greater than 20%	3
43	Slopes of 3-5% with strongly dispersive subsoil (200-1000mm) on 2 or more tests and clay content greater than 20%	5
51	Slopes of 5-8% with no subsoil (200-1000mm) dispersion	3
52	Slopes of 5-8% with low to moderate dispersive subsoil (200-1000mm) and clay content greater than 20%	4
53	Slopes of 5-8% with strongly dispersive subsoil (200-1000mm) on 2 or more tests and clay content greater than 20%	5
61	Slopes greater than 8% with no subsoil (200-1000mm) dispersion	5
62	Slopes greater than 8% with low to moderate dispersive subsoil (200-1000mm) and clay content greater than 20%	5
63	Slopes greater than 8% with strongly dispersive subsoil (200-1000mm) on 2 or more tests and clay content greater than 20%	5

Group A	
Barley-Dryland	Triticale-Dryland
Chickpea-Dryland	Wheat-Dryland
Cotton-Furrow Irrigated	
Maize-Dryland	
Millet-Dryland	
Mungbean-Dryland	
Oat-Dryland	
Safflower-Dryland	
Sorghum-Dryland	
Soybean-Dryland	
Sunflower-Dryland	

Suitability framework for the Inland Fitzroy and Southern Burdekin area

M – Soil Water Availability

212

M – Soil water availability

Limitation		Suitability subclasses for various land management options		
Value	Description	Group A	Group B	Group C
1	PAWC greater than 150mm/100cms	1	2	2
2	PAWC 125-150mm/100cms	2	2	3
3	PAWC 100-125mm/100cms	3	3	4
4	PAWC 75-100mm/100cms	3	4	5
5	PAWC 50-75mm/100cms	4	5	5
6	PAWC less than 50mm/100cms	5	5	5

Group A	Group B	Group C
Cotton-Furrow Irrigated	Maize-Dryland	Barley-Dryland
	Mungbean-Dryland	Chickpea-Dryland
	Safflower-Dryland	Millet-Dryland
	Sorghum-Dryland	Oat-Dryland
	Soybean-Dryland	Triticale-Dryland
	Sunflower-Dryland	Wheat-Dryland

R – Rockiness

215

R - Rockiness

Limitation		Suitability subclasses for various land management options	
Value	Description	Group A	Group B
C2	Cobbles 60 to 200mm and abundance less than 10%	3	3
C3	Cobbles 60 to 200mm and abundance 10-20%	3	4
C4	Cobbles 60 to 200mm and abundance 20-50%	4	4
C5	Cobbles 60 to 200mm and abundance greater than 50%	4	4
G2	Gravels less than 20mm and abundance less than 10%	1	1
G3	Gravels less than 20mm and abundance 10-20%	2	2
G4	Gravels less than 20mm and abundance 20-50%	2	3
G5	Gravels less than 20mm and abundance greater than 50%	3	3
P2	Pebbles 20 to 60mm and abundance less than 10%	2	2
P3	Pebbles 20 to 60mm and abundance 10-20%	2	2
P4	Pebbles 20 to 60mm and abundance 20-50%	3	4
P5	Pebbles 20 to 60mm and abundance greater than 50%	4	4
S2	Stones greater than 200mm and abundance less than 10%	3	3
S3	Stones greater than 200mm and abundance 10-20%	3	4
S4	Stones greater than 200mm and abundance 20-50%	5	5
S5	Stones greater than 200mm and abundance greater than 50%	5	5

Group A	Group B
Barley-Dryland	Mungbean-Dryland
Chickpea-Dryland	Soybean-Dryland
Cotton-Furrow Irrigated	
Maize-Dryland	
Millet-Dryland	
Oat-Dryland	
Safflower-Dryland	
Sorghum-Dryland	
Sunflower-Dryland	
Triticale-Dryland	
Wheat-Dryland	

Pm – Narrow Moisture Range

213

Pm - Narrow moisture range

Limitation		Suitability subclasses for various land management options
Value	Description	Group A
1	Wide moisture range for cultivation – moderately well drained to rapidly drained; not hard setting when dry and not 'spewy' (i.e. boggy) when wet. Deep sands and thick sandy surfaced texture contrast soils	1
2	Moderate moisture range for cultivation – moderately well drained to rapidly drained; not hard setting when dry and not 'spewy' when wet. Moderately to strongly self-mulching clays	1
3	Moderate moisture range for cultivation – moderately well drained to rapidly drained; predominantly hard setting when dry and not 'spewy' when wet. Well drained earths and moderately well drained hard setting loamy surfaced soils	2
4	Moderate moisture range for cultivation (but less than Pm 3) – imperfectly drained to moderately well drained; not hard setting (or only weakly) when dry and 'spewy' when wet. Sandy surfaced (less than 0.4 m), sodic texture contrast soils	3
5	Narrow moisture range for cultivation – imperfectly drained to moderately well drained; hard setting, firm or weakly self-mulching when dry and not 'spewy' when wet. Hard setting, firm or weakly self-mulching, pedal clays	3
6	Narrow moisture range for cultivation – imperfectly drained to moderately well drained; hard setting when dry and 'spewy' when wet. Loamy surfaced (less than 0.4 m), sodic texture contrast soils or dermosols	3
7	Very narrow moisture range for cultivation – imperfectly drained to moderately well drained; very hard setting when dry and 'spewy' when wet. Very hard setting, sodic clays	4

Group A
Barley-Dryland
Chickpea-Dryland
Cotton-Furrow Irrigated
Maize-Dryland
Millet-Dryland
Mungbean-Dryland
Oat-Dryland
Safflower-Dryland
Sorghum-Dryland
Soybean-Dryland
Sunflower-Dryland
Triticale-Dryland
Wheat-Dryland

Ps – Surface Condition

Ps - Surface condition

Limitation		Suitability subclasses for various land management options
Value	Description	Group A
1	Soils with soft or loose sandy to sandy loam surface horizons	1
2	Very fine self-mulching clays (peds less than 2mm)	1
3	Soils with soft, firm or only weakly hard setting, sandy to loamy surface horizons	2
4	Fine self-mulching clays (peds greater than 2-5mm)	2
5	Coarse self-mulching clays (peds greater than 5–10mm); poor seed soil contact due to separation of large peds with drying	3
6	Clay soils with hard setting, firm pedal or weakly self-mulching surface horizons	3
7	Very coarse self-mulching clays (peds greater than 10mm)	4
8	Loamy, fine sand, silty or clayey surface soils that are extremely hard setting, massive or crusting	4

Group A

Barley-Dryland
Chickpea-Dryland
Cotton-Furrow Irrigated
Maize-Dryland
Millet-Dryland
Mungbean-Dryland
Oat-Dryland
Safflower-Dryland
Sorghum-Dryland
Soybean-Dryland
Sunflower-Dryland
Triticale-Dryland
Wheat-Dryland

Tm – Microrelief

216

Tm - Microrelief

Limitation		Suitability subclasses for various land management options
Value	Description	Group A
1	No microrelief across the majority (greater than 70%) of the land surface	1
2	Very weakly developed microrelief (VI less than 0.1m) that occurs across much (30–70%) of the land surface	2
3	Normal, lattice or linear gilgai (VI 0.1–0.3m) that occurs across less than 30% of the land surface	2
4	Normal, lattice or linear gilgai (VI 0.1–0.3m) that occurs across much (30–70%) of the land surface	2
5	Normal, lattice or linear gilgai (VI 0.1–0.3m) across the majority (greater than 70%) of the land surface	2
6	Shallow, melonhole gilgai (VI 0.3–0.6m) that occurs across less than 30% of the land surface	2
7	Shallow, melonhole gilgai (VI 0.3–0.6m) that occurs across much (30–70%) of the land surface	3
8	Shallow, melonhole gilgai (VI 0.3–0.6m) across the majority (greater than 70%) of the land surface	4
9	Strongly developed, deep, melonhole gilgai (VI 0.6–1.5m) that occurs across less than 30% of the land surface	4
10	Strongly developed, deep, melonhole gilgai (VI 0.6–1.5m) that occurs across much (30–70%) of the land surface	5
11	Strongly developed, deep, melonhole gilgai (VI 0.6–1.5m) across the majority (greater than 70%) of the land surface	5

Group A

Barley-Dryland
Chickpea-Dryland
Cotton-Furrow Irrigated
Maize-Dryland
Millet-Dryland
Mungbean-Dryland
Oat-Dryland
Safflower-Dryland
Sorghum-Dryland
Soybean-Dryland
Sunflower-Dryland
Triticale-Dryland
Wheat-Dryland

W – Wetness

217

W - Wetness

Limitation		Suitability subclasses for various land management options		
Value	Description	Group A	Group B	Group C
2	Very poorly to poorly drained	5	5	5
3H	Imperfectly drained and highly permeable	2	3	3
3M	Imperfectly drained and moderately permeable	3	3	3
3S	Imperfectly drained and slowly permeable	4	4	4
4H	Moderately well drained and highly permeable	1	1	2
4M	Moderately well drained and moderately permeable	1	1	2
4S	Moderately well drained and slowly permeable	2	2	2
5	Well drained	1	1	1
6	Rapidly drained	1	1	1

Group A	Group B	Group C
Barley-Dryland	Mungbean-Dryland	Cotton-Furrow Irrigated
Chickpea-Dryland	Safflower-Dryland	
Maize-Dryland	Soybean-Dryland	
Millet-Dryland	Sunflower-Dryland	
Oat-Dryland		
Sorghum-Dryland		
Triticale-Dryland		
Wheat-Dryland		

ASIA PACIFIC OFFICES

ADELAIDE

60 Halifax Street
Adelaide SA 5000
Australia
T: +61 431 516 449

BRISBANE

Level 16, 175 Eagle Street
Brisbane QLD 4000
Australia
T: +61 7 3858 4800
F: +61 7 3858 4801

CAIRNS

Level 1 Suite 1.06
Boland's Centre
14 Spence Street
Cairns QLD 4870
Australia
T: +61 7 4722 8090

CANBERRA

GPO 410
Canberra ACT 2600
Australia
T: +61 2 6287 0800
F: +61 2 9427 8200

DARWIN

Unit 5, 21 Parap Road
Parap NT 0820
Australia
T: +61 8 8998 0100
F: +61 8 9370 0101

GOLD COAST

Level 2, 194 Varsity Parade
Varsity Lakes QLD 4227
Australia
M: +61 438 763 516

MACKAY

21 River Street
Mackay QLD 4740
Australia
T: +61 7 3181 3300

MELBOURNE

Level 11, 176 Wellington
Parade
East Melbourne VIC 3002
Australia
T: +61 3 9249 9400
F: +61 3 9249 9499

NEWCASTLE CBD

Suite 2B, 125 Bull Street
Newcastle West NSW 2302
Australia
T: +61 2 4940 0442

NEWCASTLE

10 Kings Road
New Lambton NSW 2305
Australia
T: +61 2 4037 3200
F: +61 2 4037 3201

PERTH

Grd Floor, 503 Murray
Street
Perth WA 6000
Australia
T: +61 8 9422 5900
F: +61 8 9422 5901

SYDNEY

Tenancy 202 Submarine School
Sub Base Platypus
120 High Street
North Sydney NSW 2060
Australia
T: +61 2 9427 8100
F: +61 2 9427 8200

TOWNSVILLE

12 Cannan Street
South Townsville QLD 4810
Australia
T: +61 7 4722 8000
F: +61 7 4722 8001

WOLLONGONG

Level 1, The Central Building
UoW Innovation Campus
North Wollongong NSW
2500
Australia
T: +61 2 4249 1000

AUCKLAND

Level 4, 12 O'Connell Street
Auckland 1010
New Zealand
T: 0800 757 695

NELSON

6/A Cambridge Street
Richmond, Nelson 7020
New Zealand
T: +64 274 898 628

WELLINGTON

12A Waterloo Quay
Wellington 6011
New Zealand
T: +64 2181 7186

SINGAPORE

39b Craig Road
Singapore 089677
T: +65 6822 2203

APPENDIX D

Subsidence Report

SUBSIDENCE REPORT FOR THE
ENSHAM LIFE OF MINE EXTENSION – ZONES 2 AND 3

Prepared for
Ensham Resources Pty Ltd

JANUARY 2022

EXECUTIVE SUMMARY

Ensham Mine is an existing open-cut and underground bord and pillar coal mine located approximately 35 kilometres (km) east of Emerald in Queensland. The Ensham Life of Mine Extension Project - Zones 2 and 3 (the Project) proposes to increase the life of the existing underground operations by extending the underground bord and pillar mine into Zones 2 and 3 within Mining Leases (ML) 7459, ML70326, ML70365, and, ML7459 and 70366 respectively.

The Project would produce at up to approximately 4.5 million tonnes of product coal per annum and would extend the Ensham Life of Mine (LOM) by up to one year to approximately 2029. Without zones 2 and 3, the current underground operations will become physically restrained to lower production levels and would affect the overall economic viability of the mine.

The extension of the underground operation using existing infrastructure means that no material surface construction or surface disturbance (other than the installation of four flares to be located on already cleared land) will be required to facilitate the Project.

The Project will operate using the same bord and pillar and single seam mining method currently being used on site. This mining system forms a regular array of long-term stable coal pillars and roadways in each panel and does not cause large scale overburden fracturing and subsidence. Where the Nogoa River flows through Zone 2, no mining beneath the river is proposed. In addition, greater than 75% of the Project area is located outside the flood plain.

The assessment of the long-term stability of the Project coal pillars resulting from the proposed underground mine has been undertaken using the industry accepted University of New South Wales Pillar Design Procedure. The subsidence predictions from the assessment have been verified to a high level of confidence using information from the existing bord and pillar operations at Ensham Mine site. The subsidence assessment is based on the Project design minimum pillar Factor of Safety (FoS) of 1.6 for areas beneath the floodplain, and 2.11 for access roadways beneath the Nogoa River to connect bord and pillar workings, and, for bord and pillar workings beneath the Nogoa River anabranch, has confirmed the long-term stability of the proposed mine layout. The assessment also considers the width: height ratios of the pillars, as well as the estimated critical level of overburden displacement.

The design criteria used to ensure long-term stability of the pillars has also been peer reviewed by three industry recognised (RPEQ) geotechnical consultants Mine Advice (Dr Russell Frith), Byrnes Geotechnical (Dr Ross Seedsman), and BK Hebblewhite Consulting (Emeritus Professor Bruce Hebblewhite), who all concluded that the proposed bord and pillar layout is an appropriate and well developed geotechnical design.

The temporary increase in cover depth during 0.1% AEP (Q1000) flood events has also been calculated below both the flood plain and Nogoia River and anabranh channels. Conservative maximum flood depth values of 16 m in the Nogoia River channel and 4 m across the flood plain have been used in the FoS calculations. The temporary increase in depth has been applied to the design figures to calculate the required mining height to satisfy the Project FoS during 0.1% AEP flood events.

As well as the factor of safety approach, the long-term life expectancy of pillars can be estimated using empirical studies from South Africa. Using this methodology, the proposed 24 m x 28 m (centres) pillars in the Project area, at 4.5 m high and 130 m depth of cover, are calculated to be stable in excess of 26,000 years. Furthermore in regards to long-term stability, after mining is completed and the workings flood with groundwater, the buoyancy effect of the groundwater will reduce the vertical load on the pillars by up to 40%. For a pillar below the Nogoia River anabranh, designed with a FoS of 2.11, at 140 m depth of cover, reducing the vertical load on the pillar by a conservative 25%, to account for any potential strength loss in the coal and surrounding strata, increases the FoS to 2.82. This FoS has a probability of failure well in excess of 1 in 10,000,000.

Due to the nature of the bord and pillar mining method, subsidence is predicted to be less than 30 mm in majority of the Project area, with localised areas less than 35 mm. This is as a result of elastic compression of the strata i.e. compression due to the additional load on the pillars after the coal is extracted. To provide context, the Australian Government Department of the Agriculture, Water and the Environment (DAWE) states that seasonal variation in surface levels can be up to 50 mm or more as a result of changes in moisture content.

Recent RTK (Real Time Kinematic) GPS monitoring at Ensham indicates subsidence levels of less than 10 mm above mined underground panels and confirms the predictions for the Project. This monitoring has an accuracy of ± 5 mm and is able to detect the low levels of movement predicted for the Project. Further baseline reference and ongoing monitoring data will continue to be collected to ensure that any minor subsidence is occurring and recorded, and if so that mitigation measures are put in place where required, consistent with the SMP.

Based on the available data for the Project, including high density exploration boreholes, 3D seismic and underground geological mapping, there are no localised features or variations in the geology, geotechnical conditions or surface topography that are considered likely to result in any significant deviations from the subsidence predictions presented in this report.

There is therefore a high degree of confidence in the subsidence predictions due to the accurate RTK-GPS monitoring data above existing bord and pillar mining areas at Ensham with the Project design having similar mining heights, depth of cover and mining methodology. This information has allowed a robust calibration to be achieved and provided a sound basis to enable conservative subsidence predictions.

Due to the low levels of subsidence and associated strains and tilts, no surface cracking is anticipated within the Project area. The expected low levels of subsidence are also unlikely to result in the formation of significant depressions in the surface topography, where ponding of the surface drainage may occur. This is consistent with experience at the existing Ensham Mine operations, where no surface cracking or ponding has been observed above the bord and pillar mine that has been operating for more than 10 years.

Based on mining experience at shallow depths of cover in the current Ensham underground workings, as well as experience at other mining operations around the world, the risk of sinkhole subsidence occurring in the Project area, where the depth of cover for the entire area of mining is greater than 75 m, is therefore considered to be negligible.

To address the monitoring and management of any subsidence impacts, a Subsidence Management Plan (SMP) has been developed. This plan includes the triggers for investigation of any potential subsidence impacts, soil types, guidance on surface inspections, groundwater monitoring, mitigation and management measures as well as guidelines for landowner consultation if required.

TABLE OF CONTENTS

EXECUTIVE SUMMARY	ii
1 INTRODUCTION	1
1.1 Project Description	2
1.2 Project Setting	3
1.3 Project Mining Method.....	4
1.4 Objectives	9
1.5 Report Structure	9
2 ENGINEERING GEOLOGY	10
2.1 Geological Data.....	10
2.2 Stratigraphy	11
2.3 Seam Thickness.....	12
2.4 Depth of Cover	13
2.5 Depth of Weathering	14
3 PREVIOUS SUBSIDENCE MONITORING DATA	15
3.1 Ensham Mine	15
3.1.1 Fixed RTK-GPS Monitoring.....	15
3.1.2 LIDAR	20
3.1.3 Monitoring Review.....	22
3.2 Clarence Mine	23
3.3 Tasman Mine	24
4 SUBSIDENCE PREDICTION METHODOLOGY AND RESULTS	27
4.1 Stability of Underground Workings	27
4.1.1 Factor of Safety.....	27
4.1.2 Width to Height Ratio	34
4.1.3 Criteria for Pillar Design	35
4.1.4 Long Term Stability of the Overburden	38
4.1.5 Comparison to Other Mines	38
4.1.6 Pillar Spalling	40
4.1.7 Potential For Sinkhole Subsidence	43
4.2 Subsidence Behaviour	47
4.2.1 Bearing Capacity Failure of the Floor Beneath the Pillars	48
4.2.2 Flooding Workings	49
4.2.3 Strata Compression	50
4.3 Prediction of Project Subsidence Effects.....	56
4.3.1 Subsidence in the Project Mining Area	56
4.3.2 Surface Cracking.....	60
4.3.3 Sub-surface Cracking.....	61
4.3.4 Limitations of the Subsidence Predictions.....	61
5 CONCLUSIONS	62

6	APPENDIX 1. PANEL DATA – ZONE 2 AND ZONE 3.....	64
---	---	----

List of Figures

Figure 1.	Location Plan – Ensham Mine Site.....	1
Figure 2.	Access to the Underground Workings from Ramp 3.....	2
Figure 3.	Location of Workings in Zone 2 under the Nogoia River and Anabranh.	3
Figure 4.	Surface Topography	4
Figure 5.	Bord and Pillar Layout Terminology.....	5
Figure 6.	6.5 m Wide x 3.3 m High Development Roadway (Bord) at Ensham	6
Figure 7.	5.5-6.5 m Wide x 4.8 m High Roadway after Floor Coaling at Ensham.....	7
Figure 8.	Bord and Pillar Panel Nomenclature and Outline of 3D Seismic	8
Figure 9.	Location of Exploration Boreholes	10
Figure 10.	Permian Coal Seams across the Ensham Area.....	11
Figure 11.	Working Section Thickness	12
Figure 12.	Working Section Depth.....	13
Figure 13.	Depth of Weathering.....	14
Figure 14.	Fixed GPS Monitoring Station	15
Figure 15.	Location of Remote Subsidence Monitoring – Ensham Underground	16
Figure 16.	Subsidence Monitoring above 503 Panel	17
Figure 17.	Subsidence Monitoring above 500 Mains and 502 Panel.....	18
Figure 18.	Subsidence Monitoring above 114 Panel	19
Figure 19.	Extent of the Mine Workings at the time of each LIDAR Survey.....	20
Figure 20.	Section Line above 204 Panel.....	21
Figure 21.	Section Line along the 105 Panel Belt Road	22
Figure 22.	Bord and Pillar Layout – Clarence Mine	24
Figure 23.	Subsidence over 3 North Panel at Tasman	26
Figure 24.	Influence of Panel Width on Pillar Load.....	28
Figure 25.	Paint Marks to Control the Thickness of Floor Coal Mined.....	30
Figure 26.	Standard Pillars - Maximum Mining Height for a FoS of 1.6	31
Figure 27.	Comparison of Bell Out and Standard Pillars	32
Figure 28.	Calculation of the Effective Width of the Bell Out Pillars.....	33
Figure 29.	Bell Out Pillars - Maximum Mining Heights for a FoS of 1.6	33
Figure 30.	Scaled Diagram of the Rib Canches Left Around Pillars	34
Figure 31.	Post-failure Stiffness of Coal Pillars as a Function of Width to Height....	35
Figure 32.	Design Criteria for Bord and Pillar Workings	36
Figure 33.	Kinematic Failure of Wedges.....	37
Figure 34.	Impact of Geological Structure	37
Figure 35.	Summary of Pillar Design at Ensham	39
Figure 36.	Factor of Safety versus Time to Failure.....	40
Figure 37.	Factor of Safety vs Depth of Cover.....	41

Figure 38. Typical Thin Rib Spall at Ensham after Secondary Coal Recovery – F23-24, 109A Panel.....	42
Figure 39. Illustration of Suggested Sinkhole Development Mechanism (Whittaker and Reddish, 1989).	44
Figure 40. Limiting Equilibrium Analysis for Sinkhole Subsidence above 6.5 m Wide Roadways.....	46
Figure 41. Limiting Equilibrium Analysis for Sinkhole Subsidence above Intersections and Bell Outs.....	47
Figure 42. Bearing Capacity Analysis.....	48
Figure 43. Minor Cracking of the Coal Floor, 101 Panel.....	49
Figure 44. Average Strength for the Stone Roof 0 m to 17.5 m Interval	51
Figure 45. Average Strength for the Stone Floor 0 m to 17.5 m Interval	52
Figure 46. Determination of the Geological Strength Index (GSI).....	53
Figure 47. Aries-Castor Seam Roof and Floor (Zone 2) – Borehole C4858	54
Figure 48. Aries-Castor Seam Roof and Floor (Zone 3) – Borehole C5384	54
Figure 49. Castor Seam Roof and Floor (Zone 2) - Borehole C4954	55
Figure 50. Castor Seam Roof and Floor (Zone 3) - Borehole C4986	55
Figure 51. Subsidence above the Panel Pillars in the Project area	57
Figure 52. Subsidence above the Sub Panel Pillars in the Project area.....	58
Figure 53. Subsidence above the Bell Out Pillars in the Project area.....	59

List of Tables

Table 1. Calibration of Subsidence Data.	60
---	----

List of Abbreviations

AHD	- Australian Height Datum
D	- Disturbance Factor
DAWE	- Department of the Agriculture, Water and the Environment
EA	- Environmental Authority
E _i	- Laboratory Modulus
E _{rm}	- Rock Mass Modulus
FoS	- Factor of Safety
GGPL	- Gordon Geotechniques Pty Ltd
GPS	- Global Positioning System
GSI	- Geological Strength Index
LIDAR	- Light Detection and Ranging
LOM	- Life of Mine
ML	- Mining Lease
RTK	- Real Time Kinematic
UCS	- Uniaxial Compressive Strength

Glossary

Bell out	An area on the perimeter of the panels where coal is mined and ground support is not installed.
Bord	A roadway developed in an underground mine.
Empirical	Based or acting on observation and experiment, not on theory.
Floor	Strata immediately below the mined seam.
Inbye	Direction towards the coal face.
Modulus	The ratio between applied stress and resultant strain.
Outbye	Direction away from the coal face.
Overburden	Sequence of strata above the mined seam.
Pillar	Coal that is not mined within the underground workings.
Roof	Strata immediately above the mined seam.
Secondary Coal Recovery	Mining of floor coal and bell outs.
Stratigraphy	A branch of geology that studies rock layers and layering. It is primarily used in the study of sedimentary and layered volcanic rocks.
Subsidence	Sinking or settlement of the land surface, due to any of several processes. As commonly used, the term relates to the vertical downward movement of natural surfaces although small-scale horizontal components may be present. The term does not include landslides, which have large-scale horizontal displacements, or settlements of artificial fills.
Strain	Relative change in the volume, area or length of a body as a result of stress. The change is expressed in terms of the amount of displacement measured in the body divided by its original volume, area, or length, and referred to as either a volume strain, areal strain, or one-dimensional strain, respectively. The unit measure of strain is dimensionless, as its value represents the fractional change from the former size.
Tilt	The rate of change in vertical subsidence between two points divided by the horizontal distance between those two points.

Document Status				
Revision No.	Date	Purpose of Issue	Prepared By	Approved for Issue By
1	18/12/21	Draft	N. Gordon	G. Gough
2	14/01/22	Final	N. Gordon	G. Gough

1 INTRODUCTION

Gordon Geotechniques Pty Ltd (GGPL) was commissioned by Ensham Resources Pty Ltd (Ensham Resources) to assess the potential impacts of the proposed Ensham Life of Mine Extension Project – Zones 2 and 3 (the Project) on subsidence values, in support of the Environmental Authority (EA) amendment application for the Project.

Ensham Mine is an existing open-cut and underground bord and pillar coal mine located approximately 35 kilometres (km) east of Emerald in Queensland. The Ensham Life of Mine Extension Project - Zones 2 and 3 proposes to increase the life of the existing underground operations by extending the underground bord and pillar mine into Zones 2 and 3 within Mining Leases (ML) 7459, ML70326, ML70365, and, ML7459 and 70366 respectively (**Figure 1**).




Figure 1. Location Plan – Ensham Mine Site

The Project will produce at up to approximately 4.5 million tonnes per annum and would extend the Ensham Life of Mine (LOM) by up to one year, to approximately 2029. The extension of the underground operation using existing infrastructure means that no surface construction or surface disturbance will be required to facilitate the Project other than the installation of four flares to minimise greenhouse gas production.

This assessment and the associated approvals process are focussed on the proposed mining activities within the Project area only.

1.1 Project Description

Ensham is currently operating a bord and pillar mine downdip of the open cut (**Figure 1**). Underground coal production commenced at Ensham in 2011, once the Aries-Castor Seam had been accessed by two stone drifts from Ramp 3 (**Figure 1** and **Figure 2**). These drifts provide both personnel, materials and belt access from the open cut to the underground workings.



Figure 2. Access to the Underground Workings from Ramp 3

The bord and pillar mining methodology currently used at Ensham is also planned for the Project area, with access through the existing underground workings (**Figure 1**). Zones 2 and 3 are located both below and outside the flood plain of the Nogoia River (**Figure 1**). In fact, greater than 75% of Zones 2 and 3 is located outside the flood plain (**Figure 1**).

There will be no mining below the Nogoia River channel (**Figure 1 and Figure 3**). A 200 m section of the Nogoia River anabranch is located above 115 Panel in Zone 2 (**Figure 3**).




Figure 3. Location of Workings in Zone 2 under the Nogoia River and Anabranch.

1.2 Project Setting

Due to the overlying Nogoia River and flood plain, the surface topography in the majority of the Project area is relatively flat (**Figure 4**). In Zone 2, there is a localised high in the topography outside the flood plain (**Figure 4**).




Figure 4. Surface Topography

1.3 Project Mining Method

To assist in the discussion on the subsidence aspects of the proposed bord and pillar layout in the Project area, a description of the mining method is presented below.

The fundamental concept of the bord and pillar method is that the coal seam is divided into a regular block like array, by mining the coal to form bords or roadways (**Figure 5**). The headings are intersected at regular intervals by connecting cut-throughs (**Figure 5**).

The **bords** are the headings and the cut-throughs and the **pillars** are the blocks of coal bounded by the bords (Figure 5). The pillars of coal support the overlying strata as the bords are driven.

Each regular array of bords is called a **panel**. Where smaller panels are developed from the main panel, they are called **sub panels** (Figure 5).




Figure 5. Bord and Pillar Layout Terminology

In the bord and pillar method, the bords are excavated, where ground conditions allow, to a maximum horizontal distance of 14 m, without the installation of roof and rib support. The maximum cut out distance is determined by the distance from the second last roof support to the operator of the shuttle car.

Excavation is carried out using the continuous miner cutting machine, which loads the coal into a shuttle car machine. The shuttle car then transports and loads the coal onto the conveyor belt system. Once the bord is excavated to the maximum distance, the continuous miner is moved to the next mining sequence and ground support is installed using a bolting machine termed a multibolter.

The development roadways (bords) in the current underground workings are typically 6.5 m wide and 3.1-3.5 m high (**Figure 6**). In poorer ground conditions, the roadway width may be reduced to 5.5-6.0 m to improve roof stability. This reduction in width also increases the factor of safety (FoS) of the pillars. In the Project area, the roadways are also planned to be 6.5 m wide. In the thinner seam areas of the Project area, a lower final roadway and pillar height is anticipated, which would increase the FoS.




Figure 6. 6.5 m Wide x 3.3 m High Development Roadway (Bord) at Ensham

After the completion of panel development, secondary coal recovery on retreat is carried out as follows:

- Floor coal is mined in the panels and sub panels (**Figure 7**).
- Bell outs are mined at the perimeter of the panels (**Figure 5**).

During floor coal recovery, canchs (or benches) of coal, nominally 0.3-0.5 m thick, are left along the side of the roadway to protect the mining personnel from the coal rib (**Figure 7**). The maximum roadway (bord) height is determined by the FoS of the pillar (**Section 4.1**).

The same secondary coal recovery methodology is proposed for the Project area. This methodology is a non-caving mining method such that large-scale overburden fracturing and subsidence, due to overburden sag, does not occur.




Figure 7. 5.5-6.5 m Wide x 4.8 m High Roadway after Floor Coaling at Ensham

The panel pillars in the Project area are designed with centre dimensions of 24 m x 28 m, which for 6.5 m wide roadways leaves solid 17.5 m x 21.5 m pillars (**Figure 8**). In the sub-panels, the pillars will have centre dimensions of 24 m x 24 m. The coal recovery ratios for the panel and sub-panel pillars with these dimensions are 44% and 46.8% respectively.

The naming convention for each panel is shown in **Figure 8**, for ease of reference in the subsidence assessment part of this report in **Section 4**.




Figure 8. Bord and Pillar Panel Nomenclature and Outline of 3D Seismic

Mining is single seam only, with no multi-seam mining planned. The proposed extension of the underground into Zones 2 and 3 will extract the same coal seam and encounter similar overburden and floor strata as the Ensham underground and open cut operations.

As detailed in the Ensham SMP (2021¹), the underground workings are designed where practical to avoid geological structures that may be associated with poorer mining conditions. For every panel that is mined, a hazard panel plan is produced that

¹ Ensham Resources (2021). Subsidence Management Plan. Document No. EIMP.06.00.06. Revision 1 - dated 3rd August 2021.

collates the available geological information such as faults, depth and seam thickness (Ensham SMP, 2021).

It should be stated that this assessment is being carried out on a generic mine layout. This layout may still be modified and optimised based on any geological features that may be encountered in areas that have not been surveyed with 3D seismic, such as parts of Zone 2 and all of Zone 3 (**Figure 8**).

These changes would not make the results of this subsidence assessment invalid. Rather, this assessment confirms that the various layout rules used by Ensham in developing the mine layout in the Project area are fit for purpose, as they return long-term stable remnant mine workings.

In the thicker seam areas, coal roof and coal floor will be left during the development part of the mining process, prior to secondary coal recovery (**Figure 6**). In the thinner seam areas, it is anticipated that the roadways will be mined to stone roof and stone floor, with no subsequent secondary floor coal recovery.

Between each panel, large 35-40 m (solid) barriers (blocks of coal) have been left and within each panel, the sub-panels are separated by a 25 m coal barrier (**Figure 8**). These barrier pillars are significantly larger than the panel pillars and minimise the interaction of overburden loads between the panels.

1.4 Objectives

The objective of this assessment is to predict the subsidence associated with the proposed mining activities within the Project area. The predictions are to be undertaken following a transparent and robust methodology.

1.5 Report Structure

Section 1 of this report introduces the Project area, including the proposed bord and pillar mining layout and methodology and setting.

Section 2 details the stratigraphy, depth of cover and coal seam thickness of the Project area.

Section 3 details previous subsidence monitoring data for the current Ensham underground workings and comparable bord and pillar mining operations.

Section 4 describes the subsidence prediction methodology, subsidence predictions and potential subsidence effects from the Project area.

Section 5 presents the key conclusions of the subsidence assessment.

2 ENGINEERING GEOLOGY

2.1 Geological Data

The Zone 2 and Zone 3 mining areas are covered by closely spaced exploration drilling, as shown in **Figure 9**. This spacing of exploration boreholes, supplemented with 3D seismic surveying, as well as geological mapping and surveying of the underground workings, is considered to be sufficiently detailed to identify any significant changes in the roof and floor strata that would affect the subsidence predictions prepared in this report.




Figure 9. Location of Exploration Boreholes

These drill holes record the geological sequence of the overburden and coal seams, as well as the sediments immediately below the coalesced Aries-Castor and Castor Seams targeted for mining.

In the majority of the drill holes, geophysical logs are also available, which provide additional data on the rock and coal seam properties. This density of data provides a high level of confidence in the geological variables in the Project area. The geological data presented in this report is based on the April 2018 geological model.

Based on the available data for the Project area, including high density exploration boreholes, 3D seismic and underground geological mapping, there are no localised features or variations in the geology, geotechnical conditions or surface topography that are considered likely to result in any significant deviations from the subsidence predictions presented in this report.

2.2 Stratigraphy

The Project area is located in the central part of the Bowen Basin, a sedimentary basin comprising Permian to Triassic age geology. Within the Project area, the Aries and Castor Seams are part of the Permian Rangal Coal Measures. A generalised sequence of the coal seams in the Ensham area from north to south in the ML areas and also in the Project area is shown in **Figure 10**.




Figure 10. Permian Coal Seams across the Ensham Area

This figure illustrates the roof and floor seam splitting, which is characteristic of the Ensham area. The individual plies labelled A, C, P, Q and V refer to the Aries, Castor, Pollux, Orion and Virgo Seams respectively (**Figure 10**). The current underground mining area is located in the thicker central part of the ML area where the Aries and Castor Seams are coalesced (**Figure 10**).

2.3 Seam Thickness

The Aries and Castor Seams are coalesced in the majority of Zone 2 and Zone 3 (**Figure 11**). In Zone 2, the working section is 5-6 m in the southern part of the zone (**Figure 11**). Where the Aries and Castor seams are split in the northern part of Zone 2, the Castor Seam is the targeted working section with a typical thickness range of 2-3 m.




Figure 11. Working Section Thickness

In Zone 3, the working section is 3.5-4.5 m where the seams are coalesced and 3-3.5 m where the seams are split (**Figure 11**).

It should be highlighted that the thickness contours have been generated from grids that have been cropped either side of the Aries-Castor split line to ensure the accuracy of the thickness values used in the compression analysis presented later in this report (**Figure 11**).

2.4 Depth of Cover

In Zone 2, the depth of cover is typically 130-140 m (**Figure 12**). The topographic surface feature in the north-eastern part of Zone 2, locally increases the depth of cover to 200 m (**Figure 12**). In Zone 3, the depth of cover ranges from 75 m in the east, up to 160 m in the western part of the area (**Figure 12**).




Figure 12. Working Section Depth

2.5 Depth of Weathering

The depth of weathering is typically 10-20 m thick in the majority of Zones 2 and 3 (**Figure 13**). The weathering depth locally increases to 50 m in the north-eastern part of Zone 2, due to the surface topographic feature in this area (**Figure 13**).




Figure 13. Depth of Weathering

3 PREVIOUS SUBSIDENCE MONITORING DATA

To assist in the prediction of subsidence in Zones 2 and 3, a review of the surface effects above the current underground workings has been carried out using both fixed RTK-GPS and LIDAR monitoring survey data.

In addition to the Ensham survey data, there is published subsidence data available from Clarence and Tasman Mines in NSW above partial extraction bord and pillar layouts. The relevant information from these three mining operations is discussed in the following sections.

3.1 Ensham Mine

3.1.1 Fixed RTK-GPS Monitoring

Fixed RTK-GPS monitoring survey stations have recently been installed above the current Ensham underground workings to provide a much higher level of survey accuracy (± 5 mm) than the LIDAR data (± 50 mm). These stations are installed 1.5-2 m below the ground surface level (**Figure 14**). This monitoring has been set up by GNSS Monitoring and the data can be easily accessed remotely in real time.



Figure 14. Fixed GPS Monitoring Station

The six stations that have been installed are located above 114, 500 Mains, 502 and 503 Panels, as shown in **Figure 15**. It should be highlighted that the two stations above 114 Panel are adjacent to Zone 2 (**Figure 15**).

Five of the six monitoring stations started recording data in mid-April 2021. By early December 2021, development mining (primary workings) had been completed under stations 114_1, 114_2 and 502_1 and secondary workings extraction in 502 Panel had also been completed under station 502_2 (**Figure 15**).



Figure 15. Location of Remote Subsidence Monitoring – Ensham Underground

The 500 Series monitoring stations are located in heavy, cracking clay soil, whereas a combination of non-cracking clay, surface duplex and loam surface soils occur in the vicinity of 114 Panel (Ensham SMP, 2021). Soils data has also been collected for Zones 2 and 3. Subsidence monitoring points will be established in the Project area and data recorded against the soil types at those locations. A map showing soil types overlaid with the locations of subsidence monitoring transects will be established as part of the SMP.

Remote survey measurements are recorded every 24 hours and these have been compared in the following figures (**Figure 16 to Figure 18**), with either the Duckponds (500 Series) or White Hill (114 Panel) rainfall gauges, to assess the effect (if any) of ground moisture on the measurements.

3.1.1.1 500 Series Panel Survey Stations

In the 500 Series Panel area, no mining has been carried out below stations 502_3 and 503_1 (**Figure 16**). The 14 day moving average curve indicates any vertical movement is less than the survey error of ± 5 mm (**Figure 16**). Also of note, the rainfall events since April 2021 do not appear to have affected the survey measurements of vertical movement (**Figure 16**).




Figure 16. Subsidence Monitoring above 503 Panel

Development (primary workings) was carried out in the 500 Mains below station 502_1 in late May 2021. This mining appears to have been associated with approximately 5 mm of movement that occurred over a timeframe of a month (**Figure 17**). This timing is as anticipated based on the approximate 2-3 weeks required to mine the entire width of the panel below the survey station.




Figure 17. Subsidence Monitoring above 500 Mains and 502 Panel

502 Panel developed under station 502_2 in late August 2021, extracting coal to around 3.3 m high. Similar subsidence behaviour to 502_1 was noted on the 502_2 station (**Figure 17**). Secondary extraction of an additional 1 m of floor coal was

completed under this station by late September 2021, with no additional vertical movement measured (**Figure 17**). Similarly, rainfall events do not appear to be significantly affecting the vertical movement measurements.

3.1.1.2 114 Panel Survey Stations

Mining of development roadways (primary workings) at 3.3 m high was carried out below survey stations 114_1 and 114_2 in mid-August and mid-September 2021 respectively (**Figure 18**).




Figure 18. Subsidence Monitoring above 114 Panel

The survey data from station 114_2 indicates around a two week period for the maximum 8 mm of subsidence to occur after the completion of mining below the station (**Figure 18**). Less movement, within the ± 5 mm measurement accuracy, was recorded on station 114_1 after mining was completed (**Figure 18**). Some movement of up to 10-15 mm was measured during the recent rain event on station 114_1 and can be attributed to the type of material in which the station is anchored (**Figure 18**).

3.1.2 LIDAR

LIDAR surveys flown in March 2016 and February 2017 have also been used to assess potential surface effects above mined out areas at Ensham. The extent of the underground workings at the time of these surveys is shown in **Figure 19**.




Figure 19. Extent of the Mine Workings at the time of each LIDAR Survey

It is considered that these lower accuracy (± 50 mm) LIDAR surveys will still be applicable in assessing ground movements over larger areas. This data is considered to be a back up to the more accurate RTK-GPS data and can be used to determine any trends.

These surface effects may also include natural ground movements, as well as potential subsidence effects. In some environments, up to 50 mm or more of vertical movement may occur due to seasonal moisture changes (DAWE, 2014² and 2015³).

Mining was completed in the shallower 204 Panel in the southern part of the mining area and the deeper 105 Panel located in the central part of the mine workings between the 2016 and 2017 LIDAR surveys (**Figure 19**).

The section lines above both panels show that any ground movement is less than the ± 50 mm accuracy of the LIDAR surveys (**Figure 20** and **Figure 21**). These measurements validate the subsidence predictions of typically less than 35 mm in the Project area presented in **Section 4.3** of this report.




Figure 20. Section Line above 204 Panel

² DAWE (2014). Subsidence from Coal Mining Activities. Report commissioned by the IESC and prepared by Sinclair Knight Merz Pty Ltd.

³ DAWE (2015). Monitoring and Management of Subsidence Induced by Longwall Coal Mining Activity. Report commissioned by the IESC and prepared by the Jacobs Group (Australia).




Figure 21. Section Line along the 105 Panel Belt Road

3.1.3 Monitoring Review

Almost eight months of higher accuracy (± 5 mm) monitoring survey data has now been collected over the Ensham underground workings. This data indicates that underground mining has had negligible subsidence impacts on the surface within the accuracy of the survey monitoring and validates the less than 35 mm prediction detailed in Section 4 of this report (**Figure 16 to Figure 18**).

In the 500 Series area, rainfall events appear to have had no impact on the survey measurements, whereas in 114 Panel rainfall events appear to correlate with spikes in the survey data (**Figure 16 to Figure 18**).

The soil types have been mapped across the Ensham area, as documented in the Ensham Subsidence Management Plan (SMP) (2021) and these should be referenced when interpreting the measured subsidence.

It is anticipated that prior to mining in Zones 2 and 3, the collection of additional survey data, in conjunction with rainfall records and also the location of underground mining, will provide some guidance on the proportion of movement due to both mining induced subsidence and also the seasonal variation in ground levels due to changes in moisture content.

Further baseline, reference and ongoing monitoring data will be required to ensure that any minor subsidence is identified, recorded, and mitigation measures are put in place.

This survey monitoring should confirm the subsidence predictions and any significant changes in subsidence will trigger a review of the relevant impact assessments and associated mitigation and management measures as discussed further in Section 4.8 of the Ensham SMP.

This review will also provide additional calibration data for any future subsidence predictions and assessments of subsidence effects.

As detailed in Revision 1 (August 2021) of the Ensham SMP, a subsidence monitoring report will also be produced every two years and monitoring of subsidence impacts will be continued after the completion of mining either:

- For five years or
- Until the surrender of the mining lease or
- A suitably qualified and experienced person produces a report confirming a lesser monitoring period is appropriate.

3.2 Clarence Mine

Clarence Mine operates adjacent to the Blue Mountains World Heritage area in the Western Coalfield of NSW. The 2.8-3.6 m thick Katoomba Seam is mined at depths between 60 m and 320 m (Hill and White, 2017⁴). The in-panel extraction ratios at Clarence are around 50-60%, slightly higher than those in the Project area at Ensham (44-46.8%) where there is no partial extraction of coal pillars (**Figure 22**).

At Clarence, the Development Approval limits surface subsidence to 100 mm. Monitoring since 2003 has shown that subsidence can be characterised in four stages (Hill and White, 2017):

1. Development drivage results in 5-10 mm of subsidence.
2. Partial extraction adds 15-20 mm (i.e. 20-30 mm of cumulative subsidence).
3. Drivage and partial extraction of the subsequent adjacent panel adds 5-10 mm (i.e. 25-40 mm of cumulative subsidence).
4. Long term water accumulation and panel flooding results in an additional 30 mm (i.e. 55-70 mm of cumulative subsidence).

⁴ Hill, D. and White, E. (2017). Progress in Partial Extraction Layout Design for Productivity, Safety and Subsidence Management at Clarence Colliery. Proceedings of the 10th Triennial Conference on Mine Subsidence. Pp. 235-252.

There have been no exceedances of the 100 mm subsidence limit since partial extraction started in 2003 (Hill and White, 2017).




Figure 22. Bord and Pillar Layout – Clarence Mine

3.3 Tasman Mine

Tasman Mine in NSW commenced the Duncan Method of partial extraction in 2008 of the 2.2-2.5 m thick Fassifern Seam, at depths up to 250 m (McTyer and Sutherland, 2011⁵). The extraction ratios were between 67% and 82%, which are significantly higher than the 44-46.8% recovery proposed in the Project area at Ensham.

The proximity and visibility of the cliff lines of the Sugarloaf Range State Conservation Area to Newcastle, resulted in strict mine approval conditions regarding subsidence outcomes. Under the Tasman Development Consent, there was to be no impact on the high-level cliff lines as a result of subsidence (Ditton and Sutherland, 2013⁶).

Man-made features on the site included three broadcasting towers, AAPT Optical Fibre Cable (OFC) and Telstra copper cabling, four TransGrid tension towers, Ausgrid 11 kV power line, public access road and several highly significant Aboriginal archaeological sites (Ditton and Sutherland, 2013).

⁵ McTyer, K. and Sutherland, T. (2011). The Duncan Method of Partial Pillar Extraction at Tasman Mine, 11th Underground Coal Operators' Conference, University of Wollongong & the Australasian Institute of Mining and Metallurgy, 2011, 8-15.

⁶ Ditton, S. and Sutherland, T. (2013). Management of Subsidence at the Tasman and Abel Mines - Issues and Outcomes, 13th Coal Operators' Conference, University of Wollongong, The Australasian Institute of Mining and Metallurgy & Mine Managers Association of Australia, 2013, 86-98.

Level 1 to 4 subsidence control zones were developed for mine planning purposes for the existing surface features (Ditton and Sutherland, 2013):

1. Level 1 - (Green) no mining constraints (total extraction allowed);
2. Level 2 - (Yellow) subsidence less than 150 mm along shallow cover below ephemeral creeks, steep slopes and minor cliffs; Aboriginal Heritage sites; Optical fibre cable.
3. Level 3 - (Red) subsidence less than 100 mm below Sugarloaf area, TransGrid Towers (tension).
4. Level 4 - (White) Subsidence less than 3 mm and horizontal displacements less than 20 mm at the Mount Sugarloaf Communication Towers (NBN, TransGrid and Broadcast Australia).

Level 1 areas were considered suitable for total pillar extraction, with the maximum subsidence up to 1.2-1.3 m.

Level 2 and 3 areas required partial pillar extraction techniques that could also support abutment loading from Level 1 areas. Level 2 and 3 had similar subsidence constraints however, the remnant pillar FoS ranged from 1.6 to greater than 2.11 respectively and required squat pillar geometries (i.e. width/height ratio of greater than 5) for strain hardening response in yield (Ditton and Sutherland, 2013).

McTyer and Sutherland (2011) reported the subsidence one year after mining was completed above the 3 North partial extraction panel, to range from 51 mm to 101 mm, with a maximum tilt of 1.2 mm/m (**Figure 23**).

As documented by Ditton and Sutherland (2013), 2.5 years after mining had been completed, increased levels of subsidence up to 521 mm were measured (**Figure 23**). A surface crack of 30 mm width developed above the rib line and across a public access path after the subsidence exceeded 300 mm.

These increased levels of subsidence were inferred to be due to weak claystone layers (0.1-0.4 m thick) in the immediate 1.2 m of floor below the coal pillars, which softened to 0.15-1 MPa after mining. This softening of the floor resulted in punching of the pillar and lateral squeezing failures within the first 1.5 m of floor strata.

There is a history of similar subsidence events in the Newcastle coalfield due to the behaviour of very soft floor strata. In the 1980s, more than 1 m of subsidence was measured on the foreshore of Lake Macquarie above one of the mines in this area.

Based on these experiences in soft floor mining conditions, the subsidence assessment in the Project area at Ensham has considered the floor strata below both the coalesced Aries-Castor and Castor Seams to identify any potential weak units to eliminate the possibility of similar subsidence events (**Section 4.2.1**).




Figure 23. Subsidence over 3 North Panel at Tasman

4 SUBSIDENCE PREDICTION METHODOLOGY AND RESULTS

The bord and pillar mining method proposed in Zones 2 and 3 is described in **Section 1.3**. The proposed mine layout has been specifically designed to ensure that there will be no caving of the roof or collapse of the pillars.

The long-term stability of the proposed underground workings has been assessed in **Sections 4.1.1, 4.1.2 and 4.1.4** using the design FoS, pillar dimensions (width to height ratio) and stability of the overburden respectively.

Section 4.1.5 provides a comparison of the stability of the pillars in the Project area, to published studies of pillar failure events and experience from the current Ensham underground workings.

The subsidence behaviour and effects have been assessed in **Sections 4.2 and 4.3**.

4.1 Stability of Underground Workings

4.1.1 Factor of Safety

The assessment of the long-term stability of the coal pillars in the Project area has been carried out using the industry accepted University of New South Wales Pillar Design Procedure to determine the design FoS as follows (Galvin et al, 1998⁷):

$$\text{FoS} = \text{Strength of Pillar} / \text{Load on Pillar}$$

The strength of the pillars in the Project area was calculated using the UNSW Pillar Design Power Strength Formulae. The following FoS are planned for Zone 2 and Zone 3 in the Project area:

- a) 2.11 for bord and pillar workings beneath the Nogoia River anabranch;
- b) 2.11 for access roadways beneath the Nogoia River to connect the bord and pillar and longwall mining areas; and
- c) 1.6 for all other bord and pillar workings beneath the floodplain of the Nogoia River.

4.1.1.1 Pillar Load

The load carried by the pillars was calculated using tributary area loading. The majority of the panels in the Project area have panel width to depth of cover ratios greater than 1, whereby the pillars experience the full tributary area load of the overlying strata.

⁷ Galvin, J., Hebblewhite, B., Salamon, M. and Lin, B. (1998). Establishing the Strength of Rectangular and Irregular Pillars. Final Report, ACARP Project C5024.

A recent publication by Reed et al (2016)⁸ has suggested that coal pillars may exceed their peak strength before the overburden moves enough to generate full tributary area loading conditions, as discussed further in **Section 4.1.4**.

Galvin, (2016)⁹ also proposed that the pillars on the perimeter of the panels do not carry the full tributary area load (**Figure 24**). However, for the purposes of this assessment, a conservative full tributary area load assumption is considered appropriate for the pillars in the main panels and sub-panels in the Project area. The bell-out pillars on the perimeter of the panels are anticipated to carry 70% of the overburden load as shown in **Figure 24**.




Figure 24. Influence of Panel Width on Pillar Load

⁸ Reed, G., McTyer, K. and Frith, R. (2016). An Assessment of Coal Pillar System Stability Criteria Based on a Mechanistic Evaluation of the Interaction Between Coal Pillars and the Overburden. Proceedings 35th International Conference on Ground Control in Mining, Morgantown, West Virginia.

⁹ Galvin, J.M. (2016). Ground Engineering – Principles and Practices for Underground Coal Mining.

The temporary increase in load on the underground workings during a flood event also needs to be considered (Hebblewhite, 2021¹⁰). As shown in **Figure 1**, the southern part of Zone 2 and the north-eastern corner of Zone 3 are located under the flood plain. There are no workings under the Nogoia River, however a 200 m section of the Nogoia River anabranch is located over 115 Panel (**Figure 3**).

During flood events, as well as the increase in water depth, the temporary increase in density due to saturation of the river alluvium should also be considered. For this discussion, a worst case 0.1% AEP (Q1000) flood event has been assessed.

Over the flood plain, the predicted maximum flood depth is 2-4 m (Hydro Engineering and Consulting, 2020¹¹). At a conservative 4 m flood depth over the flood plain, the increase in the effective depth of cover is 1.8 m, assuming a density for the water of 1.1 t/m³, to conservatively allow for some sediment load. In the Nogoia River anabranch, a conservative 16 m flood depth as indicated by Hebblewhite (2021), equates to an effective depth of cover of 7.2 m.

Similarly, the soil cover on the flood plain is typically less than 2 m thick and when saturated is assessed to have an upper bound density of 2.8 t/m³. This would account for an additional 0.29 m depth of cover, assuming an average overburden density of 2.45 t/m³.

4.1.1.2 Panel Pillars

The long-term stability of the pillars in the Project area has been assessed on a panel by panel basis, using a conservative maximum depth of cover (**Figure 12**). The mining height has also been adjusted for each panel to take into account the variability in the thickness of the coalesced Aries-Castor Seam and split Castor Seam across the Project area (**Figure 11**). The depth and thickness values for each panel are tabulated in **Appendix 1** of this report for Zones 2 and 3 within the Project area.

Where the Aries-Castor Seam is coalesced within the Project area, the depth of cover is between 75 m and 200 m and the seam thickness is typically 4.0-5.5 m (**Figure 11 and Figure 12**). Based on mining experience in the current underground workings, typically 0.8 m of roof coal is left in the thicker seam areas. In thinner seam areas, the roof coal thickness is reduced to around 0.4-0.5 m.

In those areas within Zones 2 and 3 where only the Castor Seam is to be mined, the seam thickness is less than 3 m and it is anticipated that the full seam section will be mined on development, with no secondary coal recovery (**Figure 12**).

¹⁰ Hebblewhite, B.K. (2021). Peer Review of the March 2020 GGPL Subsidence Report for the Ensham Life of Mine Extension Project. Report No. 2105/01.1

¹¹ Hydro Engineering and Consulting. (2020). Ensham Life of Mine Extension Project Appendix E3: Hydrology and Flooding Assessment.

The maximum allowable mining heights to satisfy a FoS of 1.6 for both the 24 m x 28 m (centres) pillars in the main part of the panels, as well as the 24 m x 24 m (centres) sub panel pillars, are summarised in **Figure 26** for a range of depths. Where the Nogoia River flows through Zone 2, no mining under the river is proposed (**Figure 1**). For the 200 m section of 115 Panel that is located under the Anabranche (**Figure 3**), the mining height will need to be reduced to satisfy the required 2.11 FoS.

It is highlighted that these calculations have used an overburden density of 2.45 tonnes/m³ based on the geophysical density logs from a large data set of exploration boreholes across the Ensham underground mining area (**Figure 9**). The pillar load calculations in **Figure 26** have also used a more accurate 9.806 ms⁻² value for acceleration due to gravity rather than the rounded up value of 10 ms⁻² that appears to have been used by Hebblewhite (2021). This addresses the recommendation to recalculate and apply minor adjustments to **Figure 26**.

Hebblewhite (2021) raised the issue of the requirement for a simple but reliable and effective means of managing mining heights and bell-out geometries. In the current underground workings, the thickness of floor coal is controlled during the mining process by spray painting the rib side to ensure the mined thickness does not exceed the amount specified on the sequence plan and Permit to Mine document (**Figure 25**).



Figure 25. Paint Marks to Control the Thickness of Floor Coal Mined.

Furthermore, as detailed in the Ensham SMP (2021), underground surveying of the completed mined roadways, bell outs and pillars is carried out. The FoS and width: height ratio of the as-mined pillars can be calculated and checked against the design values. These checks are carried out by the Geotechnical Engineer and reported in the monthly geotechnical inspection report. Experience to date has shown that there have been no exceedances of the planned mining heights in the secondary extraction panels at Ensham.

The temporary maximum effective depth of cover increase of 2.09 m over the flood plain, as detailed in Section 4.1.1.1, is not considered significant. For example, at 130 m depth of cover and 4.5 m extraction height, the FoS temporarily reduces during a

0.1% AEP (Q1000) flood event from 1.91 to 1.88 and as such no additional mitigation would be required.

Under the Nogoia River anabranch, a 16 m flood depth at 140 m depth of cover and 3.5 m extraction height, temporarily reduces the FoS from 2.21 to 2.11. In this area, the pillar size could either be increased to allow an increase in mining height or the 3.5 m mining height could be maintained for the proposed 24 m x 28 m pillar size.

As raised by Hebblewhite (2021), the temporary minor increase in depth during flood events should also be applied when referencing the pillar design chart for standard and bell out pillars (**Figure 26 and Figure 29**).




Figure 26. Standard Pillars - Maximum Mining Height for a FoS of 1.6

4.1.1.3 Bell Out Pillars

The FoS of the bell out pillars also needs to be considered. As shown in **Figure 24**, a 70% load assumption is appropriate for these pillars located on the perimeter of the panels.

It is highlighted that the secondary coal recovery methodology forms a regular pillar between the bell outs, which allows the application of standard pillar design formulae (**Figure 5 and Figure 27**). The analysis of these pillars has conservatively assumed a 10 m wide roadway equivalent to the mined bell out (**Figure 27**).

Based on the standard bell out mining sequence, the effective width of the bell out pillar with a solid length dimension between bell out stubs of 17.5 m, is 15 m (**Figure 28**). This has been calculated using the hydraulic radius approach of Wagner (1980)¹², where the effective width (w_e) is given by:

$$w_e = 4A/P$$

where: A is the pillar solid area and
 P is the pillar perimeter distance.




Figure 27. Comparison of Bell Out and Standard Pillars

For the bell out pillars, with an effective width of 15 m (solid) and a 70% loading assumption, the maximum allowable mining heights to satisfy the 1.6 FoS requirement are shown in **Figure 29**.

¹² Wagner, H. (1980). Pillar Design in Coal Mines. Journal of the SAIMM, pp. 37-45.




Figure 28. Calculation of the Effective Width of the Bell Out Pillars




Figure 29. Bell Out Pillars - Maximum Mining Heights for a FoS of 1.6

It should be highlighted that the rib canchs left after floor coaling have conservatively not been included in the FoS calculations (**Figure 30**).




Figure 30. Scaled Diagram of the Rib Canches Left Around Pillars

4.1.1.4 Barrier Pillars

The barrier pillars between panels have a high FoS. For a conservative 5 m mining height, 10 m wide bell outs and a minimum 50 m barrier length, the FoS of the 35 m wide barriers at a typical 130 m depth of cover in Zones 2 and 3 is 3.30. This increases to 3.82 for the 40 m wide barrier pillars.

Similarly, the 25 m solid barriers between the sub-panels have minimum FoS values of 2.40 at 130 m depth of cover. This exceeds the minimum 2.11 FoS recommended by Hebblewhite (2021) for barriers in the Ensham area.

4.1.2 Width to Height Ratio

As well as the FoS, the width to height ratio of the pillars also has to be considered in the long-term stability of the pillars. This ratio has a significant controlling influence on the post-failure behaviour of the pillar, ranging from a complete structural collapse (termed strain softening), to a more controlled squeeze with the pillar becoming stronger as it is compressed further (termed strain hardening).

Reed et al (2016) suggest that the use of laboratory-based testing data may be flawed due to the very smooth top and bottom contacts in the test rig. This is particularly important as the transition to squat pillars is about the development of frictional based confinement within the core of the pillar. As such, published laboratory data shows substantial strain softening at width: height ratios as high as 9 (Das, 1986¹³).

¹³ Das, M.N. (1986). Influence of Width/Height Ratio on Post Failure Behaviour of Coal. Int. J. Mining. Geological Engineering. No.4.

Reed et al (2016) refer to the available in situ testing data for coal pillars that indicates that the post-failure modulus should transition from negative (strain-softening) to positive (work-hardening) at a width/height ratio of around 4 (**Figure 31**).

Galvin (2016) also indicated that if the width to height ratio is greater than 4, any pillar failure will be controlled and may be arrested through the application of confinement to the pillar sides.




Figure 31. Post-failure Stiffness of Coal Pillars as a Function of Width to Height

4.1.3 Criteria for Pillar Design

Hill (2005¹⁴) presented an empirical database of Australian and South African failed pillars, in terms of both width to height ratio and FoS (**Figure 32**). This database is also consistent with the analysis of Reed et al (2016), with the majority of pillar failures occurring with width: height ratios less than 4 (**Figure 32**).

¹⁴ Hill, D (2005). Coal Pillar Design Criteria for Surface Protection. COAL2005 – Moving Technology – Maintaining Competence. 6th Australasian Coal Operators Conference. Brisbane, pp31-37.

For the development pillars in the current underground workings at Ensham, the width to height ratios are typically 5 or greater. Using the limiting FoS of 1.6, it is not until the width to height ratio is less than 3.5 that the design criteria in **Figure 32** become relevant.

It should be highlighted that there has been technical debate over the validity of the pillar in the database with a width to height ratio of 8.16 (**Figure 32**). The implications of including this data point are that the UNSW pillar strength formulae may conservatively underestimate the pillar strength and overestimate the probability of failure.




Figure 32. Design Criteria for Bord and Pillar Workings

There is value to step away from the empirical design criteria presented by Hill and consider what may be driving the upper bound for the width to height ratio. Considering the kinematic stability of a pillar that is cut diagonally from the roof on one side to the floor on the other is shown in **Figure 33**.

The top wedge may be pushed sideways depending on the shear strength developed along the roof line and on the diagonal surface. If frictional restraint only is assumed then using a conservative friction angle of 20° for unstructured coal indicates a width to height ratio of 2.75 is required to prevent shear of the coal pillar. This is consistent

with the empirical database in **Figure 32**, where the majority of failed cases have width to height ratios of less than 2.75.




Figure 33. Kinematic Failure of Wedges

For structured coal, a lower friction angle of 15° would be more representative, requiring a greater width to height ratio of 3.7 to prevent failure. This aspect is illustrated by Hill (2005) in **Figure 34**, where geological structure may weaken the pillar, hence reducing the FoS.




Figure 34. Impact of Geological Structure

Hebblewhite (2021) also requested further clarity with respect to known geological structures across the Project area and how these have been taken into account of within the design. Due to the poorer ground conditions associated with geological structures, these are avoided where practical and are not considered to have an impact on both pillar stability and overburden integrity, with respect to both subsidence and hydrogeological impacts. In the majority of the workings, development and secondary extraction is carried out in geologically unstructured areas.

4.1.4 Long Term Stability of the Overburden

Mine Advice (2018¹⁵) demonstrated for the Hume Project in NSW, that for the overburden to become critically unstable and so drive the coal pillars to a collapsed state or high levels of yield, a critical level of overburden settlement is first needed to be exceeded.

If the critical level of settlement is not exceeded, then the stability of the workings is strongly controlled by the stability of the overburden. If however the critical level is exceeded, then the stability of the workings is almost entirely reliant upon the coal pillars.

The idea of evaluating global mine stability via displacement criteria in addition to pillar loading criteria, was raised by Emeritus Professor Ted Brown during the experts review meeting of the Hume Project (Mine Advice, 2018).

With reference to the Hume Project, the predicted surface settlements were in the order of 20 mm. Published data indicates that surface settlements of at least 150 mm are required before the overburden starts to lose its stability.

Based on this discussion, Mine Advice (2018) defined the term system stability according to an overburden displacement FoS, to complement that of the pillar system. In the case of the Hume Project, the system stability FoS was found to be in the order of 7 (150/20).

This displacement based FoS for the overburden provides a measure to the level of conservatism involved in making the full tributary area assumption detailed in Section 4.1.1. This discussion adds further stability arguments to pillar FoS and width: height criteria for long term stability in the Project area.

4.1.5 Comparison to Other Mines

As shown in **Figure 35**, the pillar dimensions in the underground workings at Ensham after secondary coal recovery, plot to the right of the red design curve of Hill (2005) and the width: height ratio is typically between 3 and 4 (**Figure 35**).

¹⁵ Mine Advice Pty Ltd (2018). Interpretation of the Numerical Modelling Study of the Proposed Hume Project EIS Mine Layout. Report No. HUME22/1.

The lower width to height ratio pillars shown on **Figure 35**, were mined in the shallowest part of the Ensham underground workings with centre dimensions of 20 m x 20 m. These are smaller than the pillars planned in the Project area. With reference to **Figure 35**, the majority of the failed pillars have width to height ratios less than 3.

In the Project area, the FoS and width to height ratios of the pillars after secondary coal recovery, are also well above any of the failed cases from South Africa and Australia presented by Hill (**Figure 35**).

Furthermore, with reference to **Figure 35**, there are no cases of failed pillars with the design factors of safety and width to height ratios exhibited by the mine layout in the Project area.




Figure 35. Summary of Pillar Design at Ensham

It is also highlighted that none of the failed cases with FoS greater than 1.6 have occurred more than five years after mining based on the data of Hill (2005) shown in **Figure 36**. It is now more than eight years since the completion of secondary coal recovery in SE2, the first extraction panel at Ensham.

These FoS and W:H design criteria have also been peer reviewed by three industry recognised (RPEQ) geotechnical consultants namely Mine Advice¹⁶, Byrnes Geotechnical¹⁷ and Professor Bruce Hebblewhite, who all concluded that the proposed bord and pillar layout is an appropriate and well developed geotechnical design.




Figure 36. Factor of Safety versus Time to Failure

4.1.6 Pillar Spalling

It is noted that Canbulat (2010¹⁸) has published data from South African collapsed cases using the original Salamon and Munro pillar strength formula. The data has a number of pillars with FoS greater than 1.6 that have failed due to time dependent spalling or scaling of the pillars.

Frith and Reed (2019¹⁹) have provided an explanation for this apparent conundrum of these high FoS collapsed cases. Additional failed cases from South Africa with high FoS are also included in **Figure 37**. It is noted that the majority of failed cases occur at depths less than 100 m. The majority of the proposed workings in the Project area are at depths greater than 100 m.

¹⁶ Mine Advice Pty Ltd (2020). Peer Review Outcomes – GGPL Subsidence Report.

¹⁷ Byrnes Geotechnical (2020). Peer Review of Ensham Life of Mine Extension Project Subsidence Report. Report No. Ensh-01.

¹⁸ Canbulat I. (2010). Life of Coal Pillars and Design Considerations. In: Proceedings of the 2nd Australasian Ground Control in Mining Conference. Victoria (Australia): AusIMM; 2010. p. 57–66.

¹⁹ Frith, R. and Reed, G. (2019). Limitations and Potential Design Risks When Applying Empirically Derived Coal Pillar Strength Equations to Real-Life Mine Stability Problems. International Journal of Mining Science and Technology 29 (2019) 17–25.

These additional cases were published by Salamon et al (1998²⁰) who put forward the idea of swelling clays driving pillar scaling as a possible explanation to explain the collapsed cases. The authors however did clarify that “no direct evidence appears to exist to substantiate the proposed model of pillar scaling”. The same model was used by Canbulat (2010) in his analysis of the time to failure of high FoS pillars.




Figure 37. Factor of Safety vs Depth of Cover

Frith and Reed (2019) suggest that the high FoS values in **Figure 37** may be erroneous due to the pillar strength equation used, substantially overestimating the actual coal pillar strength. They concluded that the scaling is due to under designed pillars rather than the presence of swelling clays.

In comparison, the author of this subsidence assessment report for the Project area inspected the abandoned workings of 106 Panel in July 2019, where secondary coal recovery had been completed. It was noted that the ground conditions had not deteriorated significantly since the panel was mined in 2017 (GGPL, 2019²¹). Where

²⁰ Salamon, M.D.G, Ozba, M.U and Madden, B. J. (1998). Life and Design of Bord and Pillar Workings Affected by Pillar Spalling. J. S. Afr. Min. Metall. 1998;98(3):135–45.

²¹ GGPL (2019). Inspection of the Underground Workings on 22-23rd July 2019. Report No. Ensham19-R8.

rib spall occurs at Ensham, it is typified by thin 100-200 mm slabs and large-scale pillar spalling as documented by Canbulat (2010) is not present (**Figure 38**).

It should also be highlighted that there are no swelling clay bands, such as those referenced by Canbulat (2010), present within the Aries and Castor Seams in the Ensham underground mining area neither existing, nor proposed.



Figure 38. Typical Thin Rib Spall at Ensham after Secondary Coal Recovery – F23-24, 109A Panel

Van der Merwe (2016²²) also presented a formula to calculate the long-term life expectancy of pillars, as follows:

$$T = [d_c / (m \cdot h^x)]^{1/(1-x)}$$

Where: T = Time to failure (years)
 h = Mining height (m)
 m = 0.1799
 x = 0.7549

and d_c is the critical scaling distance, which for an ultimate safety factor of 0.5 is given by:

²² Van der Merwe, J.N. (2016). Review of Coal Pillar Lifespan Prediction for the Witbank and Highveld Coal Seams. The Journal of the Southern African Institute of Mining and Metallurgy. Pp. 1083-1090, Volume 116.

$$d_c = w - [0.002285 \cdot H \cdot h \cdot C^2]^{\wedge 0.3571}$$

Where: H = Depth of cover (m)
C = Pillar centre distance (m)
w = Pillar width (m)
h = Mining height (m)

Using this approach, the proposed 24 m x 28 m (centres) pillars in Zones 2 and 3 at 4.5 m high and 130 m depth of cover, are stable in excess of 26,000 years. It should be highlighted that the database used by Van der Merwe (2016) was sourced from South African mines with a maximum solid pillar width of 10.5 m and maximum depth of cover of 102 m and hence some extrapolation of the technique is required.

It is also noted that the Van der Merwe data shows that absolute scaling is independent of the age of the pillar, leading to the conclusion that the scaling rate must reduce with time. It is therefore assessed that pillar scaling or spalling will not lead to pillar collapse with the pillar sizes proposed for Zones 2 and 3.

4.1.7 Potential For Sinkhole Subsidence

In addition to overall pillar stability, the risk of roadway (intersection) collapse such that sinkholes develop at the surface should be considered in the Ensham underground area. Significantly, it is reported in the technical literature that sinkholes are restricted to shallow mining areas and generally only reach the surface at depths **less than 50 m**^{23,24,25}.

As shown in **Figure 12**, the depth of cover in Zones 2 and 3 area is **greater than 75 m**. This shallower area in the southern part of Zone 3 is also located outside the flood plain (**Figure 1**).

Furthermore, underground mining has already been carried out in the currently approved Ensham bord and pillar workings at depths of 40 m, with no evidence of sinkhole subsidence occurring above the excavated roadways.

These observations are confirmed by the following discussion on the mechanism of sinkhole subsidence and supplemented with design calculations for a potential failure

²³ Mahar, J.W. and Marino, G.G., (1982). Building response and mitigation measures for building damage in Illinois. Proceedings of Workshop on Surface Subsidence due to Underground Mining, Morgantown, West Virginia University, pp. 238-252.

²⁴ Whittaker, B.N. and Reddish, D.J., (1989). Subsidence: Occurrence, prediction and control, Elsevier, Amsterdam, 528p.

²⁵ Nielen Van Der Merwe, J and Madden, B.V.J. (2002) Rock Engineering for Underground Coal Mining. South African Institute of Mining and Metallurgy. Special Publications Series 7.

to occur. These design calculations were also peer reviewed by geotechnical consultants Mine Advice in 2016²⁶.

4.1.7.1 Mechanism of Sinkhole Development

Whittaker and Reddish (1989) devote an entire chapter to sinkhole subsidence above bord and pillar mines. They present various analyses examining the development and propagation of sinkholes and also review the published literature, supplemented with some case examples.

Whittaker and Reddish concluded that the local geology and the natural strength of the immediate roof are important factors in assessing the potential for sinkhole development. The mining dimensions and geometry of workings are also of equal importance and should be considered in making an assessment of subsidence risks above bord and pillar mines.

Mine Advice (2016) provided further analysis of this aspect and one of the key issues in regards to sinkhole development through fresh rock material is the extent by which the upwards progression of a roof cavity is truncated by either lithology or natural arching (**Figure 39**). **Figure 39** shows that sinkholes develop with vertical sides rather than any form of natural arching, which will cause the effective span to decrease higher into the cavity.




Figure 39. Illustration of Suggested Sinkhole Development Mechanism (Whittaker and Reddish, 1989).

²⁶ Mine Advice Pty Ltd (2016). Peer Review of Gordon Geotechniques (GGPL) Report to Ensham Coal – Geotechnical Review of the Ensham Mine Plan in Areas 1 and 2 (Dated March 2015).

As discussed by Mine Advice, this failure mechanism is commonly observed in underground coal mines and along with roof lithology acts to restrict the height of roadway roof fall cavities to typically only a few metres rather than propagating higher as shown in **Figure 39**. This is consistent with observations in the current Ensham underground workings.

4.1.7.2 Analysis of Sinkhole Subsidence

The risk of sinkhole subsidence of shallow workings to the surface has been assessed using a limiting equilibrium analysis as detailed below. The analysis is presented in Brady and Brown (2006²⁷) as follows:

For **dry** conditions:

$$F_1 = \frac{2c'(a + b \cos\alpha)}{uabc\cos\alpha} + \frac{k \tan\phi'}{(2h - b\sin\alpha)} * \frac{\{h^2 + (h - b\sin\alpha)^2\}}{b\cos\alpha} + \frac{2[h(h - b\sin\alpha) + \frac{b^2\sin^2\alpha}{3}]}{a}$$

For **saturated** conditions:

$$F = F_1 - \frac{2u_w \tan\phi'}{3u(2h - b\sin\alpha)} * \frac{\{h^2 + (h - b\sin\alpha)^2 - 2d(2h - b\sin\alpha - d)\}}{b\cos\alpha} + \frac{2[3h(h - b\sin\alpha) + b^2\sin^2\alpha - 3d(2h - b\sin\alpha - d)]}{3a}$$

where:

- F, F_1 = factor of safety
- c' = cohesion in kPa
- ϕ' = friction angle in degrees
- a = intersection width 1 (metres)
- b = intersection width 2 (metres)
- k = average of the horizontal to vertical stresses
- α = seam dip in degrees
- u = rock density in kN/m^3
- u_w = water density in kN/m^3
- d = water table depth (metres)
- h = thickness of fresh rock (metres)

For the Ensham mining area, cohesion (c') and friction angle (ϕ') values of 0 kPa and 30° have been used respectively, assuming the failure mode is along joints, with some surface roughness. The roadway width is 6.5 m and the seam dip 3° .

²⁷ Brady, B.H.G. and Brown, E.T. (2006) Rock Mechanics in Underground Mining. 3rd Edition.

The stress ratio value (k) has been reduced to 1.2 for the shallow depth of cover in the Project area. This value is also consistent with the in-situ stress measurements presented in Brady and Brown (2006).

The analysis has been carried out for both dry and saturated conditions. To maintain a Factor of Safety of greater than 2 in saturated conditions, **at least 12 m** of fresh rock is required for 6.5 m wide roadways (**Figure 40**).

Ensham technical personnel applied a conservative minimum 20 m of fresh rock for the extraction of bord and pillar panels in the southern part of the mining area. In this area, the total depth of cover including weathered rock, was 40 m.




Figure 40. Limiting Equilibrium Analysis for Sinkhole Subsidence above 6.5 m Wide Roadways.

Larger intersections and bell out excavations also need to be considered. For a large intersection, with an average diagonal span of 14 m, the side dimensions would be 9.9 m. In this case, the required thickness of fresh rock would approach 20 m in saturated conditions, applying a Factor of Safety of 2 (**Figure 41**). For a 15 m wide bell out, this approaches 30 m of fresh rock (**Figure 41**).

These calculations endorse the conservative design criteria of a minimum 40 m depth of cover and a Factor of Safety of 2 applied to the shallow Ensham underground workings.

Based on mining experience at shallow depths of cover in the current Ensham underground workings, as well as experience at other mining operations around the world, the risk of sinkhole subsidence occurring in the Zone 2 and Zone 3 underground area, where the depth of cover is greater than 75 m, is considered to be negligible.




Figure 41. Limiting Equilibrium Analysis for Sinkhole Subsidence above Intersections and Bell Outs.

4.2 Subsidence Behaviour

Unlike longwall mining, where the subsidence comprises two main components namely sag subsidence and strata compression, in the Project area, the subsidence will be due to strata compression alone. This results in low levels of surface lowering and minimal associated surface effects due to the associated low tilts, curvatures and strains.

Before a compression analysis of the roof, floor and coal in the Project area can be carried out, the potential for bearing capacity failure of weak floor strata below the coal pillars needs to be assessed. A commentary is also included on the effect of flooding the workings after mining is completed.

4.2.1 Bearing Capacity Failure of the Floor Beneath the Pillars

Several years ago, in the Newcastle coalfield in NSW, the stone floor beneath the pillars failed in a panel designed with FoS greater than 2.11. In this area, very soft layers (less than 1 MPa) were present in the immediate stone floor below the seam. The overburden consisted of thick conglomerate, which was able to span over more than 50 m.

The potential for bearing capacity failure of the floor beneath the pillars in the Project area has therefore been analysed using the following formula:

$$\text{Bearing Capacity of the Floor (MPa)} = \text{UCS}/2 \cdot (4.14159 + 0.5 \cdot W/T)$$

Where: W = Pillar Width (m)
 T = Thickness of Weak Floor (m)
 UCS = Floor Strength (Mpa)

The factor of safety for floor failure is equal to the bearing capacity of the floor divided by the stress on the pillar.

For the proposed pillar sizes in the deeper part of the Project area, a bearing capacity failure beneath these pillars after secondary coal recovery could only occur if there were layers of floor rock with a low strength of 1.8 MPa and a thickness of 2 m (**Figure 42**). For a 10 m floor layer, the strength required for failure marginally increases to 2.9 MPa.




Figure 42. Bearing Capacity Analysis

Review of the geophysical sonic velocity logs in the Project area identified that the weakest floor strata layers are less than 0.5 m thick and have a floor strength of 10 MPa. This demonstrates that a bearing capacity failure of the floor beneath the pillars is unlikely with a high FoS.

This analysis is consistent with the lack of any noticeable heave in the Ensham underground workings. Very minor floor cracking (less than 100 mm) has only been observed in localised areas after secondary coal recovery (**Figure 43**). This cracking is typically restricted to the higher quality, friable C22 ply that may have been left in the floor after secondary coal recovery has been completed. Heave and cracking of the stone floor has not been observed.



Figure 43. Minor Cracking of the Coal Floor, 101 Panel

4.2.2 Flooding Workings

In the longer term, the flooding of old panels in the Project area needs to be considered. Galvin (2008²⁸) discusses this aspect in more detail and suggested that flooding of mine workings could influence the pillar load in two ways.

1. The water pressure acting on the roof of the workings would function as a hydraulic jack to unload the pillars or
2. The overburden may be fully saturated over the full water head, effectively reducing the density, resulting in lower loads on the pillars.

Both these mechanisms have a positive impact on the long-term stability of old workings.

The other aspect that needs to be considered is the effect of water on the strength of the pillar system. Galvin (2008) details that water can reduce friction on fracture planes

²⁸ Galvin, J. (2008). Geotechnical Engineering in Underground Coal Mining – Basic Principles of Pillar Behaviour and Design. ACARP Report.

and roof/floor interfaces. The water can also accelerate the degradation of clay rich minerals in the roof, floor and coal seam.

The buoyancy effect of water will reduce the vertical load on the pillars by up to 40% and hence increase the factor of safety. This effect is calculated using the formula:

$$\text{Effective Stress on Pillar} = \text{Total stress on Pillar} - \text{Pore Pressure due to Flooding}$$

The effective stress on the pillar is therefore 1.5 (2.5-1) or 60% (1.5/2.5) of the total stress. The extent of the increase in stability will depend on any strength loss in the coal and the surrounding strata, which may be up to 10-15%.

It should be highlighted that the coal seam and immediate roof and floor strata in the Project area do not contain puggy or water sensitive material that could degrade over time. Furthermore, failure of the floor due to transient strength reduction effects is unlikely as the groundwater recovers.

A conservative 25% reduction in load would significantly increase the FoS of 24 m x 28 m (centre) pillars at 5 m high and 130 m depth of cover, from 1.76 to 2.31.

There is a case of a pillar collapse in a flooded bord and pillar iron ore mine in France. Conversely, many of the mines in the Newcastle Coalfield of NSW have been flooded for years without adverse effect on stability.

Galvin cautions that careful consideration needs to be given to the possible adverse effects on stability by dewatering the workings, as there is a history of pillar collapses soon after being dewatered.

4.2.3 Strata Compression

The induced surface deformation due to strata compression has been estimated analytically by calculating the combined pillar, roof and floor compression using modulus values. This is discussed in the following sections.

4.2.3.1 Coal Strength Modulus

An in-situ modulus value of 2500 MPa has been used for the Aries-Castor and Castor Seams in the Project area, based on geotechnical testing of coal core samples recovered during exploration drilling at Ensham.

4.2.3.2 Strength of the Stone Roof and Stone Floor

For a 17.5 m wide pillar, the influence into the roof and floor is one pillar width. As such, the average strength of both the stone roof and stone floor above and below the

coal seam for this distance in the Project area has been determined from the geological model.

The average strength of these intervals typically ranges from 20 to 40 MPa (**Figure 44 and Figure 45**).




Figure 44. Average Strength for the Stone Roof 0 m to 17.5 m Interval




Figure 45. Average Strength for the Stone Floor 0 m to 17.5 m Interval

These values have been determined from the extensive database of sonic velocity logs recorded in the exploration boreholes in the Project area, which have been converted to strength using the Ensham site correlation, as follows (**Figure 9**):

$$UCS = 0.583e^{(0.00117*t)}$$

Where: UCS = Uniaxial Compressive Strength in MPa
t = Sonic Transit Time in m/sec

4.2.3.3 Compression Analysis

As part of the strata compression analysis, the strength values have been converted to a laboratory modulus value using the formula from the geotechnical testing of core samples at Ensham (GGPL, 2021²⁹):

$$\text{Laboratory Modulus (GPa)} = 0.325 * \text{Strength (MPa)}$$

The methodology of Hoek and Diederichs (2006³⁰) is then used to reduce the roof and floor laboratory modulus values (E_i) to rock mass values (E_{rm}), to consider the discontinuities in the rock mass.

$$E_{rm} = E_i * \{0.02 + (1-D/2) / (1 + \exp((60+15D-GSI)/11))\}$$

The laboratory modulus values are reduced using a Disturbance Factor (D) of 0 and representative Geological Strength Index (GSI) values for the roof and floor (**Figure 46**).




Figure 46. Determination of the Geological Strength Index (GSI)

²⁹ GGPL (2021). Geotechnical Reference Report for the Ensham Underground Mine. Report No. Ensham GRR - Rev C.

³⁰ Hoek, E. and Diederichs, M. (2006). Empirical Estimates of Rock Mass Modulus. International Journal of Rock Mechanics and Mining Sciences, 43, 203-215.

Based on the lithological and bedding characteristics shown in **Figure 47** and **Figure 48** for the Aries-Castor Seam and **Figure 49** and **Figure 50** for the Castor Seam, roof and floor GSI values of 55 and 50 respectively have been applied. The location of these four boreholes are shown on **Figure 9**.



Figure 47. Aries-Castor Seam Roof and Floor (Zone 2) – Borehole C4858




Figure 48. Aries-Castor Seam Roof and Floor (Zone 3) – Borehole C5384



Figure 49. Castor Seam Roof and Floor (Zone 2) - Borehole C4954



Figure 50. Castor Seam Roof and Floor (Zone 3) - Borehole C4986

The pillar compression is then calculated as follows using the methodology of Poulos and Davis (1974)³¹ for analysing rigid footings:

$$\text{Compression}_{\text{pillar}} = (\sigma_c * h)/E$$

Where: σ_c = Vertical stress change (MPa)
 h = Pillar height (m)
 E = Young's modulus of coal pillars (MPa)

³¹ Poulos, H.G. and Davis, E.H. (1974). Elastic Solutions for Soil and Rock Mechanics.

The compression of the roof and floor is calculated as follows:

$$\text{Compression}_{\text{roof or floor}} = I_P * (\sigma_c * w/2) / E$$

Where: σ_c = Vertical stress change (MPa)
 I_P = Influence Factor (for a rigid footing) = 1.4
 w = Pillar width (m)
 E = Young's modulus of roof or floor (MPa)

The change in vertical stress on the pillars can be estimated as:

$$\sigma_c = \text{Tributary Area Stress} - \text{Virgin Stress}$$

4.3 Prediction of Project Subsidence Effects

4.3.1 Subsidence in the Project Mining Area

The compression analysis has been carried out for the maximum depth of cover above each panel pillar and bell out pillar in the Project area, using the roof and floor strength values shown in **Figure 44** and **Figure 45**. The maximum seam thickness has also been applied. These assumptions provide the likely worst-case subsidence effects and therefore is a conservative scenario for the assessment of the impacts in the Project area.

The strength values selected for each panel in the Project area are tabulated in **Appendix 1**.

Where the maximum seam thickness is greater than the maximum allowable extraction thickness for a FoS of 1.6, the reduced thickness has been used in the compression analysis.

Based on this analysis, the predicted subsidence above the panel and sub panel pillars following secondary coal recovery in the Project area is typically less than 35 mm (**Figure 51** and **Figure 52**). This reduces to typically less than 20 mm above the bell out pillars, as they do not carry the full tributary area load on the perimeter of the panels (**Figure 53**). This level of subsidence is assessed to have negligible impact on soil composition and structure.

In relation to bord and pillar mining, guidance published by DAWE (2014) states:

“Where the pillars have been designed to be stable, the vertical subsidence is typically less than 20 mm. Natural or seasonal variations in the surface levels, due to the wetting and drying of soils, are approximately 20 mm; hence, vertical subsidence of less than 20 mm can be considered to be no more than the variations that occur from natural processes and should have negligible impact on surface infrastructure.”

This is consistent with Ensham's approach of developing long-term stable pillars that result in negligible subsidence. Whilst the Commonwealth guidance discusses seasonal variation of 20 mm having a negligible effect on surface infrastructure, the guidance also states that seasonal variation can be as high as 50 mm or more due to changes in moisture content (DAWE, 2014).




Figure 51. Subsidence above the Panel Pillars in the Project area




Figure 52. Subsidence above the Sub Panel Pillars in the Project area




Figure 53. Subsidence above the Bell Out Pillars in the Project area

4.3.1.1 Calibration of the Compression Analysis

The monitoring of six RTK-GPS survey stations over the current Ensham underground area since April 2021 has allowed the compression analysis, used to predict the subsidence in Zones 2 and 3, to be calibrated (See Section 3.1.1).

Two stations 502_2 and 114_2 show the most consistent monitoring results and have been chosen for this analysis (**Figure 17** and **Figure 18**). The results are summarised in **Table 1**.

Monitoring Station	Depth (m)	Solid Pillar Width (m)	Solid Pillar Length (m)	Roadway Width (m)	Extraction Height (m)	Actual Subsidence (mm)	Predicted Subsidence (mm)
502_2	195	20	24	6	4.3	6	27.8
114_2	140	17.5	21.5	6.5	3.2	8	25.1

Table 1. Calibration of Subsidence Data.

It is evident that at both stations the actual subsidence measured is less than the predicted subsidence using the compression analysis presented in this report (**Table 1**). As detailed in Section 4.2.3 of this report, there are number of input parameters required in the strata compression analysis. These include:

- Coal modulus.
- Conversion formulae to estimate strength and modulus.
- Roof and floor strata strength and modulus.
- Geological Strength Index (GSI) for the roof and floor strata
- Influence factor in the compression analysis.

For example, a small increase of 10 MPa in the strength of the roof and floor strata and an increase in the GSI values from 50-55 to 65, reduces the subsidence significantly from 25.1 mm to less than 12 mm.

This analysis of measured subsidence data in the Ensham mining area therefore provides greater confidence that the subsidence predictions are a conservative estimate of the anticipated subsidence in Zones 2 and 3.

4.3.2 Surface Cracking

As detailed in **Section 3.3**, a surface crack of 30 mm width developed above the rib line of 3 North Panel and across a public access path at the Tasman bord and pillar mine in NSW, only after the subsidence exceeded 300 mm. No surface cracking developed in areas where the subsidence was less than 300 mm.

Based on this observation from NSW, and GGPL's experience at comparable Queensland bord and pillar mines, surface cracking is not predicted above the Project area due to the predicted low levels of maximum surface subsidence of less than 35 mm.

4.3.3 Sub-surface Cracking

The nature of the proposed mining method in the Project area indicates that the surface subsidence will be due to elastic compression of the strata (**Section 4.2.3**). The mining activities do not create areas of caving, which could result in fracturing of the overburden.

This is confirmed by experience in NSW at Clarence Mine, which uses partial extraction bord and pillar methods at the north western edge of the Blue Mountains Heritage Area (**Section 3.2**). As detailed by Hill and White (2017), there have been no exceedances of the 100 mm subsidence limit and interaction with the overlying perched groundwater system since partial extraction started in 2003.

4.3.4 Limitations of the Subsidence Predictions

Based on the available data for the Project area, there are no localised features or variations in the geology, geotechnical conditions or surface topography that are considered likely to result in any significant deviations from the subsidence predictions presented in this report.

There is a high degree of confidence in the subsidence predictions due to the amount of information from the existing bord and pillar mining at Ensham with similar mining heights, depth of cover and mining methodology. This information has allowed a robust calibration to be achieved and provided a sound basis to enable conservative subsidence predictions.

5 CONCLUSIONS

The key conclusions from this report include:

1. Due to the nature of the bord and pillar mining method, low levels of subsidence, typically less than 35 mm, are predicted in the Project area as a result of elastic compression of the strata. Recent RTK-GPS monitoring at Ensham indicates subsidence levels of less than 10 mm above mined underground panels and confirms this prediction for the Project.
2. The magnitude of the predicted subsidence is less than the natural ground movements of up to 50 mm or more that can occur (DAWE, 2014 and 2015).
3. The subsidence assessment is based on the Project design Factor of Safety (FoS) and width: height ratios of the pillars, as well as the estimated critical level of overburden displacement. This assessment, using a minimum pillar FoS of 1.6 for areas beneath the floodplain, and 2.11 for access roadways beneath the Nogoa River to connect bord and pillar workings, and, for bord and pillar workings beneath the Nogoa River anabranh, has confirmed the long-term stability of the proposed mine layout.
4. The temporary increase in cover depth during 0.1% AEP (Q1000) flood events has been calculated below both the flood plain and Nogoa River and anabranh channels. Conservative maximum flood depth values of 16 m in the Nogoa River channel and 4 m across the flood plain have been used in the FoS calculations. The temporary increase in depth has been applied to the design figures to calculate the required mining height to satisfy the Project FoS during 0.1% AEP flood events.
5. The design criteria used to ensure long-term stability of the pillars has been peer reviewed by three industry recognised (RPEQ) geotechnical consultants Mine Advice (Dr Russell Frith), Byrnes Geotechnical (Dr Ross Seedsman), and BK Hebblewhite Consulting (Emeritus Professor Bruce Hebblewhite), who all concluded that the proposed bord and pillar layout is an appropriate and well developed geotechnical design.
6. As well as the factor of safety approach, the long-term life expectancy of pillars can be estimated using empirical studies from South Africa. Using this approach, the proposed 24 m x 28 m (centres) pillars in Zones 2 and 3 at 4.5 m high and 130 m depth of cover, are calculated to be stable for greater than 26,000 years.
7. After mining is completed and the workings flood with groundwater, the buoyancy effect of water will reduce the vertical load on the pillars by up to 40%. For a pillar below the Nogoa River anabranh designed with a FoS of 2.11, at 140 m depth of cover, reducing the vertical load on the pillar by a conservative

25%, to account for any potential strength loss in the coal and surrounding strata, increases the FoS to 2.82. This FoS has a probability of failure well in excess of 1 in 10,000,000.

8. The nature of the mining method generating only elastic compression of the strata indicates that sub-surface cracking above the Project area is not expected.
9. Due to the predicted low levels of subsidence and associated strains and tilts, no surface cracking is predicted above the Project area. This is consistent with operational experience in the current Ensham underground where surface cracking has not been observed above the bord and pillar mining areas and is supported by experience at other comparable bord and pillar mines in Queensland and NSW.
10. The expected low levels of subsidence are unlikely to result in the formation of significant depressions in the surface topography where ponding of the surface drainage may occur. This is also consistent with operational experience in NSW and Queensland where ponding has not been observed above previous similar bord and pillar mining areas.
11. Based on mining experience at shallow depths of cover in the current Ensham underground workings, as well as experience at other mining operations around the world, the risk of sinkhole subsidence occurring in the Project area, where the depth of cover is greater than 75 m, is considered to be negligible.

6 APPENDIX 1. PANEL DATA – ZONE 2 AND ZONE 3

Panel	Min Depth (m)	Max Depth (m)	Max Thick (m)	Average 0-17.5 m Roof Strength (MPa)	Average 0-17.5 m Floor Strength (MPa)	Strata Compression above 17.5 m x 21.5 m (Solid) Pillars (mm)	Strata Compression above 17.5 m x 17.5 m (Solid) Pillars (mm)	Strata Compression above 15 m x 15 m Bell Out (Solid) Pillars (mm)
ZONE 2 MINING AREA								
600 Mains	140	140	5.6	44	22	26.5	29.3	16.9
115	140	150	5.8	36	22	29.3	32.4	18.5
115A	130	140	6	40	18	30.5	33.8	19.3
116	130	140	5.8	38	24	26.1	28.8	16.6
117	130	130	5.8	38	22	25.7	28.6	16.5
117A	130	130	6	38	24	24.5	27.2	15.8
North Mains	130	130	5.8	36	24	24.9	27.6	16.0
605	150	150	5.6	40	26	26.0	28.7	16.5
606	140	140	5.6	44	22	27.1	30.4	13.4
700 Mains	150	200	5.2	44	32	28.5	31.4	17.9
702	140	150	5.4	32	28	26.7	29.5	17.0
704	130	160	5.2	42	30	25.0	27.6	15.9
705	150	150	5.2	40	32	23.4	25.8	14.9
706	130	190	5.2	42	36	26.1	28.7	16.5
707	140	200	2.4	36	38	26.4	29.6	16.4
707A	150	170	2.2	28	38	24.6	27.6	15.2
707B	150	150	2.2	26	38	22.4	25.1	13.9
707C	140	150	2.4	32	38	20.7	23.0	12.9
ZONE 3 MINING AREA								
SE7	80	120	4.6	42	26	20.5	23.0	12.9
SE8	90	130	4.4	38	24	23.6	26.5	14.8
SE9	90	130	4.4	36	24	24.0	26.8	15.0
SE10	80	140	4.2	36	24	25.6	28.7	16.0
SE10A	100	120	4.2	38	22	22.7	25.5	14.2
SE10B	90	100	4.2	38	26	17.2	19.3	10.8
SE10C	75	90	4.4	34	26	16.2	18.1	10.1
SW Mains	130	160	4.4	40	26	27.4	30.2	17.2

APPENDIX E

Subsidence Management Plan



Ensham
R E S O U R C E S

EIMP.06.00.06

SUBSIDENCE MANAGEMENT PLAN

ENVIRONMENTAL IMPACT MANAGEMENT
PLAN (EIMP)

APPROVAL

	Name	Position	Signature	Date
Document Owner	Dave Meyers	Manager HSECT		
SSE	Andy Mifflyn	GM Operations		
Revision	2			

Contents

1	Introduction	4
1.1	Scope	4
2	Ensham Mine Overview	6
2.1	Mining Activities	6
2.2	Topography and Drainage	6
2.3	Soils.....	6
2.4	Geology.....	11
2.5	Groundwater Regime	12
2.6	Land Use	12
3	Predicted Subsidence	14
3.1	Introduction.....	14
3.2	Pillar Design	14
3.3	Compression Analysis	15
3.4	Predicted Subsidence	16
3.5	Surface and Subsurface Cracking	16
3.6	Subsidence Impacts	17
4	Subsidence Monitoring.....	17
4.1	LIDAR Monitoring	17
4.2	Real Time Monitoring	20
4.3	Monitoring Surveys	22
4.4	Underground Surveying.....	26
4.5	Surface Inspections.....	26
4.6	Groundwater Monitoring	27
4.7	Monitoring Schedule and Trigger Levels	29
4.8	Subsidence Management Measures	29
4.9	Emergency Procedures.....	31
5	Legal Compliance and References	32
6	Terms and Abbreviations.....	32
6.1	Abbreviation and Description.....	32

7	Document Preparation	33
8	Review History	33
9	Roles and Responsibilities	33

Figures

Figure 1-1.	Existing Operations and Proposed Mining Plan For Zones 2 And 3	5
Figure 2-1.	Surface Topography and drainage.	7
Figure 2-2.	Soil Types (Desktop And Field Mapping).	8
Figure 2-3.	Conceptual Hydrogeological Model Cross Section (EIS Submission, 2021).	12
Figure 2-4.	Land Uses at Ensham Mine (2021)	13
Figure 3-1.	Maximum Mining Height for a FoS of 1.6.	15
Figure 4-1.	LIDAR transect across an area of unmined Vertosol soil.....	18
Figure 4-2.	LIDAR transect along an area of 502 panel with Vertosol soil mined during 2021	18
Figure 4-3.	LIDAR transect along an area of 114 panel mined during 2021	19
Figure 4-4.	Expanded LIDAR transect along an area of 114 panel mined during 2021.	20
Figure 4-5.	Fixed Monitoring Station.	21
Figure 4-6.	Location of Remote Subsidence Monitoring – Ensham Underground Area.	22
Figure 4-7.	Monitoring Data – 502_3 And 503_1 Stations.	23
Figure 4-8.	Monitoring Data – 502_1 And 502_2 Stations.	24
Figure 4-9.	Monitoring Data – 114 Panel Stations.....	25
Figure 4-10.	Groundwater Monitoring Bores.	28

Tables

Table 2-1.	Terrain Units and Soil Types.	9
Table 2-2.	Stratigraphy.	11
Table 4-1.	Monitoring Schedule.	29
Table 5-1.	References.	32
Table 6-1.	Terms.	32
Table 8-1.	Review History.	33

1 INTRODUCTION

Ensham Mine (EM) is an opencut / underground bord and pillar coal mine located approximately 35 km east of Emerald along the Nogoa River in Central Queensland. The mine is operated by Ensham Resources Pty Ltd (Ensham), a wholly owned subsidiary of Idemitsu Australia Resources Pty Ltd (Idemitsu), on behalf of the Ensham Mine joint venture (JV) partners. The JV partners, and holders of the Environmental Authority, are Bligh Coal Limited, Idemitsu Australia Pty Ltd, and Bowen Investment (Australia) Pty Ltd. EA EPML00732813 (the EA) is the relevant environmental authority under which Ensham operates the mine (DES, 2020).

Ensham currently undertakes underground mining using continuous miner operations, whilst utilizing the existing access and supporting infrastructure located within the current Mining Leases. The mine also produces coal from open cut pits using both dragline, and truck and shovel operations. Mining extracts a portion of the combined Aries/Castor seam plies, typically leaving the higher ash, uppermost plies in the roof of the underground roadways.

It is proposed to extend the life of the existing underground bord and pillar operation into areas north, south of existing operations, into existing granted mining leases i.e. Zones 2 and 3 (refer **Figure 1-1**):

1.1 SCOPE

This Plan addresses the monitoring and management of subsidence impacts from Ensham's approved bord and pillar underground mining operation and Zones 2 and 3. This includes the triggers for investigation of potential subsidence impacts, guidance on surface inspections, groundwater monitoring, mitigation and management measures are also included, as well as guidelines for landowner consultation if required.




FIGURE 1-1. EXISTING OPERATIONS AND PROPOSED MINING PLAN FOR ZONES 2 AND 3

2 ENSHAM MINE OVERVIEW

2.1 MINING ACTIVITIES

The Ensham underground mine has been operating since 2011. The mine will continue to produce around 4.5 million tonnes per annum (Mtpa) of thermal coal with the addition of Zones 2 and 3.

Coal from the underground mine is mined by five production units and transferred to the surface via the Ramp 3 drift conveyor.

2.2 TOPOGRAPHY AND DRAINAGE

The terrain in the Ensham area is generally low-lying, and the few hills within the area are capped by a hard layer formed on the surface known as duricrusts (**Figure 2-1**). The main drainage of the area is via the Nogoia River, which flows in an easterly and south-easterly direction through the Ensham mining leases before joining the Comet River to form the Mackenzie River near the town of Comet (**Figure 2-1**).

In the Ensham area, the elevation of the Nogoia River banks average 150 metres above Australian Height Datum. The Nogoia River is used for irrigation, drinking water and stock water supply, with flow maintained by releases from Fairbairn Dam, located south of Emerald. Due to the supply of water from the Fairbairn Dam to downstream users, the Nogoia River flows essentially all year round. The anabranch however is ephemeral and flows generally following a significant rain event.

The low-lying area includes floodplains and riparian zones along the Nogoia River and an anabranch, which runs to the north of the Nogoia River.

2.3 SOILS

The soils over the underground mine plan were mapped in 2006 and updated in 2021 for Zones 2 and 3 (refer **Figure 2-2** and described in more detail in **Table 2-1**). The different soil types react differently to climatic conditions, which may affect the level of subsidence and / or surface movement detected. The effect of soil type and underlying surface lithological units on subsidence is yet to be assessed. With the soil types now mapped (refer **Figure 2-2**) and the characteristics of the underlying surface lithologies determined by closely spaced exploration drilling, the effect of soil type/underlying lithologies on subsidence can be assessed now that monitoring and collection of subsidence data is underway. Additional RTK GPS monitors will be added to the Zones 2 and 3 area so the relationship between subsidence levels and soil type/underlying lithologies can be further evaluated. More recently, field mapping in Zones 2 and 3 was carried out in November 2021 (**Figure 2-2**) and correlated with previous mapping.




FIGURE 2-1. SURFACE TOPOGRAPHY AND DRAINAGE.




FIGURE 2-2. SOIL TYPES (PREVIOUS AND PRESENT MAPPING).

TABLE 2-1. TERRAIN UNITS AND SOIL TYPES.

	Formation / Lithology	No.	Description - (Surface Form and Slope Range)	Group No.	Major Soil Group	Soil Type	Soil Description	Australian Soil Classification Order	Soil Description
Qa	Quaternary Alluvium; River and Floodplain Deposits - clay, silt, sand, gravel	0	Channel floors, low flood terraces and banks of major streams and rivers; overall stream gradient <1%, bank slopes variable 25% to locally sub-vertical	1	Shallow Rocky Soils associated with rock outcrop or exposed rock with skeletal gravelly sandy or loamy soils	1	Shallow uniform mainly coarse to medium-textured very rocky soils; rock outcrop is common	Leptic Rudosols	Shallow soils with generally little, if any, pedologic organization and the upper 0.5 m is underlain with hard materials
Cz	Cainozoic Soil Cover including Older Alluvial and Colluvial Deposits - soil, sand, siliceous and ferruginous gravel and reworked laterite	1	Depressional and shallowly incised drainageways, Intermediate stream terraces, floodplain and drainage flats, frequently flood prone and subject to surface water ponding following wet periods; slopes mostly <1 %	2	Gravelly Sand, Loams or Clays, medium to deep uniform or weakly gradational soils dominated by gravel content throughout much of the middle to upper parts of the solum.	2.2	Thin sandy to loamy surface soils grading through gravelly loam- loamy gravel subsoils underlain by dense gravelly colluvium and/or HWR	Regolithic Chernic Tenosols	Thin soils with generally only weak pedologic organization apart from the A horizon. With a melacic or melanic horizon, no conspicuously bleached A2 horizon and overlying other unconsolidated mineral materials.
Ta	Tertiary Emerald Formation - lateritised sediments, laterite, claystone, siltstone, sandstone, and pebbly sandstone.	2	Near flat to gently undulating alluvial plain, gently inclined outwash slopes, valley flats and intermediate and higher river terraces and back plains; slopes mostly <2%			2.3	Stony or thin silt to clay loam surface soils with lenses of gravelly clay or clayey gravels underlain by strongly acidic clay subsoils or HWR below 0.5-1.0 m	Acidic Brown Clastic-Leptic Rudosols	Acidic shallow soils with generally little, if any, pedologic organization consisting dominantly of gravelly unconsolidated mineral materials and the upper 0.5 m is underlain with hard materials
P-T	Permo-Triassic Rewan Formation - mudstone and interbeds of lithic sandstone	3	Undulating plains with broad low rises, gently inclined broadly rounded dissection slope interfluvies and near level to gently sloping crestal areas on mesas and eroded plateau remnants; slopes mostly 2-3% locally up to 5%	3	Gradational Red and Yellow Earth Soils.	3.2	Sandy loam to loamy surface soils grading to red, reddish brown or yellowish brown apedal massive sandy clay or light, or medium to heavy clay subsoils	Acidic Mesotrophic Red Kandosols	Acidic red soils without a strong texture contrast. Massive or only weak structured B horizons, not calcareous throughout and mesotrophic in the major part of B2 horizon
P	Permian Undifferentiated Blackwater Group, comprising the Rangal Coal Measures, Burngrove Formation and Fairhill Formation - carbonaceous mudstone, thinly interbedded mudstone and fine sandstone, siliceous siltstone, calcareous and feldspathic sandstone	4	Moderately strongly undulating lands with irregular low rounded rises and moderately inclined dissection slope interfluvies and shallowly incised erosion gullies with local low jump-ups adjacent to flatter benched surfaces; slopes variable up to about 12% in the steeper parts	4	Texture Contrast (Duplex) Soils	4.1	Shallow to med. deep often stony thin loamy surface duplex soils with dark brown, brown or reddish brown medium to heavy clay subsoils over HWR	Subnatric Brown Sodosols	Brown soils with a strong texture contrast, sodic B horizon (ESP between 6 and <15) and are not strongly acid

		5	Undulating to rolling rises, gently to moderately inclined broadly rounded dissection slope interfluvies and footslopes; slopes mostly in the range 6-15%			4.2	Mostly deep, thin silty to loamy surface duplex soils with brown or reddish brown neutral to strongly alkaline med. to heavy clay subsoils	Eutrophic Mesonatric Brown Sodosols	Brown soils with a strong texture contrast, sodic B horizon (ESP between 15 and 25) and are not strongly acid. Major part of the B2t horizon is eutrophic and not calcareous
		6	Irregular low hills and rises and low hilly lands, with moderately steep dissection slope interfluvies; slopes mostly up to 25%, locally steeper areas occur.	5	Uniform (or weakly gradational) Fine- textured (Non-cracking) Clay Soils	5.1	Shallow to med. deep, stony surface, brown, yellowish brown or reddish brown uniform or weakly gradational medium to heavy and heavy clay soils over HWR	Sodic Pedaric Brown Dermosols	Brown Soils with a structured B2 horizon and lacking a strong texture contrast. The upper part of the B2 horizon has a strong blocky or polyhedral structure with average ped-size between 5-20 mm with weak adhesion. At a minimum the lower part of the B2 horizon is sodic
		7	Hilly lands with steep irregular planar hill slopes mostly within the range 25- 35%			5.2	Mainly deep uniform or weakly gradational brown or yellowish brown medium to heavy alkaline clay soils with surface stone and some stony lenses included	Sodic Pedaric Brown Dermosols	Brown Soils with a structured B2 horizon and lacking a strong texture contrast. The upper part of the B2 horizon has a strong blocky or polyhedral structure with average ped-size between 5-20 mm with weak adhesion. At a minimum the lower part of the B2 horizon is sodic
		8	Steep escarpment slopes, 25-50 m high, with steep irregular planar and locally benched slopes typically in the range 35 – 60% to locally sub-vertical.			5.3	Deep uniform or weakly gradational brownish black, dark grey-brown or dark brown strongly structured alkaline clay soils of medium to high or high plasticity; (incipient cracking clay)	Sodic Pedaric Brown Dermosols	Brown Soils with a structured B2 horizon and lacking a strong texture contrast. The upper part of the B2 horizon has a strong blocky or polyhedral structure with average ped-size between 5-20 mm with weak adhesion. At a minimum the lower part of the B2 horizon is sodic
				6	Uniform (Cracking) Clay Soils	6.2	Mainly deep brownish black, dark grey-brown, dark brown or brown, uniform strongly structured heavy alkaline clay soils, locally with gilgai development designated	Endohypersodic, Epipedal Black, Grey or Brown Vertosols	Black, grey or brown clay soils with shrink-swell properties that exhibit strong cracking when dry and at depth have slickensides and/or lenticular peds. These soils have pedal A horizon that is either not or only weakly self-mulching, no surface crusty horizon and some horizon within the upper 0.5 m has an ESP of >15

Example: Terrain Unit ([Qa1/6.2-5.3](#)) Geological Regime [Qa](#), Landform [1](#), Soil Type [6.2-5.3](#)

2.4 GEOLOGY

Ensham mine is located in the western part of the Bowen Basin, which is one of five major foreland sedimentary basins formed along the eastern side of Australia during the Permian period. The Bowen Basin is the largest productive coal basin in Australia and stretches from Townsville, to south of the Queensland-New South Wales border in a north to south direction.

Table 2-2 provides a summary of the stratigraphic sequence in the Ensham area. This comprises unconsolidated Quaternary aged sediments, unconformably overlying consolidated Tertiary and Permian sediments.

TABLE 2-2. STRATIGRAPHY.

Age	Unit	Maximum thickness ¹ (m)	Description
Quaternary	-	25	Alluvium - silt, clay, sand and gravel
Tertiary	-	ND	Duricrusted palaeosols at the top of deep weathering profiles, including ferricrete and silcrete; duricrusted old land surfaces
	Emerald Formation	50	Fluviatile and lacustrine claystone and siltstone, quartzose sandstone, pebbly sandstone, gravel, lignite, oil shale, interbedded basalt; all deeply weathered in outcrop
	Basalt	ND	Tertiary volcanics (basalt) mapped as being present over 10 km west of the site
Triassic	Rewan Group	200	Lithic sandstone, pebbly lithic sandstone, green to reddish brown mudstone and minor volcanolithic pebble conglomerate (at base); deposited in a fluvial-lacustrine environment.
Permian	Rangal Coal Measures	125	Feldspathic and lithic sandstone, carbonaceous mudstone, siltstone, tuff and coal seams. Coal seams include the Aries, Castor, Pollux and Orion seams. The main economic seams at Ensham are the Aries 2 and Castor seams.
	Burngrove Formation	200	Sandstones, siltstones and mudstones, and banded coal seams frequently interbedded with tuff and tuffaceous mudstones - coal seams include the Virgo and Leo seams.
	Fair Hill Formation	150	Lithic and feldspathic labile sandstone, siltstone, mudstone and conglomerate
	Macmillan Formation	100	Lithic and feldspathic sublabile mudstone, siltstone and sandstone

¹ Approximate maximum thickness based on available exploration holes and/or relevant literature
 ND: not defined, not enough data available

The Permian and Triassic strata form regular layered fluvio-deltaic sedimentary sequences, while the Quaternary sediments are more complex and irregular. The coal seams mined at Ensham Mine are found within the Rangal Coal Measures, which is the uppermost Permian unit of the portion of the Bowen Basin.

The Rewan Group aquitard overlies the Rangal Coal Measures and separates the Nogoa River and associated floodplain alluvium from the underground workings. Each are discussed in more detail in (**Table 2-2**).

The underground mine surface geology is dominated by the Nogoa River alluvium, with the Tertiary sediments mapped to the south and the north.

2.5 GROUNDWATER REGIME

The principal groundwater bearing formations in the Ensham area are associated with the Permian coal seams. The Triassic Rewan Group siltstones and sandstones are considered a regional scale aquitard. A conceptual hydrogeological model is shown in **Figure 2-3**.

Alluvial deposits are associated with the Nogoa River and its anabranch (**Figure 2-3**). The Quaternary aged alluvium comprises shallow sequences of clay, silty sand and sand, underlain by discontinuous basal sands and gravel. A comprehensive network of bores listed in the EA is located in the alluvium to monitor any impact of mining on the alluvial aquifers.




FIGURE 2-3. CONCEPTUAL HYDROGEOLOGICAL MODEL CROSS SECTION (EIS SUBMISSION, 2021).

2.6 LAND USE

Ensham mine is located within a rural setting, typical of the Central Queensland region, within the rural margins between a range of central township nodes. The largest nearby townships include Emerald, which is located approximately 35 km south-west, and Blackwater which is located 49 km south-east. The small township of Comet is located approximately 18 km south-east of the mine site.

The predominant land uses within the wider region include cropping, grazing and resource activities (**Figure 2-4**). The existing land uses include resource activities, cropping, grazing land and waterways with fringing riparian vegetation.

As part of Cultural Heritage Management Plans with the traditional owners' groups over Ensham, two preservation areas above underground workings have been set up where significant amounts of

artefact material is stored (refer **Figure 2-4**). Both areas have been mined under, are fenced and are subject to periodic inspection.




FIGURE 2-4. LAND USES AT ENSHAM MINE (2021)

3 PREDICTED SUBSIDENCE

3.1 INTRODUCTION

The bord and pillar mining layout at Ensham has been specifically designed to ensure that there will be no caving of the roof or collapse of the pillars. The long-term stability of the underground workings has been assessed using the design Factor of Safety (FoS), pillar dimensions (width to height ratio) and stability of the overburden.

Unlike longwall mining, where the subsidence comprises two main components namely sag subsidence and strata compression, in the Ensham mining area, the subsidence will be due to strata compression alone. This results in low levels of surface lowering and minimal associated surface effects due to the associated low tilts, curvatures and strains.

The underground workings are designed where practical to avoid geological structures that may be associated with poorer mining conditions. Seismic surveying is used in future mining areas to delineate these structures prior to mining, allowing the optimization of the underground workings. For every panel that is mined, a hazard panel plan is produced that collates the available geological information such as:

- Location of geological structures.
- Depth of cover.
- Seam thickness.
- Seam levels.
- Roof strength.

Furthermore, the maximum excavation heights to maintain the required minimum FoS, in both the roadways and bell outs, are detailed on the Permit to Mine (PTM) for each mining area. The final roadway and pillar profiles are surveyed to confirm compliance with the design excavation heights. These checks are carried out by the Geotechnical Engineer and reported in the monthly geotechnical inspection report.

3.2 PILLAR DESIGN

The stability of the coal pillars in the Ensham underground mine are assessed using the industry accepted University of New South Wales Pillar Design Procedure to determine the design FoS as follows (Galvin et al, 1998):

$$\text{FoS} = \text{Strength of Pillar} / \text{Load on Pillar}$$

The strength and load carried by the pillars in the Ensham Area are calculated using the UNSW Pillar Design Power Strength Formulae and tributary area loading methodology respectively.

A minimum design FoS of 1.6 has been applied to ensure the long-term stability of the underground workings below the flood plain (**Figure 3-1**). Where pillars are located below the flood plain, a conservative temporary flood depth of 4 m equating to an effective increase in depth of cover of 2.1 m should be applied to the load calculations in **Figure 3-1**.




FIGURE 3-1. MAXIMUM MINING HEIGHT FOR A FOS OF 1.6.

The long term stability of the pillars (in excess of 200 years) has been confirmed by three separate industry recognized geotechnical consultants who have peer reviewed the subsidence assessment for the extension mining area. Below the Nogoia River channel and anabranh, a FoS of 2.11 will be adopted for mining, equating to a probability of pillar failure of 1 in 1 million. Similarly, a conservative temporary flood depth of 16 m in the channel and anabranh equates to an effective 7.5 m increase in the depth of cover and will be taken into account when undertaking pillar design.

The barrier pillars between panels and sub-panels are also designed to ensure FoS values greater than 2.11, equating to a probability of failure of 1 in 1 million.

3.3 COMPRESSION ANALYSIS

The deformation induced at the surface by bord and pillar mining due to strata compression can be estimated analytically by calculating the combined pillar, roof and floor compression using modulus values as follows.

The pillar compression is then calculated as follows using the methodology of Poulos and Davis (1974) for analysing rigid footings:

$$\text{Compression}_{\text{pillar}} = (\sigma_c * h)/E$$

Where:

σ_c = Vertical stress change (MPa)

h = Pillar height (m)

E = Young's modulus of coal pillars (MPa)

The compression of the roof and floor is calculated as follows:

$$\text{Compression}_{\text{roof or floor}} = I_p * (\sigma_c * w/2)/E$$

Where:

σ_c = Vertical stress change (MPa)

I_p = Influence Factor (for a rigid footing) = 1.4

w = Pillar width (m)

E = Young's modulus of roof or floor (MPa)

The change in vertical stress on the pillars can be estimated as:

$$\sigma_c = \text{Tributary Area Stress} - \text{Virgin Stress}$$

3.4 PREDICTED SUBSIDENCE

LIDAR has been used to determine the existence of any subsidence over previously mined areas, with no trends or evidence being observed. Subsidence predictions for future mining areas indicate levels less than 35 mm, which is less than the accuracy of LIDAR and less than natural ground movement of up to 50 mm (IESC, 2015).

In 2021, more accurate RTK (Real Time Kinematic)-GPS monitoring above mined out bord and pillar panels at Ensham has confirmed the low levels of surface subsidence as discussed in Section 4.2. It is considered that the lower accuracy (± 50 mm) LIDAR surveys will still be applicable in assessing the possibility of pillar collapses or squeezes that may have occurred in previously mined out areas.

3.5 SURFACE AND SUBSURFACE CRACKING

No surface or sub-surface cracking has been observed in the Ensham underground mined area since underground bord and pillar mining began in 2011.

3.6 SUBSIDENCE IMPACTS

Underground mining at Ensham considers potential impacts to the following aspects:

- Groundwater.
- Surface water - Nogoa and Anabranh and other creeks and flood plain.
- Flora and fauna.
- Surface infrastructure (mining).
- Agricultural infrastructure including laser levelled irrigation paddocks.
- Cultural Heritage.

The expected low levels of subsidence are unlikely to result in the formation of significant depressions in the surface topography where ponding of the surface drainage may occur. Furthermore, based on mining experience at shallow depths of cover in the current Ensham underground workings, as well as experience at other mining operations around the world, the risk of sinkhole subsidence occurring in Zones 2 and 3, where the depth of cover is greater than 75 m, is considered to be without known precedent.

4 SUBSIDENCE MONITORING

Subsidence monitoring at Ensham comprises:

- LIDAR (+/- 50 mm accuracy).
- Real Time Kinematic (RTK)-GPS monitoring (+/- 5 mm accuracy).
- General surface inspections if monitoring indicates exceedance of one or more subsidence trigger levels.
- Groundwater monitoring to determine whether Environmental Authority (EA) trigger levels have been exceeded.

Prior to mining in Zones 2 and 3, baseline assessments have been carried out. As part of these assessments, the surface has been mapped to produce terrain models.

4.1 LIDAR MONITORING

LIDAR data was collected over the underground mine initially in 2009, then on an annual basis since 2016 including areas where bord and pillar has been or will be carried out. No discernible surface movement due to subsidence has been able to be detected to date.

Example profiles have been produced for each different soil type to define the amount of surface movement that can be expected naturally from climatic conditions and discussed as follows.

4.1.1 Cracking Clay Soil (Vertosol)

Much of the underground mining is located below this soil type (**Figure 2-2**). The transect below is located between the main channel and the anabranh of the Nogoa River and has never been subject to mining activities but has been covered by the 2010/2011 flood and periodic vegetation control and burning (**Figure 4-1**). There is no discernible pattern over time and is a reflection of the climatic

conditions at the time of the survey. Similar, patterns have been measured in the same soil type over the 502 Panel which was mined during 2021 (**Figure 4-2**). Considerable surface soil movement is expected over time in this soil type.




FIGURE 4-1. LIDAR TRANSECT ACROSS AN AREA OF UNMINED VERTOSOL SOIL




FIGURE 4-2. LIDAR TRANSECT ALONG AN AREA OF 502 PANEL WITH VERTOSOL SOIL MINED DURING 2021

From the data provided by LIDAR monitoring, the surface soil movement from climatic conditions and farm management activities can range from 200 – 400 mm over time.

4.1.2 Rudosol, Sodosol and Dermosol Soil Types

These soil types are typically gravelly sand, loams or clays, duplex or non-cracking clay soils. Panel 114 is located under a mixture of these soil types in which the principal natural movement appears to be soil movement down the slopes and deposition on the flatter areas (**Figure 4-1**).




FIGURE 4-3. LIDAR TRANSECT ALONG AN AREA OF 114 PANEL MINED DURING 2021




FIGURE 4-4. EXPANDED LIDAR TRANSECT ALONG AN AREA OF 114 PANEL MINED DURING 2021.

From the data provided by LIDAR monitoring, the surface soil movement from climatic conditions and erosion / deposition can range from 200 – 500 mm. This soil type mainly occurs in areas of steeper terrain used for cattle grazing. It was mined under during 2021.

4.2 REAL TIME MONITORING

Based on LIDAR monitoring to date and more recently, fixed monitoring RTK (Real Time Kinematic) GPS stations, any ground movements resulting from bord and pillar mining are shown to be less than natural ground movement. Mitigation measures have therefore not been necessary to date for bord and pillar mined areas.

Fixed monitor GPS stations have been installed in 2021 and provide a much higher level of accuracy of +/- 5 mm (Figure 4-5) than LIDAR. These stations are installed 1.5-2 m into the ground surface to be able to better determine ground movement and minimise the impact of surface soil movement.



FIGURE 4-5. FIXED MONITORING STATION.

Ensham has now installed six of these remote GPS monitoring stations above 114, 500 Mains, 502 and 503 Panels in the current underground area, as shown in Figure 4-6. Five of the six monitoring stations started recording data in mid-April 2021. By early February 2022, development mining (primary workings) had been completed under station 502_1 and secondary workings had also been completed under stations 114_1, 114_2 and 502_2. This monitoring has been set up by GNSS Monitoring and the data can be easily accessed remotely in real time.

An additional nine RTK GPS monitoring stations will be established (in real time i.e. continuous monitoring) to monitor subsidence levels in Zones 2 and 3.

- Three monitors located north of the Nogoia River in Zone 2
- Three monitors located south of the Nogoia River in Zone 2
- Three monitors located in Zone 3.

One of the monitors (in each set of 3) will be used as a control (i.e. no mining) at each location.

The stations will be established prior to mining to obtain reference data for comparison with post-mining subsidence data.



FIGURE 4-6. LOCATION OF REMOTE SUBSIDENCE MONITORING – ENSHAM UNDERGROUND AREA.

Vertosol soil type which is a heavy clay soil, occurs on the surface above the 500 Series Panels. A number of different soil types occur on the surface above 114 Panel.

4.3 MONITORING SURVEYS

4.3.1 500 Series Stations

In the 500 Series Panel area, no mining has been carried out below stations 502_3 and 503_1 (**Figure 4-7**). The 14 day moving average curve indicates any vertical movement is less than the survey error of ± 5 mm (**Figure 4-7**). Also of note, the rainfall events since April 2021 do not appear to have affected the survey measurements of vertical movement in this area (**Figure 4-7**).




FIGURE 4-7. MONITORING DATA – 502_3 AND 503_1 STATIONS.

Development (primary workings) was carried out in the 500 Mains below station 502_1 in late May 2021. This mining appears to have been associated with approximately 5 mm of movement that occurred over a timeframe of a month (**Figure 4-8**). This timing is as anticipated based on the approximate 2 to 3 weeks required to mine the entire width of the panel below the survey station.




FIGURE 4-8. MONITORING DATA – 502_1 AND 502_2 STATIONS.

The reserve recovery in the 500 Mains below station 502_1 is 38.5%, at 195 m depth of cover. The FoS of the 500 Mains pillars for a 3.5 m mining height in this area is 1.90, equivalent to a probability of failure of 1 in 90,000.

502 Panel developed under station 502_2 in late August 2021, extracting coal to around 3.3 m high. Similar subsidence behavior to 502_1 was noted on the 502_2 station (**Figure 4-8**). Secondary workings of an additional 1 m of floor coal was completed under this station by late September 2021, with no additional vertical movement measured (**Figure 4-8**). Similarly, rainfall events do not appear to be significantly affecting the vertical movement measurements in this area.

4.3.2 114 Panel Stations

Mining of development roadways (primary workings) at 3.3 m high was carried out below survey stations 114_1 and 114_2 in mid-August and mid-September 2021 respectively (**Figure 4-9**).




FIGURE 4-9. MONITORING DATA – 114 PANEL STATIONS.

Prior to mining under station 114_1, a greater amount of scatter in the data was evident (**Figure 4-9**). This station also appears more susceptible to changes during rainfall events, which can be attributed to the type of material in which the station is anchored. The data from station 114_2 appears more reliable and indicates around a two week period for the maximum 8 mm of subsidence to occur (**Figure 4-9**).

4.3.3 Summary

By February 2022, almost ten months of higher accuracy (± 5 mm) monitoring survey data has been collected over the Ensham underground workings. This data indicates that underground mining has been associated with surface movements less than 10 mm, which is within the accuracy of the survey monitoring and validates subsidence predictions.

It is anticipated that prior to mining in Zones 2 and 3, more data of the natural surface movement will allow interpretation to determine any subsidence movement component. This data will be reviewed in conjunction with rainfall records and also the location of underground mining, to provide some guidance on the proportion of movement due to both mining induced subsidence and also the seasonal variation in ground levels due to changes in moisture content.

Nine monitoring stations will be installed in Zones 2 and 3. Three of the stations will be used as a control and will be located within an area which will not be subject to mining as discussed in Section 4.2.

It is considered that LIDAR surveys will still be applicable in assessing ground movements over larger areas above trigger levels.

This monitoring (LIDAR and RTK) should confirm the subsidence predictions and any significant changes in subsidence will trigger a review of the relevant impact assessments and associated mitigation and management measures as discussed further in **Section 4.8**.

This review will also provide additional calibration data for any future subsidence predictions and assessments of subsidence effects.

A subsidence monitoring report will also be produced every two years and monitoring of subsidence impacts will be continued for 5 years after the completion of mining.

4.4 UNDERGROUND SURVEYING

As well as the surface monitoring, underground surveying of the completed mined roadways and pillar dimensions is carried out. The FoS and width: height ratio of the as-mined pillars can be calculated and checked against the design values.

These values can be referenced when reviewing the subsidence predictions.

4.5 SURFACE INSPECTIONS

Detailed surface inspections will be carried out on areas that have been identified through Lidar or fixed GPS monitoring as having triggered an investigation as discussed in **Section 4.7**.

Any underground crossings under the Nogoia river within Zone 2 will be subject to an annual inspection of the bed and banks adjacent to the crossing to identify any visible subsidence as a result of mining operations that may impede on fish passage.

4.6 GROUNDWATER MONITORING

Ensham Mine's existing groundwater monitoring bore network is extensive and allows for the compilation of groundwater data from the Quaternary (alluvium), Triassic age sediments, Rewan Group, and Rangal Coal Measures (**Figure 4-10**). The existing groundwater monitoring plan for the current Ensham includes baseline, operations and post closure.

Ensham Mine proposes to maintain the current monitoring network and frequency with new monitoring bores to be added as proposed by the Groundwater Management and Monitoring Program defined in EA Condition C47. The location of existing monitoring bores along with the trigger levels in the EA are sufficient to require an investigation to be undertaken.




FIGURE 4-10. GROUNDWATER MONITORING BORES.

4.7 MONITORING SCHEDULE AND TRIGGER LEVELS

The monitoring schedule for the various aspects detailed in this SMP are summarized in **Table 4-1**. This schedule also includes the frequency and responsible department. Trigger levels have also been specified to initiate a review.

TABLE 4-1. MONITORING SCHEDULE.

Monitoring/Survey	Who by	How often	Trigger Levels
LIDAR	Technical Services/Survey	Annual	>100mm movement when LIDAR surfaces are compared on an annual basis
Fixed GPS	Technical Services/Survey	Real Time	35 mm
Surface Surveying	Technical Services/Survey	As per land compensation agreements	As per land compensation agreements
Underground Surveying	Survey	Daily	As per Strata Control Management Plan
Surface Inspections	Environmental	Annual or if investigation is triggered	Water ponding, new gully erosion or changes to Nogoia River bed and banks (that may indicate an impact to fish passage) not attributed to natural processes at locations where underground mining has occurred Surface inspections will be confirmed using Lidar
Groundwater Monitoring	Environmental	Quarterly	Refer Schedule C of EA conditions for groundwater quality and water level triggers

4.7.1 Subsidence Trigger Levels

Based upon the accuracy of LIDAR (+/-50mm) and the natural soil variation of 50mm (IESC, 2015), a LIDAR trigger level of 100mm lower than previous annual surface is considered a realistic value for cracking clay soils and other soils located on slopes to investigate.

Similarly, a 35 mm variation in the more accurate fixed pole RTK-GPS ground monitoring is considered a valid trigger level based on the initial monitoring over 114, 500 Mains and 502 Panels (**Figure 4-7 to**

Figure 4-9), which is based on the magnitude of the predicted subsidence as per the Subsidence Report for the Ensham Life of Mine Extension – Zones 2 and 3, February 2022).

4.8 SUBSIDENCE MANAGEMENT MEASURES

Due to the low-level subsidence effects measured and observed as a result of bord and pillar mining at Ensham, remedial management measures are presently not required unless a significant deviation in the level of subsidence identified from future monitoring. The subsidence monitoring results detailed in **Section 4.3**, confirm the surface movements due to mining of less than 10 mm. This level of movement requires no remediation in view of the natural soil variation, which may exceed 50 mm (IESC, 2015).

Any significant detection of subsidence (ie where the level of subsidence exceeds the trigger levels) will trigger a review of underground mining activities as detailed in **Section 4.7**. Depending on the land use and risk involved in the activity, different mitigation measures may be required:

- Grazing – rip to eliminate risk to stock
- Dry land cropping – plough out if effecting crop yield
- Irrigated cropping – re-level to ensure continued drainage.

Where surface levels indicate a difference in elevation greater than the trigger levels in **Table 4-1** and likely as a result of mining activities, an investigation will be undertaken by Ensham. Where the investigation supports that the elevation change is associated with mining, then a detailed investigation will be completed by a suitably qualified person and, where warranted, an investigation report will be prepared and submitted to the Administering Authority and to the land owner/land occupier. The investigation will nominate the necessary rehabilitation (which may include monitoring and management of soil erosion) to be undertaken if necessary. Land will be rehabilitated in accordance with the approved PRCP and the current Environmental Authority.

Furthermore, in regards to long-term stability, after mining is completed and the workings flood with groundwater, the buoyancy effect of the groundwater will reduce the vertical load on the pillars by up to 40%. For a pillar below the Nogoia River anabranch, designed with a FoS of 2.11, at 140 m depth of cover, reducing the vertical load on the pillar by a conservative 25%, to account for any potential strength loss in the coal and surrounding strata, increases the FoS to 2.82. This FoS has a probability of failure in excess of 1 in 10,000,000. As well as the factor of safety approach, the long-term life expectancy of pillars can be estimated using empirical studies from South Africa. Using this methodology, the pillars are calculated to be stable well in excess of 200 years.

If subsidence monitoring identifies a potential impact to fish passage within the Nogoia River as a result of mining activities, then rehabilitation and restoration works would be undertaken. The trigger levels based on monitoring, surveying and inspection are detailed in **Table 4-1**. These trigger levels would be reviewed annually (or following an investigation) to ensure that there are no impacts to fish passage in the Nogoia river. Furthermore, the stability of the underground workings is checked by

regular inspections. In the current underground workings, the thickness of floor coal is controlled during the mining process by spray painting the rib side to ensure the mined thickness does not exceed the amount specified on the sequence plan and Permit to Mine document (**Figure 4-11**).

Furthermore, as detailed in Section 3.1, underground surveying of the completed mined roadways, bell outs and pillars is carried out. The FoS and width: height ratio of the as-mined pillars can be calculated and checked against the design values. These checks are carried out by the Geotechnical Engineer and reported in the monthly geotechnical inspection report. Experience to date has shown that there have been no exceedances of the planned mining heights in the secondary workings panels at Ensham.



FIGURE 4-11 PAINT MARKS TO CONTROL THE THICKNESS OF FLOOR COAL MINED.

No underground mining is proposed beneath the Nogoa River main channel within Zone 2, with mining only to occur to construct roadways to connect the bord and pillar mining areas (**Figure 1-1**). Surface inspections for impacts from subsidence on the Nogoa River will be completed at each location where an underground crossing is constructed. Some underground mining is planned for approximately 200 m under the Nogoa River anabranch in Zone 2, however this channel only holds water at times of flooding and therefore provides limited fish passage compared to the Nogoa River main channel.

4.9 EMERGENCY PROCEDURES

A principal hazard management plan, PHMP (UG PHMP.09.17.01 Precautions Against Inrush Principal Hazard Management Plan) defines the requirements for the effective control of the risks associated with Inrush and the principal hazard of inundation due to water, gas, or material that flows, in the underground workings of Ensham Coal Mine. It applies to all aspects, activities and personnel associated with underground coal mining at Ensham Resources Pty Ltd. The objective is to identify areas where Inrush or inundation could occur and to prevent such occurrences. It also provides for

the requirements of the Coal Mining Safety and Health Regulation 2017 (CMSHR) Sections 292, 293, 294, 295. The management plan is underpinned by Risk Assessment (RA.BT014 Inrush into underground workings) and Trigger Action Response Plan, TARP (UG TARP.09.17.01-01 Potential for Inrush Underground TARP).

5 LEGAL COMPLIANCE AND REFERENCES

TABLE 5-1. REFERENCES.

Legislation / Recognized Standards	<ul style="list-style-type: none"> Environmental Authority EPML00732813 Environmental Protection Biodiversity Conservation Act 1999. Water Act 2000
Reports	Independent Expert Steering Committee (IESC), 2015. Monitoring and Management of Subsidence Induced by Longwall Coal Mining Activity. Report to the Department of the Environment.

6 TERMS AND ABBREVIATIONS

6.1 ABBREVIATION AND DESCRIPTION

TABLE 6-1. TERMS.

Abbreviation	Description
EA	Environmental Authority
EPBC Act	<i>Environment Protection and Biodiversity Protection Act 1999</i> (Commonwealth).
GM	General Manager
GPS	Global Positioning System
HSE	Health, Safety and Environment
LIDAR	Light Detection And Ranging
PHMP	Principal Hazard Management Plan
RTK	Real Time Kinematic
SSE	Site Senior Executive
TARP	Trigger Action Response Plan

7 DOCUMENT PREPARATION

This SMP has been prepared by Gordon Geotechniques Pty Ltd (GGPL), in conjunction with Ensham technical and environmental personnel, and peer reviewed by Mine Advice Pty Ltd. The SMP has been based on the Subsidence Report prepared by Gordon Geotechniques in January 2022, and has been peer reviewed by Mine Advice in January 2022.

8 REVIEW HISTORY

This Subsidence Monitoring Plan will be subject to review annually or under the following conditions due to:

- Change to licence conditions and/or reporting requirements.
- Significant change to current mine plan/operations.
- An investigation report recommendation.

TABLE 8-1. REVIEW HISTORY.

Date of review	Revision Number	Trigger for review	New revision Number
8/2/2022	1	Requirement of EIS assessment report and EA Amendment – Zones 2 and 3 subsidence technical report	2

9 ROLES AND RESPONSIBILITIES

Survey Section

- Carry out monitoring – fixed monitor and LIDAR.
- Prepare monitoring data.
- Ensure compliance of the dimensions of the underground pillars and roadways.

Environmental Section

- Surface inspections.
- Monitor creeks/rivers/groundwater.
- Liaise with landowners.

Technical Services Section

- Underground inspections.
- Plan subsidence monitoring requirements.
- Prepare subsidence monitoring report
- Review and reconcile subsidence monitoring data.
- Facilitate review if trigger levels are exceeded.

- Liaise with landowners.

APPENDIX F

Subsidence Report – Peer Review Letter

15th February 2022

Garry Gough
Ensham Resources

Garry,

**SUBJECT: Peer Review Outcomes – GGPL Mine Layout and Surface Subsidence Assessment
Report, Ensham Life of Mine Extension, Zones 2 and 3**

This report contains the findings of an independent peer review of a Gordon Geotechniques Pty Ltd (GGPL) technical report entitled “*Subsidence Report for the Ensham Life of Mine Extension – Zones 2 and 3*”, (the report) dated February 2022, which has been prepared for Ensham Resources Pty Ltd (Ensham). It is confirmed that the author has been provided with a final copy of the report in question and has had various communications and discussions with the author, Nick Gordon, on matters of clarification as part of carrying out this peer review.

The basic tenet of the report relates to the design of remnant mine workings in two proposed future mining areas, Zones 2 and 3, that are part of the extension of the current Ensham mining area, the proposed mining method being as per that currently in use at the mine (i.e. bord and pillar development, followed by both secondary floor coaling where seam thickness allows, and/or bell-outs around the periphery of production panels).

Whilst the report does not specifically describe the nature of overlying land use other than the presence of the Nogoia River and Anabranh, it is self-evident that the associated mine layout design objectives are two-fold, namely:

- (i) that coal pillars left in place post-mining are consistent with being long-term stable thereby reliably preventing a pillar and overburden collapse, and
- (ii) that the likely surface settlements due to the proposed mining with coal pillars remaining long-term stable are within tolerable, albeit currently undefined, levels.

It is confirmed that the report comprehensively addresses both issues, as is now summarised.

1. Long-Term Remnant Coal Pillar Stability

The pillar stability assessment as contained in the report considers three key mine stability parameters, namely pillar Factor of Safety (FoS), pillar width to height ratio (w/h) and the settlement of the overburden in respect of whether it is likely to be unstable and so load remnant coal pillars under full-tributary area loading, or not. This is judged to be a comprehensive assessment and design approach whereby the stabilising contribution of both the coal pillars and the overburden are fully recognised and given due consideration.

The use of pillar FoS (as determined using the UNSW Pillar Design Procedure or UNSW PDP under the assumption of full tributary area loading to surface (FTA Loading)) in combination with pillar w/h ratio (as outlined in **Hill 2005**) has been the mainstay of the pillar design at Ensham to-date and there is no obvious

imperative as to why this needs to be changed for the Life of Mine Extension area. However, given potential surface constraints as previously described, it is judged to be prudent that GGPL have brought in an overburden settlement stability criterion to supplement the **Hill 2005** approach, the resultant displacement-based overburden FoS being a measure of the extent by which the assumed pillar loading condition of FTA Loading will eventuate in reality (see **Section 2**). As stated by GGPL, the assumption of FTA Loading is a “conservative” pillar loading assumption, the overburden displacement FoS providing an indication as to the level of the associated conservatism which can then be considered alongside the pillar FoS when evaluating overall system stability for the overburden and coal pillars in combination.




FIGURE 1. Factor of Safety vs Width:Height Ratio for Zones 2 and 3, Ensham LoM Extension Area

Figure 1, reproduced from the GGPL report, contains the range of pillar FoS and w/h ratio design outcomes within Zones 2 and 3 of the Life of Mine (LoM) Extension Area. As is clear from **Figure 1**, the proposed remnant pillar designs have no precedent in terms of a pillar collapse based on the **Hill 2005** combined pillar stability criteria of FoS and w/h. This design outcome is assessed to be a minimum requirement and needs to be supplemented with other relevant considerations in order to gain a more comprehensive understanding of the actual robustness of the proposed designs in terms of ensuring long-term stability of the remnant mine workings.

The report also includes an analysis of the stability of the floor strata below coal pillars and the extent to which it might be prone to a bearing-capacity type failure under the applied vertical loads through the remnant pillars. The analysis outcomes lead to the conclusion that such a failure scenario is in the “*practically impossible*” qualitative risk-likelihood category hence it is eliminated as a credible mechanism by which either pillar stability or surface settlements due to mining could be adversely affected post-mining.

The report also includes a first-ever assessment of the potential time-frame that can be assigned to the term long-term pillar stability. Based on the analyses undertaken the report concludes that a time-period in excess of 200 years can be credibly assigned, the author confirming his agreement with the method of analysis and critically, the conclusion arrived at in the context of what can reasonably be inferred from the method of analysis that has been selected.

2. Surface Settlements Due to Mining

As was outlined in detail in **Reed et al 2017**, the overburden needs to displace or settle a certain amount before it becomes critically unstable to surface such that FTA Loading of coal pillars applies in reality. If the overburden does not reach this critical level, it can be reliably inferred that it retains a level of self-supporting ability which adds significantly to the overall stability of the remnant mine workings, over and above that inferred from the pillars in isolation. In recognition of this, the GGPL report addresses two key issues:

- (i) the presence or absence of near-seam thick, puggy low stiffness/highly compressible clay materials that would significantly influence the magnitudes of surface settlement due to mining (all other factors being equal), and
- (ii) an estimate of surface settlement magnitudes due to the proposed mining, this being based on estimating the vertical compression of the coal pillars, roof strata and floor strata in combination.

It is self-evident that the presence of near-seam thick, puggy claystone material as described in (i) would add to any surface settlements calculated in (ii), thereby decreasing the overall stability of the overburden (all other factors being equal). This is why it is imperative to determine whether such material is likely to be present or not, the finding in the GGPL report being that it is generally absent at Ensham. This is a positive attribute in terms of post-mining stability of the remnant mine workings.

The report utilises a standard analytical method for estimating coal, roof, and floor strata compressions due to mining, the combination of which provides for the pre-mining prediction of surface settlements due to mining. Having reviewed the method of analysis, the manner by which the required values of Young's Modulus and E have been determined and recognising that rock stiffness increases as a direct function of confinement, it is assessed that the predicted surface settlement values can be considered as credible worst-case scenarios.

Maximum surface settlements are calculated to be 35 mm or less. The measured overburden and surface subsidence displacement data sets contained in both **Frith and Reed 2017** and **2019**, indicate that the onset of overburden instability to surface occurs at surface settlements of no less than 150 mm between barrier pillars, this being taken to be the critical level of overburden settlement whereby FTA Loading of the overburden to surface might start to develop. Comparing this value to the predicted maximum surface settlements due to mining of < 35 mm, returns an overburden stability FoS in excess of 4 (i.e. 150/35), which incorporates a significant error margin in terms of the overburden becoming critically unstable above the remnant mine workings.

It is noted that Ensham have introduced a surface subsidence monitoring system (fixed RTK-GPS system) that aims to minimise the influence of reactive surface soils on subsidence measurements which have previously resulted in accuracies of no better than ± 20 mm being applied to such measurements. This level of measurement uncertainty is problematic when attempting to correlate and verify pre-mining predictions with actual values post-mining. That Ensham have invested in this technology and demonstrated measurement accuracies of ± 5 mm assists greatly in having the highest level of confidence that pre-mining predictions of surface subsidence will not be exceeded in practice.

In terms of the potential for large-magnitude surface movements that would inevitably manifest if a chimney or sinkhole failure were to propagate up from the mine workings and reach the surface, the report contains a detailed assessment of sinkhole potential. The conclusion from the analyses is endorsed by the author,

namely that it is not a credible subsidence mechanism within the Zone 2 and 3 areas, primarily by virtue of the cover depths involved and that unsupported spans within the mine workings are limited to those of headings, intersections and bell-outs.

3. Summary

Based on the geotechnical characterisation and design analyses contained in the GGPL report, the author concurs with the conclusions arrived at, noting that a combination of pillar FoS > 1.6 under FTA Loading, pillar w/h values > 3.5 and overburden stability FoS between barriers of > 4, are fully consistent with the design requirement for long-term stable remnant mine workings. The predicted maximum surface settlement of 35 mm associated with the retention of long-term stable pillars is agreed with and is considered to represent the credible worst-case outcome in this regard.

As a final point of note, the GGPL report has considered and addressed the time-dependent pillar spalling model of **Canbulat 2010**, concluding that given the absence of swelling clays within the intended coal seam working sections, it has no obvious application at Ensham. This is fully endorsed by the author, in addition to the general concern, as outlined in **Frith and Reed 2019**, that the Canbulat model is flawed in its fundamental premise, namely that the failed pillar cases on which it is based collapsed due to time-dependent pillar spalling, rather than simply being inadvertently and unknowingly under-designed in the initial instance.

It is confirmed that in the professional opinion of the author, the GGPL report is fit for purpose in terms of being used as an input into any subsequent short, medium and long-term subsidence impact assessments that may be undertaken in relation to Zones 2 and 3 within the LoM Extension area at Ensham.

Please contact the under-signed if you require anything further in these matters.

Yours sincerely,



Russell Frith
Senior Principal Geotechnical Engineer
FAusIMM CP(Geotech) RPEQ # 12952

REFERENCES

Canbulat, I. (2010). **Life of Coal Pillars and Design Considerations**. Proc. 2nd Ground Control Conference, Sydney, pp 57-66.

Frith, R. Reed, G. (2017). **Coal Pillar Design When Considered a Reinforcement Problem Rather Than a Suspension Problem**. International Journal of Mining Science and Technology <https://doi.org/10.1016/j.ijmst.2017.11.013>

Frith, R. Reed, G. (2019). **The Limitations and Potential Design Risks When Applying Empirically-Derived Coal Pillar Strength Equations to Real-Life Mine Stability Problems**. International Journal of Mining Science and Technology 29 (2019) 17–25.

Hill, D. (2005). **Coal Pillar Design Criteria for Surface Protection**. Proceedings of the Coal Operators' Conference. Brisbane, Queensland: University of Wollongong.

Reed, G. McTyer, K., Frith, R. (2017). **An Assessment of Coal Pillar System Stability Criteria Based on a Mechanistic Evaluation of the Interaction Between Coal Pillars and the Overburden**. International Journal of Mining Science and Technology 27 (2017) 9–15.

APPENDIX G

Subsidence Management Plan – Peer Review Letter

7th March 2022

Garry Gough
Ensham Resources

Garry,

SUBJECT: Peer Review Outcomes – Subsidence Management Plan, Zones 2 and 3, Ensham Life of Mine Extension

This short report contains the summary outcomes of an independent peer review of the Ensham Resources Subsidence Management Plan (SMP), document reference EIMP.06.00.06, which was prepared in association with Gordon Geotechniques Pty Ltd as the appointed Geotechnical Engineer at Ensham Mine and includes the two proposed mining areas known as Zones 2 and 3. It is confirmed that the author has been provided with a final copy of the SMP document in question as part of carrying out this peer review.

It is noted at the outset that the mine design and associated surface subsidence predictions that will need to be managed during mining operations by the SMP have their origin in **GGPL 2022**, which has already been formally peer-reviewed by Mine Advice, as confirmed in **Mine Advice 2022**.

It is confirmed that in the professional opinion of the author, the supplied SMP is fit for purpose on the basis of the following summary points:

- (i) the described method of mining, layout design approach and subsidence prediction methodology are fully consistent with that contained in **GGPL 2022**.
- (ii) the proposed measurement and assessment of both the as-formed mine workings and consequent surface settlements due to mining are entirely consistent with ensuring that actual settlements are within the upper bound predictions contained in **GGPL 2022**, thereby ensuring that actual Factors of Safety against both excessive settlements and/or pillar collapse are consistent with those determined from pre-mining layout design and subsidence analyses.
- (iii) in particular, the planned use of the fixed RTK-GPS surface level monitoring system with a demonstrated accuracy of ± 5 mm, is regarded as best-practice for reliably tracking very low level surface settlements due to bord and pillar mining that leaves stable remnant pillars in place, and provides for the highest possible level of confidence that post-mining stability of the remnant workings is equal to if not better than those determined from the pre-mining layout design process.
- (iv) it is considered that the combination of measurements and surface and underground observations as well as their respective frequencies, are fully consistent with the rate that new mine workings will be formed-up and their actual stability will need to be evaluated and confirmed via the SMP.

In summary, I concur with the intent and contents of the SMP for Zones 2 and 3 including its comprehensive link to the layout design and surface subsidence settlement predictions as contained in **GGPL 2022**.

Please contact the under-signed if you require anything further in this matter.

Yours sincerely,

A handwritten signature in black ink, consisting of a stylized 'R' followed by a stylized 'A'.

Russell Frith
Senior Principal Geotechnical Engineer
FAusIMM CP(Geotech) RPEQ # 12952

REFERENCES

GGPL (2022). **Subsidence Report for the Ensham Life Of Mine Extension – Zones 2 and 3.** Commercial consulting report to Ensham Resources, February 2022.

Mine Advice (2022). **Peer Review Outcomes – GGPL Mine Layout and Surface Subsidence Assessment Report, Ensham Life of Mine Extension, Zones 2 and 3.** Commercial consulting report to Ensham Resources, 15th February 2022.